

RECEIVED
22 JUL 2011

A D U S
BUILDING CONTRACTORS AND
DECORATORS

9th June 2011

X 9 Sheffield Stands (powder coated black or galvanised finish) under fix.

Installation – excavate ground surface 1.30 x 5m (proposed area) lay membrane (impermeable sheets), Type 1 MOT compacted to 100mm., install timber surround) and timber beams, screw Sheffield stands into the timber beams and finish with shingle flooring.

Roof and 2x side frames to be of plastic black corrugated sheets. Please refer to picture attached.

Installation of Sheffield stands at the front of the building:
Sheffield stands to be bolted into the concrete.

Materials £950 + £800 = £1750

Labour £720 + £720 = £1520

Total £2,270

Bin area

4x Scaffold poles to be bolted into the ground (concrete) and roof to be constructed of plastic black corrugated sheet.

Materials - £600

Labour - £680

Total - £1280

Grand Total - £3,350

175 PRAYLE GROVE LONDON NW2 1BD

PHONE: 07799323441

RECEIVED
22 JUL 2011



PHOTO 1

Palmer House Bike Store;

The 2x side panels and the roof to be of black plastic corrugated sheets. The back will be up against the existing wall. Please refer to drawing no 110 SK001B