

Lighting Load Schedule I King's Cross Southern Facade Canopy South East Stair Enclosure
ENG-BRF-OAP-SSQ-CBSE-004

SF Document Ref : 3011_04_002 rev02

Date : 27/07/11

1 of 2

[illegible]

Lighting Load Schedule I King's Cross Southern Facade Canopy South East Stair Enclosure
ENG-BRF-OAP-SSQ-CBSE-004

SF Document Ref : 3011_04_002 rev02

Date : 27/07/11

2 of 2

Luminaire ref	Channel ref	Description	QTY	Lamp Type	Circuit Load	Control type	Total Load (W)
---------------	-------------	-------------	-----	-----------	--------------	--------------	----------------

Southern Façade Canopy

L11	55	IP65 linear LED luminaire complete with diffuser and integral gear.	54	LED	40	Switched timeclock/photocell	2160
-----	----	---------------------------------------------------------------------	----	-----	----	---------------------------------	------

South East Stair Enclosure

L12	56	IP65 linear LED luminaire complete with diffuser and integral gear.	24	LED	40	Switched timeclock/photocell	960
-----	----	---------------------------------------------------------------------	----	-----	----	---------------------------------	-----

*Note: For Luminaire information see specification schedule

Total lighting load (W) 3120

Lamp Ref	Description
LED	LED

Refer to Studio Fractal documentation when reading this schedule

Additional Cost Notes.

1. Contractor to confirm wattages with manufacturers prior to order
2. Contractor / Electrical engineers to confirm dimming / control gear protocol