GENERAL NOTES:

1. ALL DIMENSIONS AND LEVELS SHALL BE CHECKED ON SITE PRIOR TO CONSTRUCTION WORK COMMENCING.
2. ALL LANDSCAPE DRAWINGS TO BE READ IN CONJUNCTION WITH ALL RELEVANT ENGINEER'S AND ARCHITECT'S DRAWINGS AND SPECIFICATIONS.
3. ALL DRAWINGS TO BE READ IN CONJUNCTION WITH THE LANDSCAPE SPECIFICATION.
4. ANY DISCREPANCY CONCERNING THE DRAWINGS SHOULD BE REFERRED TO THE LA IMMEDIATELY.
5. ALL DIMENSIONS IN MILLIMETRES UNLESS NOTED OTHERWISE
6. ALL LEVELS IN METRES.
7. DO NOT SCALE OFF THIS DRAWING.
8. EXISTING SERVICE ALIGNMENTS SHALL BE CHECKED ON SITE BY THE CONTRACTOR PRIOR TO CONSTRUCTION WORK COMMENCING.

PRELIMINARY PLANTING SCHEDULE

TYPE	KEY	SPECIES	SIZE	NOTES	Quantity
Existing Trees Retained		Refer to Tree Retention & Removal Drawing (bd 0055 DD 005)		Tree Protection fencing in accordance with BS5837:2005	
Specimen Semi-Mature Tree Planting to Playground		Ginkgo biloba GINBIL	30-35cm girth 5 - 10m ht 2.5m clear stem	Pit/pit system underground guyed with 6m? semi-mature tree planting medium (ref 5)	3
Semi-Mature Trees to Access Lane		Betula utilis Jacquemontii BET.UTI	20-25cm girth 4 - 5m ht 2.0m clear stem	Pit/pit system underground guyed with 6m? semi-mature tree planting medium (ref 5)	2
Specimen Multi-Stem Trees to Secret Garden		Amelanchier lamarckii AME.LAM	Multi-stem Bushes at 1m apart girth 18-20 5-5.5m ht 2.0m clear stem	Pit/pit system underground guyed with 6m? semi-mature tree planting medium (ref 5)	2
Advanced Nursery Stock Trees to Cover Space		Betula utilis Jacquemontii 'Multi Stem' BET.UTI ms Prunus subhirtella 'Autumnalis' PRU.SUB	18-20cm girth 5.5-6.5m ht 2.0m clear stem	Pit/pit system underground guyed with 6m? semi-mature tree planting medium (ref 5)	2 4
Shrubs, Herbaceous & Groundcover Planting		Bergenia cordifolia BER.COR Calamagrostis acutiflora 'Karl Foerster' CAL.ACU Potentilla fruticosa 'Tangerine' POT.FRU Rudbeckia fulgida 'Goldsturm' RUD.FUL Lavandula angustifolia 'Hidcote' LAV.ANG & ROS.OFI Heuchera 'Midnight Rose' HEU.MID Lavandula angustifolia 'Hidcote' LAV.MID Persicaria amplexicaulis PER.ATR Hosta 'Halcyon' HOS.PLA Dicentra eximia DIC.EXI	45-60cm 6/9L.m 45-60cm 4/9L.m 30-40cm 4/9L.m 45-60cm 6/9L.m 45-60cm 4/9L.m 45-60cm 4/9L.m 45-60cm 4/9L.m 60-80cm 4/9L.m 45-60cm 12/9L.m 20-25cm Bare Root 60 shoots	3L pot - Bushy for Groundcover 3L pot Bushy min 3 stems 3 shoots 3L pot, fully rooted with healthy crown 3L pot - 30/40 incl planting at 3L pot 3L pot Good champ root developed 3L pot 3L pot 3L pot	10 17 8 30 84 7 15 20 20 4
Hedge Planting		Carpinus betulus CAR.BET Sarcococca hookeriana var. digyna SAR.HOO	80-100cm 2/9L.m 20-30cm 6/9L.m	3L pot size. Maintained to height of 1.5m 3L pot size	153 80
Climbers		Lonicera periclymenum 'Belgica' LON.PER Jasminum officinale JAS.OFI Wisteria sinensis 'Alba' WIS.SIN Parthenocissus tricuspidata 'Veitchii' PAR.TRI	90-150cm height As shown	5L pot size upon major trellis. Supplied with installed support frames	5 5 6 15
Grass seed		Playturf plastic protected matting 50% amenity grass seed, low maintenance mix BS 4428 to specular	25.35g/m² /sq.m		15
		Grass seed mix 2: Cornflower Wildflower seed planting. BSH Wildlife or similar with prep planting TBC	2.5 g/m² /sq.m		240
		Grass seed mix 3: Woodland Wildflower seed planting. BSH Wildlife or similar with prep planting TBC	3.5 g/m² /sq.m		115
* Undergrowth to Secret Garden		Alium, Tulip, Geranium, Narcissus, Bulbocodium, Bulb planting	TOPSIZE 5/5L.m	Underplanting to groundcover & perennial areas as indicated with*	

Rev	Date	Description	Drawn	Ch'd
01	14/10/2010	Employers Requirements Issue	LB	RB
00	17/09/2010	Stage E Issue for comment	LB	RB

b:d landscape:architecture urban:design

bd landscape architects ltd
Tum Street
Tewkesbury
GLOS GL20 5NX
T: 01684 295 775
e: info@bdlandarch.com
w: www.bdlandarch.com

CLIENT
London Diocesan Board for Schools, London Borough of Camden & Emmanuel C of E Primary School

PROJECT
Emmanuel C of E School
Mill Lane

TITLE
Soft Landscape Layout Plan

Status:	Drawn:	Checked:
Stage E	LB	RB
Scale: 1:100 @ A0	Date: 16.09.2010	Approved: RB

Drawing & Revision Number:
bd 0055 DD 003 R01