
Scaffold poles Protective fencing to comprise of vertical and horizontal framework of scaffolding, well braced to resist impacts and to support Heras temporary fencing panels Soft Ground Option Scaffold poles driven into ground to NOTE: Where necessary to ensure secure fixings and stable fence line back braces are to be incorporated. Hard Ground Option Heras fencing to be fixed into proprietary footings (concrete or rubber). Approx. 3000mm Centres to accommodate Heras fencing panels (or similar approved) and to provide

Common Causes of Tree Death



Please use copies of this as an on-site poster for personnel

(Source: Arboricultural Information Exchange 2005)

PENERAL MOTEC.

- ENSIONS AND LEVELS SHALL BE CHECKED ON SITE PRIOR TO
- ALL LANDSCAPE DRAWINGS TO BE READ IN CONJUNCTION WITH ALL RELEVANT ENGINEER'S AND ARCHITECT'S DRAWINGS AND SPECIFICATION
- ALL DRAWINGS TO BE READ IN CONJUNCTION WITH THE LANDSCAPE
- 4. ANY DISCREPANCY CONCERNING THE DRAWINGS SHOULD BE REFERE
- ALL DIMENSIONS IN MILLIMETRES UNLESS NOTED OTHERW
- ALL LEVELS IN METRES. DO NOT SCALE OFF THIS DRAWING.
- DO NOT SCALE OFF THIS DRAWING.
 EXISTING SERVICE ALIGNMENTS SHALL BE CHECKED ON SITE B

ADDITIONAL NOTES:

Arboricultural Survey

The information shown on this drawing should be read in conjunction with the Arboricultural Survey carried out by Crown Consultants dated 11th September 2009; document ref 0879.

Tree Protection Zones - Protective Fencing

All trees, shrubs and hedgerows on site to be retained within or adjacent to the extent of the site shall be protected during the course of works in the following manner and in accordance with BS 5837: 2005 Trees in Relation to Construction.

Workmansh

All workmanship is to be in accordance with good practice and shall conform to 85 3998: 1989 Recommendations for Tree Works and 85 5837: 2005 Trees in Relation to Construction and the Landscape Specification. The standard of workmanship must be to the best possible standard by highly experienced operatives. All tree works to be carried out by a certified Arboriculturalist to the Project Managers approval.

Works within Tree Protection Zon

Any works within the TPA to be undertaken in accordance with BS 5837 : 2005 and approved contractor method statements.

Fencing Locat

Refer to Drawing bd 0055 DD 005 for proposed location of protective fencing. Alignment of fencing to be agreed with Landscape Architect/Tree Officer on site prior to exerction.

 o1
 2g/to/2010
 Employers Requirements issue
 LB

 o0
 o6/og/2010
 Stage E Issue for comment
 RB

 Rev
 Date
 Description
 Drawn G

D ° C

Sun Street Tewkesbury GLOS GLao 5NX t: 07515 155 775 e: info@bdlandarch.c

> NT London Diocesan Board for Schools, London Borougl of Camden & Emmanuel C of E Primary School

Emmanuel C of E School

Tree Protection Detail

bd 0055 DD 301 R01