



DO NOT SCALE FROM THIS DRAWING

Note:- Metal trusses and associated timber purlins carefully taken down for cleaning and repair; Metal girders cleaned and repaired in place (All in accordance with Richard Griffiths specialist report). Metal trusses reinstalled to existing locations and timber purlins replaced with cold rolled steel sections in existing purlin locations with 2 no. new purlins located at ridge and eaves all to S.E. detail and spec. -Flashing material and repair works to Midland Goods Shed and regeneration house shown for clarification; not part of contract 3. -All dimensions to be checked on site -Lead flashings to have protective coating as necessary to prevent direct contact with other adverse materials. -Lead flashings around recessed arches and copings to be lapped in accordance with standard LDA details to provide continuous water proofing. -Bird Deterrent not provided as part of this contract.

K	MW	19	MW	Purlin removed. Rooflight note amended.
J	MN	08	MW	Drawing status changed, glazing to typical plan re-aligned, notes altered. PV's amended.
H	MW	08	MW	ROOF LIGHT NOTE AMENDED. DRAWING STATUS AMENDED.
rev	by	date	van can	chkd amendments

key plan

BAM Design Ltd
An operating company of BAM Construct UK Ltd
Centrium Business Park
Griffiths Way, St Albans
Herts, AL1 2RD
Tel (01727) 894200
E-mail design@bam.co.uk

Architecture
Structural Engineering
Environmental Services
Interior Design
Feasibility Studies
3D Visualisation

project

ARGENT ESTATES Ltd
EGY - KINGS CROSS CENTRAL
3753 3

title

**WEST HANDYSIDE CANOPY
TYPICAL DETAILS OF WHC ABUTTING
MGS**

drawing status				
CONSTRUCTION				
contract no.	LN0217	scale	As indicated	@ A1
client ref.	ARGENT	date	20/10/08	
drawn by	MW	checked by	JC	
drawing no	3753	ARCH	H1404	K