

Gripple (maxi) tensioner  
2no. per tree and  
125x25mm timber frame  
to protect rootball.

Arboresin porous bound stone  
surfacing laid in accordance  
with Greenleaf instructions.

Root Rain Precinct  
installed around the  
guyed rootball.  
Ensure inlet is flush  
with surround level.

Galvanised Greenleaf support  
frame to fit top of  
Root Director RD1400 Modular  
(1400x1700x450)  
Root Management System.

`Dead Man` anchors, kerb  
stones or similar.  
4mm guy wire looped  
twice around minimum.  
Use 4 anchor points per tree.

Loosen and shape base as  
shown to aid root penetration  
and pit drainage.

