

MN	
1	<u>General Notes:</u>
	1. Drawings are not to be scaled (images have been scanned).
	<ol> <li>For typical Connection Details refer to Drg No, 18000/S_1145.</li> </ol>
	<ol> <li>Connection design forces shown thus : (kN), acting downwards. All forces are factored. Where such connection forces are only shown at one end of the beam it should be</li> </ol>
	<ul> <li>assumed the force is the same at both ends.</li> <li>4. Concrete grade to insitu beams and stabs (not on steel decking) to be RC40, refer to Arup concrete specification details.</li> </ul>
	<ul> <li>Nominal cover to all reinforcement to be 30mm, to BS8500.</li> <li>5. Concrete grade to insitu slabs on permanent metal decking to be RC30, refer to Arup concrete specification for details.</li> </ul>
	Nominal Cover to be 30mm.
	<ol> <li>For Temporary Works proposals refer to Drg No, 111800/ S_1147 &amp; S_1743.</li> </ol>
	<ol> <li>Concrete upstand to all levels at front of lift to be provided. Refer to Drg No, 118000/S_1146 Detail 'F'.</li> </ol>
	8. Locations of Existing W.I. Beams to be confirmed to Engineer prior to demolition.
	<ol> <li>Any descrepancies between Architect's &amp; Engineer's Drawings to be highlighted to both parties.</li> </ol>
	10. All general dimensional information & setting out to be
R Holestive Demie	refered to Architect's Drawings. 11. Lifting beams & secondary lift steelwork to be Contractor
E SLIEZE DETRIL (4)	designed.
	<ol> <li>Proposed method statement &amp; construction sequence to be agreed with Engineer.</li> </ol>
3 - 3 Sul 	
	C3 19/05/09 AS JB BJ
	Issued For Construction           C2         18/06/07         JL         JB         BJ
	Issued For Construction C1 05/03/07 JL JB BJ
	Issued for construction
	Issue Date By Chkd Appd
	ARUP
	13 Fitzroy Street London W1T 4BQ
	Tel +44 (0)20 7636 1531 Fax +44 (0)20 7580 3924 www.arup.com
	Client Manhattan Lofts
	Corporation Limited
	Job Title
	St. Pancras Chambers
	Drawing Title
	Platform Level Glazed Screen Bases
	Sheet 2
	Scale at A1
	Plot ID EEB97014-DB7D-4F74-A161-2F891AD57A53
	Drawing Status Construction
	Job No Drawing No Issue
	118000 S 4013 C3