

Landmark Trees

ARBORICULTURAL IMPACT ASSESSMENT REPORT:

56 Belsize Avenue,
London NW3 4AA

REPORT PREPARED FOR:

Mr & Mrs Stirling,
56 Belsize Avenue,
London NW3 4AA

REPORT PREPARED BY

Adam Hollis
MSc ARB MICFor FArbor A MRICS C Env

Ref: STR/BLZ/AIA/01

Date: 7th July 2010

The content and format of this Report are for the exclusive use of the Client. It may not be sold, lent, hired out or divulged to any third party, not directly involved in the subject matter without Landmark Trees written consent.

Web: www.landmarktrees.co.uk
e-mail: info@landmarktrees.co.uk
Tel: 0207 851 4544

London Office: 20 Broadwick Street, W1F 8HT, London

Registered Office: Grange Cottage, All Cannings, Devizes, Wiltshire, SN10 3NR

Landmark Trees is the trading name of Landmark trees Ltd. Registered in Wales. Reg No. 3882076



| Section | Content | Page N° |
|----------------|-----------------------------|----------------|
| 1.0 | SUMMARY | 5 |
| 2.0 | INTRODUCTION | 6 |
| 2.1 | Terms of Reference | 6 |
| 2.2 | Drawings Supplied | 6 |
| 2.3 | Scope of Survey | 7 |
| 2.4 | Survey Data | 7 |
| 3.0 | OBSERVATIONS | 8 |
| 3.1 | Site Descriptions | 8 |
| 3.2 | Subject Trees | 9 |
| 3.3 | Planning Status | 19 |
| 4.0 | DEVELOPMENT CONSTRAINTS | 10 |
| 4.1 | Primary Constraints | 10 |
| 4.2 | Secondary Constraints | 12 |
| 5.0 | ARBORICULTURAL IMPACTS | 13 |
| 6.0 | DISCUSSION | 14 |
| 6.1 | Rating of Primary Impacts | 14 |
| 6.2 | Rating of Secondary Impacts | 14 |
| 6.3 | Mitigation of Impacts | 14 |
| 7.0 | CONCLUSION | 15 |
| 8.0 | RECOMMENDATIONS | 15 |
| 9.0 | REFERENCES | 19 |

APPENDICES

| | | |
|------------|-----------------------------|----|
| APPENDIX 1 | Survey Data | 20 |
| APPENDIX 2 | Recommended Tree Works | 22 |
| APPENDIX 3 | Trees for Constricted Sites | 24 |
| APPENDIX 4 | Tree Constraints Plan | 25 |
| APPENDIX 5 | Impact Assessment Plan | 27 |

Caveats

This report is primarily an arboricultural report. Whilst comments relating to matters involving built structures or soil data may appear, any opinion thus expressed should be viewed as qualified, and confirmation from an appropriately qualified professional sought. Such points are usually clearly identified within the body of the report.

It is not a full safety survey or subsidence risk assessment survey. These services can be provided but a further fee would be payable. Where matters of tree condition with a safety implication are noted during an inspection they will of course appear in the report.

Inherent in tree inspection is assessment of the risk associated with trees close to people and their property. Most human activities involve a degree of risk, such risks being commonly accepted if the associated benefits are perceived to be commensurate.

Risks associated with trees tend to increase with the age of the trees concerned, but so do many of the benefits. It will be appreciated, and deemed to be accepted by the client, that the formulation of recommendations for all management of trees will be guided by the cost-benefit analysis (in terms of amenity), of tree work that would remove all risk of tree related damage.

Prior to the commencement of any tree works, an ecological assessment of specific trees may be required to ascertain whether protected species (e.g. bats, badgers and invertebrates etc) may be affected.

Tree Constraints & Protection Overview

| | | | |
|---|---|---|----------------------------|
| Client: | Mr & Mrs Stirling, | Case Ref: | STR/BLZ/ AIA/01 |
| Local Authority: | LB Camden | Date: | 25/7/10 |
| Site Address: 56 Belsize Avenue, London NW3 4AA | | | |
| Proposal: front garden basement extension | | | |
| Report Checklist | Y/N | | Y/N |
| Arboricultural constraints on site | Y | Trees removed | Y |
| Tree Survey | Y | Topographical Survey | Y |
| BS5837 Report | Y | Conservation Area | Y |
| Tree Preservation Orders | N | | |
| Tree Protection Plan: | N/a | (include In future method statement) | |
| Tree Constraints Plan: | Y | | |
| Arboricultural Impact Assessment: | Y | | |
| Site Layout | | | |
| Site Visit | Y | Date: 14/05/10 | Access Full/Partial/None F |
| Trees on Site | Y | Off site Trees | Y |
| Trees affected by development | Y | O/s trees affected by development | N |
| Tree replacement proposed | Y | On or off-site trees indirectly affected by development | N |
| Trees with the potential to be affected | | | |
| Front garden: T4 / mature ash tree removed to facilitate development. | | | |
| Rear garden: Unaffected. | | | |
| Comments | | | |
| Slightly sprawling ash does not add greatly to rhythm and line of avenue planting. Replacement planting within verge proposed to complement avenue planting. | | | |
| Recommendations | | | |
| 1 | Proposal will mean the loss of trees (TPO/CA) | | Y |
| 2 | Proposal has sufficient amelioration for tree loss | | Y |
| 3 | Proposals provide adequate tree protection measures | | Y |
| 4 | Proposal will mean retained trees are too close to buildings | | N |
| 5 | Specialist demolition / construction techniques required | | N |
| 6 | The Proposal will result in significant root damage to retained trees | | N |
| 7 | Further investigation of tree condition recommended | | Y |

RPA= Root Protection Area

TPP= Tree Protection Plan

AMS= Arboricultural Method Statement

AIA = Arboricultural Implication Assessment

BS5837: 2005 'Trees in relation to construction – recommendations'

1. SUMMARY

- 1.1 This report comprises an arboricultural impact assessment of the revised proposals for 56 Belsize Avenue, London NW3 4AA, reviewing any conflicts between the proposals and material tree constraints identified in our survey.
- 1.2 There are 5 trees surveyed on or around the site, of which 2 are 'B' category *(Moderate Quality), 2 'C' category *(Low Quality) and 1 'R' category *(Poor Quality). The three trees (T1-3) in the rear garden are unaffected by the proposals. This report is principally concerned with the two trees (T4 & 5) at the front of the property. T4 is a mature ash tree within the front courtyard garden. The tree is rather large for the small space and has been pruned accordingly to the point that has developed a rather sprawling habit. It is rated C Category. T5 is an early mature, purple maple within the roadside verge. It is unlikely to be affected but will need protecting from site traffic.
- 1.3 In theory, only the good-moderate quality trees are a material constraint on development. However, the low quality trees may still comprise a constraint in terms replacement planting within the conservation area.
- 1.4 The sole impact in the current proposals is the removal of T4. Although the tree is mature and stands within the conservation area it has been rated low quality: its sprawling habit and dominance of the front garden space detracts from the rhythm and line of the open avenue of tall lime trees with their regular and erect habits. Removal of the tree may actually improve the visual character of the area from an aesthetic point of view. There will be a gross environmental loss from the tree's removal, but this loss needs to be netted of all future management costs to cyclical pruning were the tree retained. The environmental benefits of unsuitable trees begin to pale under the fossil fuel commitment of bringing a tree gang in from the suburbs every few years to shoehorn them back into place. It may be more environmentally friendly to replace with a suitable specimen. In this instance, a new lime tree is proposed for the roadside verge to complement the existing lime avenue and replace another verge tree that was recently lost to the area.
- 1.4 Thus, with suitable mitigation, the tree removal is rated low impact and the scheme is held to be arboriculturally viable.

* British Standards Institute. 2005. Trees in Relation to Construction BS 5837: 2005 HMSO, London

2. INTRODUCTION

2.1 Terms of reference

- 2.1.1 LANDMARK TREES were asked by Mr & Mrs Stirling to undertake an arboricultural planning survey of the site: 56 Belsize Avenue, London NW3 4AA. The report is to accompany a planning application.
- 2.1.2 The proposals are for the construction of PROPOSALS and this report will assess the impact on the trees and their constraints, identified in our survey. Although the proposals were known at the time of the survey, Landmark Trees endeavour to survey each site blind, working from a topographical survey, wherever possible, with the constraints plan informing their evolution.
- 2.1.3 I am a Registered Consultant and Fellow of the Arboricultural Association and a Chartered Forester, with a Masters Degree in Arboriculture and 20 years experience of the landscape industry - including the Forestry Commission and Agricultural Development and Advisory Service. I am a UK Registered Expert Witness, trained in single joint expert witness duties. I am also Chairman of the UK & I Regional Plant Appraisal Committee, inaugurated to promote international standards of valuation in arboriculture.

2.2 Drawings supplied

- 2.2.1 The drawings supplied by the client and relied upon by Landmark Trees in the formulation of our survey plans are:
- Topographical survey – explan140610
- Proposed ground floor – proplan140610

2.3 Scope of survey

- 2.3.1 As Landmark Trees' arboricultural consultant, I surveyed the trees on site on 14th May 2009, recording relevant qualitative data in order to assess both their suitability for retention and their constraints upon the site, in accordance with British Standard 5837:2005 Trees in relation to construction – Recommendations [BS5837].
- 2.3.2 Our survey of the trees, the soils and any other factors, is of a preliminary nature. The trees were inspected on the basis of the Visual Tree Assessment method expounded by Mattheck and Breloer (The Body Language of Trees, DoE booklet Research for Amenity Trees No. 4, 1994). I have not taken any samples for analysis and the trees were not climbed, but inspected from ground level.
- 2.3.3 The survey does not cover the arrangements that may be required in connection with the laying or removal of underground services.

2.4 Survey data & report layout

- 2.4.1 Detailed records of individual trees are given in the survey schedule in Appendix 1 to this report.
- 2.4.2 A site plan identifying the surveyed trees, based on the client's drawings / topographical survey is provided in Appendix 4.
- 2.4.3 This plan also serves as the Tree Constraints Plan with the theoretical Recommended Protection Areas (RPA's), tree canopies and shade constraints, (from BS5837: 2005) overlain onto it. These constraints are then overlain in turn onto the client's proposals to create an Arboricultural Impact Assessment Plan in Appendix 5. General observations and discussion follow, below.

3.0 OBSERVATIONS

3.1 Site description



Fig. 1 Looking NE along the avenue with T4 (right) & T5 (left) in foreground



Fig. 2 Looking SW along the avenue with established lime avenue

- 3.1.1 The site is a residential terrace in Belsize Park with southeast-facing gardens to the rear and northwest-facing courtyards to the front. The adjoining network of rear gardens provides a good degree of tranquility and greenery. The dominant green infrastructure is the mature lime avenue which characterises the area.
- 3.1.2 The site is relatively level.
- 3.1.3 In terms of the Soil Survey of England and Wales, the soil lies within the unsurveyed area of Greater London where the soils are generally, highly shrinkable clay; e.g. slowly permeable seasonally waterlogged fine loam over clay. Such soils are prone to compaction during development. Damage to soil structure can have a serious impact on tree health. Design of foundations near problematic tree species will also need to take into consideration subsidence risk. A structural engineer may be able to advise further on the local geology and its implications for development.

3.2 Subject trees

- 3.2.1 There are 5 trees surveyed on or around the site, of which 2 are 'B' category *(Moderate Quality), 2 'C' category *(Low Quality) and 1 'R' category *(Poor Quality). The three trees (T1-3) in the rear garden are unaffected by the proposals. This report is principally concerned with the two trees (T4 & 5) at the front of the property. T4 is a mature ash tree within the front courtyard garden. The tree is rather large for the small space and has been pruned accordingly to the point that has developed a rather sprawling habit. It is rated C Category. T5 is an early mature, purple maple within the roadside verge.


3.3 Planning Status

- 3.3.1 The property stands within a Conservation Area, which will affect trees on the site. It is a criminal offence to disturb or damage such trees without permission from the local authority.

4.0 DEVELOPMENT CONSTRAINTS

4.1 Primary constraints

- 4.1.1 BS5837: 2005 gives Recommended Protection Areas (RPA's) for any given tree size. The individual RPA's are calculated in the Tree Schedule in Appendix 1 to this report, or rather the notional radius of that RPA, based on a circular protection zone. The prescribed radius is generally 12-x stem diameter at 1.5m above ground level, except where basal diameters are used in the case of multi-stemmed trees, and the radius is set at 10x the diameter.
- 4.1.2 Circular RPA's are appropriate for individual specimen trees grown freely such as these, but where there is ground disturbance, the morphology of the RPA can be modified to an alternative polygon, and where appropriate shifted 20% in the direction of undisturbed ground, as shown in the diagram below. In less fanciful terms, one needs to remember that RPA's are area-based and not linear. **No modifications have been made in this instance.**




- 4.1.3 R Category trees are discounted from the process. Category-C trees would not normally constrain development individually, unless they provide some external screening function. As discrete, internal trees, their removal will not affect the wooded envelope that encloses much of the site.
- 4.1.4 "Care should be exercised over misplaced tree preservation. Attempts to retain too many or unsuitable trees on a site are liable to result in excessive pressure on the trees during development work and subsequent demands for their removal. The end result is usually fewer and less suitable trees than would be the case if proper planning, selection and conservation had been applied from the outset." (BS5837: 2005)

- 4.1.5 In theory, only the good and moderate quality trees are a material constraint on development. However, the low quality trees may still comprise a constraint in terms of at least, replacement planting within the conservation area. Of the two trees to the front of the property, only T5 is B category. T5 is unlikely to be affected by the proposals, but will need protecting from site traffic.

4.2 Secondary Constraints

4.2.1 The second type of constraint produced by trees that are to be retained is that the proximity of the proposed development to the trees should not threaten their future with ever increasing demands for tree surgery or felling to remove nuisance shading, honeydew deposition or perceived risk of harm.



4.2.3 The shading constraints are crudely determined from BS5837 by drawing an arc from northwest to east of the stem base at a distance equal to the height of the tree, as shown in the diagram opposite. Shade is less of a constraint on non-residential developments, particularly where rooms are only ever temporarily occupied. This arc represents the effects that a tree will have on layout through shade, based on shadow patterns of 1x tree height for a period May to Sept inclusive 10.00-18.00 hrs daily.

4.2.4 The principal secondary constraint would be shading on to any light wells illuminating the basement. However, the roadside trees will cast their shadows to the north away from the property.

Note: Sections 5 & 6 will now assess the impacts upon constraints identified in Section 4. Table 1 in Section 5 presents the impacts in tabular form (drawing upon survey data presented in Appendices 1 & 2). Impacts are presented in terms of whole tree removal and the effect on the landscape or partial encroachment (% of RPA) and its effect on individual tree health. Section 6 discusses the table data, elaborating upon the impacts' significance and mitigation.

5.0

Table 1: Arboricultural Impact Assessment for Retained Trees

(Impacts assessed prior to mitigation and rated with reference to From Matheny & Cark (1998))

Hide irrelevant

Show All Trees

| B.S. Cat. | Tree No. | Species | Impact | Tree / RPA Affected | Age | Growth Vitality | Species Tolerance | Impact on Tree Rating | Impact on Site Rating | Mitigation |
|-----------|----------|-------------|-------------------------------------|-------------------------|--------|-----------------|-------------------|--------------------------|--------------------------|-------------------------------|
| C | 4 | Ash, Common | Felled to Facilitate Development | m ² N/A % | Mature | Normal | N/A | N/A | Low | New planting / landscaping |

6.0 DISCUSSION

6.1 Rating of Primary Impacts

- 6.1.1 The sole impact in the current proposals is the removal of T4. Although the tree is mature and stands within the conservation area it has been rated low quality: its sprawling habit and dominance of the front garden space detracts from the rhythm and line of the open avenue of tall lime trees with their regular and erect habits. Removal of the tree may actually improve the visual character of the area from an aesthetic point of view.
- 6.1.2 Removal of T4 is rated low impact.

- 6.1.3 There will be a gross environmental loss from the tree's removal, but this loss needs to be netted of all future management costs to cyclical pruning were the tree retained. The environmental benefits of unsuitable trees begin to pale under the fossil fuel commitment of bringing a tree gang in from the suburbs every few years to shoehorn them back into place. It may be more environmentally friendly to replace with a suitable specimen.

6.2 Rating of Secondary impacts

- 6.2.1 There are no secondary impacts in the current proposals.

6.3 Mitigation of Impacts

- 6.3.1 In this instance, a new lime tree is proposed for the roadside verge to complement the existing lime avenue and replace another verge tree that was recently lost to the area.

7.0 CONCLUSION

- 7.1 The potential impacts of development are rated low in terms of overall effect on the visual character of the local area.
- 7.2 Therefore, the proposals will not have any significant impact on either the retained trees or wider landscape.

8.0 RECOMMENDATIONS

8.1 Specific Recommendations

- 8.1.1 Tree works recommendations are found in Appendix 2 to this report. Any tree removals recommended within this report should only be carried out with local authority consent.
- 8.1.3 Replace felled tree T4 with 1 x native lime (*Tilia cordata*) pit-planted as 14-16 cm girth nursery stock under current best practice; i.e. conforming to and planted in accordance with the following:

- BS 3936:1980 Nursery Stock;
- BS 4043:1966 Transplanting Semi-Mature Trees; and
- BS 5236:1975 Cultivation and Planting of Trees in the Advanced Nursery Stock Category.
- All replacement stock should be planted and maintained as detailed in BS 4428:1989 (Section 7): Recommendations for General Landscape Operations.

8.2 General Recommendations

- 8.2.1 Any trees which are in close proximity to buildings proposed for demolishing should be protected with a Tree Protection Barrier (TPB). This TPB should comprise steel, mesh panels 2.2m in height ('Heras') and should be mounted on a scaffolding frame (shown in Fig 2 of BS5837). The position of the TPB can be shown on plan as part of the discharge of conditions, once the lay out is agreed with the planning authority. The TPB should be erected prior to commencement of works, remain in its original form on-site for the duration of works and removed only upon full completion of works.
- 8.2.2 A TPB may no longer be required during soft landscaping work but a full arboricultural assessment must be performed prior to the undertaking of any excavations within the RPA of a tree. This will inform a decision about the requirement of protection measures. It is important that all TPBs have permanent, weatherproof notices denying access to the RPA.
- 8.2.3 The use of heavy plant machinery for building demolition, removal of imported materials and grading of surfaces should take place in one operation. The necessary machinery should be located above the existing grade level and work away from any retained trees. This will ensure that any spoil is removed from the RPAs. It is vital that the original soil level is not lowered as this is likely to cause damage to the shallow root systems.
- 8.2.4 Any pruning works must be in accordance with British Standard 3998:1989 Tree work [BS3998].
- 8.2.5 Where sections of hard surfacing are proposed in close proximity to trees, it is recommended that "No-Dig" surfacing be employed in accordance with BS5837:2005 and 'The Principles of Arboricultural Practice: Note 1, Driveways Close to Trees, AAIS 1996 [APN1]'.

- 8.2.6 Where scaffolding installation is required within the RPA the provisions of Figure 3 of BS5837 with regard to ground protection must be employed.
- 8.2.7 If the RPA of a tree is encroached by underground service routes then BS5837 and NJUG 10 provisions should be employed. If it is deemed necessary, further arboricultural advice must be sought.
- 8.2.8 Numerous site activities are potentially damaging to trees e.g. parking, material storage, the use of plant machinery and all other sources of soil compaction. In operating plant, particular care is required to ensure that the operational arcs of excavation and lifting machinery, including their loads, do not physically damage trees when in use.

- 8.2.9 To enable the successful integration of the proposal with the retained trees, the following points will need to be taken into account:
- 1) Plan of underground services.
 - 2) Schedule of tree protection measures, including the management of harmful substances.
 - 3) Method statements for constructional variations regarding tree proximity (e.g. foundations, surfacing and scaffolding).
 - 4) Site logistics plan to include storage, plant parking/stationing and materials handling.
 - 5) Tree works: felling, required pruning and new planting. All works must be carried out by a competent arborist in accordance with BS3998.

- 6) Site supervision: the Site Agent must be nominated to be responsible for all arboricultural matters on site. This person must:
- * be present on site for the majority of the time
 - * be aware of the arboricultural responsibilities
 - * have the authority to stop work that is causing, or may cause harm to any tree
 - * ensure all site operatives are aware of their responsibilities to the trees on site and the consequences of a failure to observe these responsibilities.
 - * make immediate contact with the local authority and/or a retained arboriculturalist in the event of any tree related problems occurring.
- 8.2.10 These points can be resolved and approved through consultation with the planning authority via their Arboricultural Officer.
- 8.2.11 The sequence of works should be as follows:
- * initial tree works: felling, stump grinding and pruning for working clearances
 - * installation of TPB for demolition & construction
 - * installation of underground services
 - * installation of ground protection
 - * main construction
 - * removal of TPB
 - * soft landscaping

9.0 REFERENCES

- British Standards Institute. 2005. Trees in Relation to Construction BS 5837: 2005 HMSO, London.
- Barlow JF & Harrison G. 1999. Shade By Trees, Arboricultural Practice Note 5, AAIS, Farnham, Surrey.
- Lonsdale D 1999. Research for Amenity Trees No.7: Principles of Tree Hazard Assessment and Management, HMSO, London.
- Centre for Ecology & Hydrology. 2006. Tree Roots in the Built Environment, HMSO, London.
- Matheny, N; Clark, J. R.1998. Trees and Development: A Technical Guide to Preservation of Trees during Land Development. Champaign
- Mattheck C. & Breloer H. 1994. Research for Amenity Trees No.2: The Body Language of Trees, HMSO, London.
- Thomas P, 2000. Trees: Their Natural History, Cambridge University Press, Cambridge.

APPENDIX 1TREE SCHEDULE - Notes for Guidance

| | |
|----------------|--|
| Dm - | is the diameter of the trunk in millimetres at 1.5m above ground level. |
| Spread - | is in metres at the points of the compass relevant to the woodland boundary |
| Class/Colour - | refers to the retention classifications in Section 5.2 BS5837: 2005 and colouring on the site map - Highly High Quality (A) (Green), Moderate Quality (B) (Blue), Low Quality (C) (Grey), Poor Quality (R) (Red) |

BS5837 Tree Constraints Survey Schedule

Site: 56 Belsize Avenue, London NW3 4AA

Surveyor(s): Adam Hollis

Date: 14th May 2010

Ref:

| Tree No. | English Name | Height | Crown Spread | Ground Clearance | Age Class | Stem Diameter | Protection Multiplier | Protection Radius | Growth Vitality | Structural Condition | Landscape Contribution | B.S. Cat | Sub Cat | Useful Life | Observations |
|----------|------------------|--------|--------------|------------------|--------------|---------------|-----------------------|-------------------|-----------------|----------------------|------------------------|----------|---------|-------------|---|
| 1 | Poplar, Lombardy | 24 | 3322 | 4 | Mature | 1000 | 12 | 12.0 | Normal | Fair | High | B | 1 | 20-40 | Remote survey only |
| 2 | Poplar, Hybrid | 12 | 4433 | 4 | Mature | 600 | 12 | 7.2 | Normal | Poor | Low | R | | <10 | Unprofessionally topped/lopped Entry wounds on trunk Remote survey only |
| 3 | Cedar, Atlantic | 8 | 4223 | 3 | Early Mature | 300 | 12 | 3.6 | Moderate | Fair | Low | C | 2 | 20-40 | Remote survey only |
| 4 | Ash, Common | 15 | 6,10,8,5 | 3 | Mature | 510 | 12 | 6.1 | Normal | Fair | Medium | C | 2 | 20-40 | Co-dominant limbs Entry wounds on trunk Sprawling habit 5m to build |
| 5 | Maple, Norway | 16 | 5344 | 4.5 | Early Mature | 380 | 12 | 4.6 | Normal | Fair | Medium | B | 1 | 20-40 | Co-dominant limbs Entry wounds on trunk |

Notes:

1. Height describes the approximate height of the tree measured in meters from ground level.
2. The Crown Spread refers to the crown radius in meters from the stem centre and is expressed as an average of NSEW aspect if symmetrical.
3. Ground Clearance is the height in meters of crown clearance above adjacent ground level.
4. Stem Diameter is the diameter of the stem measured in millimeters at 1.5m from ground level for single stemmed trees or at ground level for multi-stemmed trees. Stem Diameter may be estimated where access is restricted.
5. Protection Multiplier is 12 for single stemmed and 10 for multi-stemmed trees and is the number used to calculate the tree's protection radius and area.

6. Protection Radius is a radial distance measured from the trunk centre.
7. Growth Vitality - Normal growth, Moderate (below normal), Poor (sparse/weak), Dead (dead or dying tree).
8. Structural Condition - Good (no or only minor defects), Fair (remediable defects), Poor - Major defects present.
9. Landscape Contribution - High (prominent landscape feature), Medium (visible in landscape), Low (secluded/among other trees).
10. B.S. Cat refers to (British Standard 5837:2005 Table 1) and refers to tree/group quality and value; 'A' - High, 'B' - Moderate, 'C' - Low, 'R' - Remove.
11. Sub Cat refers to the retention criteria values where 1 is Arboricultural, 2 is Landscape and 3 is Cultural including Conservational, Historic and Commemorative.
12. Useful Life is the tree's estimated remaining contribution in years.

APPENDIX 2

RECOMMENDED TREE WORKS

Recommended Tree Works

Hide irrelevant

Show All Trees

Site: 56 Belsize Avenue, London NW3 4AA

Surveyor(s): Adam Hollis

Page

Date: 14th May 2010

Ref:

| Tree No. | English Name | Height | Stem Diameter | Crown Spread | Recommended Works | Comments/ Reasons |
|----------|------------------|--------|---------------|--------------|-------------------|---|
| 1 | Poplar, Lombardy | 24 | 1000 | 3322 | FInv | Remote survey only |
| 2 | Poplar, Hybrid | 12 | 600 | 4433 | FInv | Unprofessionally topped/lopped Entry wounds on trunk Remote survey only |
| 4 | Ash, Common | 15 | 510 | 6,10,8 ,5 | Fell | Co-dominant limbs Entry wounds on trunk Sprawling habit 5m to build Recommended to permit development |

Notes:

- CB - Cut Back to boundary/clear from structure.
- CL# - Crown Lift to given height in meters.
- CT#% - Crown Thinning by identified %.
- CCL - Crown Clean (remove deadwood/crossing and hazardous branches and stubs).
- CR#% - Crown Reduce by given maximum % (of outermost branch & twig length)
- DWD - Remove deadwood.
- Fell - Fell to ground level.
- FInv - Further Investigation (generally with decay detection equipment).
- Pol - Pollard or re-pollard.
- Mon - Monitor ongoing condition (annually by staff / owners & every 2-3 yrs by consultant).
- Svr Ivy / Clr Bs - Sever ivy / clear base and re-inspect base / stem for concealed defects.

APPENDIX 3: TREE SELECTION FOR CONSTRICTED SITES


Table 4: Rosaceous Tree Species for Constricted Planting Sites

| Common Name | Species | Selected Form |
|----------------------|-----------------------------|---------------------|
| Hawthorn | <i>Crataegus monogyna</i> | Stricta |
| Cockspur | <i>Crataegus prunifolia</i> | Splendens |
| Cherry | <i>Prunus x hillieri</i> | Spire |
| Bird cherry | <i>Prunus padus</i> | Albertii |
| Rowan / Mountain ash | <i>Sorbus aucuparia</i> | Cardinal Royal |
| Rowan / Mountain ash | <i>Sorbus aucuparia</i> | Rossica Major |
| Rowan / Mountain ash | <i>Sorbus aucuparia</i> | Sheerwater Seedling |
| Swedish whitebeam | <i>Sorbus intermedia</i> | Brouwers |
| Bastard whitebeam | <i>Sorbus x thuringiaca</i> | Fastigiata |

Table 5: Specimen Tree Species for Constricted Planting Sites

| Common Name | Species | Selected Form |
|------------------------|------------------------------------|-------------------------------|
| Chinese red bark birch | <i>Betula albosinensis</i> | Fascination |
| Swedish birch | <i>Betula pendula</i> | Dalecarlica |
| Hornbeam | <i>Carpinus betulus</i> | Fastigiata Frans Fountaine |
| Turkish Hazel | <i>Corylus colurna</i> | |
| Maidenhair tree | <i>Ginkgo biloba</i> | |
| Pride of India | <i>Koelreuteria paniculata</i> | Fastigiata |
| European larch | <i>Larix decidua</i> | Sheerwater Seedling |
| Tulip tree | <i>Liriodendron tulipifera</i> | Fastigiata |

APPENDIX 4TREE CONSTRAINTS PLAN



Root Protection Areas (RPA) are derived from stem diameter measured at 1.5 m above adjacent ground level (taken on sloping ground on the upslope side of the tree base) or immediately above the root flare for multi-stemmed trees.

2 Sheraton Street, London, W1F 8BH
Tel: 0800 055 6912 Mobile: 07812 989928
e-mail: info@landmarktrees.co.uk Web: www.landmarktrees.co.uk

Key:

- Category A
High Quality
- Category B
Moderate Quality
- Category C
Low Quality
- Category R
Poor Quality

The diagram shows a tree with a central trunk and a canopy. The trunk is labeled 'Root' and 'Protection Area'. The canopy is labeled 'Crown Spread'. The tree is divided into three main sections: 'Root', 'Trunk', and 'Canopy'. The 'Trunk' section is labeled 'Tree Number' and 'Species'. The 'Canopy' section is labeled 'Category'.

Category

Root

Protection Area


Crown Spread

Tree Number

Species

Category

APPENDIX 5ARBORICULTURAL IMPACT ASSESSMENT PLAN




NOTE:

This survey is of a preliminary nature. The trees were inspected from the ground only on the basis of the Visual Tree Assessment method. No samples were taken for analysis. No decay detection equipment was employed. The survey does not cover the arrangements that may be required in connection with the laying or removal of underground services.

Branch spread in metres is taken at the four cardinal points to derive an accurate representation of the crown.

Root Protection Areas (RPA) are derived from stem diameter measured at 1.5 m above adjacent ground level (taken on sloping ground on the upslope side of the tree base) or immediately above the root flare for multi-stemmed trees.




Landmark Trees
2 Sheraton Street, London, W1F 8BH
Tel: 0800 055 6912 Mobile: 07812 989928
e-mail: info@landmarktrees.co.uk Web: www.landmarktrees.co.uk


| | |
|---|-----------|
| Site: 56 Belsize Avenue | 1-200@A3 |
| Drawing Title: Arboricultural Impact Assessment | June 2010 |

Key:

- Category A High Quality
- Category B Moderate Quality
- Category C Low Quality
- Category R Poor Quality



- Crown Spread
- Tree Number
- Species
- Category
- Root Protection Area

 Tree Proposed for Removal