Arboricultural Impact Assessment

59 Aberdare Gardens London NW6 3AL

291003-PD-02 October 2009

CONTENTS PA	GE
--------------------	----

1	INTRODUCTION	2
	TERMS OF INSTRUCTION	. 2
	HISTORY OF PROJECT INVOLVEMENT	. 2
	DOCUMENTS PROVIDED	. 2
	METHODOLOGY	. 2
2	THE SITE AND ITS SETTING	3
	GENERAL AREA DESCRIPTION	. 3
	BOUNDARIES OF THE SITE	. 3
	OVERVIEW OF TREES ON THE SITE	. 3
3	DATA COLLECTION	4
	SITE VISIT	. 4
	METHODOLOGY OF SURVEY	.4
	SUMMARY AND ANALYSIS OF TREES	. 5
4	PLANNING GUIDANCE AND CONSTRAINTS	6
	LEGAL PROTECTION OF THE TREES	. 6
	NATIONAL POLICIES AND GUIDANCE	. 6
	REGIONAL POLICIES AND GUIDANCE	. 7
	LOCAL POLICIES AND GUIDANCE	. 7
5	DEVELOPMENT PROPOSALS	8
	PROPOSED DEVELOPMENT	. 8
	PROPOSED DEVELOPMENT	. 8 . 8
	PROPOSED DEVELOPMENT THE MAIN ARBORICULTURAL IMPACTS TO BE CONSIDERED TREE WORKS	. 8 . 8 . 8
6	PROPOSED DEVELOPMENT THE MAIN ARBORICULTURAL IMPACTS TO BE CONSIDERED TREE WORKS JUXTAPOSITION OF TREES AND STRUCTURES	. 8 . 8 . 8 . 8
6	PROPOSED DEVELOPMENT THE MAIN ARBORICULTURAL IMPACTS TO BE CONSIDERED TREE WORKS JUXTAPOSITION OF TREES AND STRUCTURES ABOVE GROUND CONSTRAINTS – GENERAL	. 8 . 8 . 8 . 9
6	PROPOSED DEVELOPMENT THE MAIN ARBORICULTURAL IMPACTS TO BE CONSIDERED TREE WORKS	.8 .8 .8 .9 .9
6	PROPOSED DEVELOPMENT THE MAIN ARBORICULTURAL IMPACTS TO BE CONSIDERED TREE WORKS JUXTAPOSITION OF TREES AND STRUCTURES ABOVE GROUND CONSTRAINTS – GENERAL ABOVE GROUND CONSTRAINTS – LIGHT AND SHADE ABOVE GROUND CONSTRAINTS – CONSTRUCTION DELOW CROUND CONSTRAINTS – CONSTRUCTION	.8 .8 .9 .9
6	PROPOSED DEVELOPMENT THE MAIN ARBORICULTURAL IMPACTS TO BE CONSIDERED TREE WORKS JUXTAPOSITION OF TREES AND STRUCTURES ABOVE GROUND CONSTRAINTS – GENERAL ABOVE GROUND CONSTRAINTS – LIGHT AND SHADE ABOVE GROUND CONSTRAINTS – CONSTRUCTION BELOW GROUND CONSTRAINTS	.8 .8 .9 .9 .9
6	PROPOSED DEVELOPMENT THE MAIN ARBORICULTURAL IMPACTS TO BE CONSIDERED TREE WORKS JUXTAPOSITION OF TREES AND STRUCTURES ABOVE GROUND CONSTRAINTS – GENERAL. ABOVE GROUND CONSTRAINTS – LIGHT AND SHADE ABOVE GROUND CONSTRAINTS – CONSTRUCTION BELOW GROUND CONSTRAINTS TREE PROTECTION	.8 .8 .9 .9 .9 .9
6	PROPOSED DEVELOPMENT THE MAIN ARBORICULTURAL IMPACTS TO BE CONSIDERED TREE WORKS JUXTAPOSITION OF TREES AND STRUCTURES	.8 .8 .9 .9 .9 .9 .9 .9
6 7	PROPOSED DEVELOPMENT	.8 .8 .9 .9 .9 .9 .9
6 7 8	PROPOSED DEVELOPMENT	.8 .8 .9 .9 .9 .9 .1 11 11
6 7 8 AP	PROPOSED DEVELOPMENT	.8 .8 .9 .9 .9 .9 .9 .1 11 11 11 11
6 7 8 AP	PROPOSED DEVELOPMENT. THE MAIN ARBORICULTURAL IMPACTS TO BE CONSIDERED. TREE WORKS. JUXTAPOSITION OF TREES AND STRUCTURES. ABOVE GROUND CONSTRAINTS – GENERAL. ABOVE GROUND CONSTRAINTS – LIGHT AND SHADE. ABOVE GROUND CONSTRAINTS – CONSTRUCTION. BELOW GROUND CONSTRAINTS – CONSTRUCTION. BELOW GROUND CONSTRAINTS. TREE PROTECTION. THE USE OF PLANNING CONDITIONS TO SAFEGUARD TREES. PHYSICAL PROTECTION. SUMMARY AND CONCLUSIONS . 1 PENDIX A: PLANS. 1 PENDIX B: TREE SCHEDULE . 1 1 1 1 1 1 1 1 1 1 1 1 1	.8 .8 .9 .9 .9 .9 .11 11 11 12 .3
6 7 8 AP AP	PROPOSED DEVELOPMENT. THE MAIN ARBORICULTURAL IMPACTS TO BE CONSIDERED. TREE WORKS JUXTAPOSITION OF TREES AND STRUCTURES ABOVE GROUND CONSTRAINTS – GENERAL. ABOVE GROUND CONSTRAINTS – LIGHT AND SHADE ABOVE GROUND CONSTRAINTS – CONSTRUCTION. BELOW GROUND CONSTRAINTS – CONSTRUCTION. BELOW GROUND CONSTRAINTS. TREE PROTECTION. 1 THE USE OF PLANNING CONDITIONS TO SAFEGUARD TREES. PHYSICAL PROTECTION. 1 SUMMARY AND CONCLUSIONS 1 PENDIX A: PLANS 1 PENDIX B: TREE SCHEDULE 1 PENDIX C: LOCAL PLAN EXTRACTS.	.8 .8 .9 .9 .9 .9 .11 11 11 12 .3 .4

1 INTRODUCTION

Terms of instruction

- 1.1 The following arboricultural impacts assessment (AIA) has been commissioned by Mr Georg Schraut in order to provide information to assist all parties involved in the planning process to make balanced judgements with regard to arboricultural features in relation to the proposed development at 59 Aberdare Gardens, London NW6 3AL.
- 1.2 This report includes:
 - an assessment of the trees, their quality and value and constraints to development posed by these;
 - the impact of the proposed development upon the tree population in and around the site;
 - measures to be taken to protect trees during the proposed works.

History of project involvement

1.3 Arboricultural involvement has followed the recommendations of BS5837:2005. A layout for the proposed development had been prepared before taking arboricultural advice.
 Following our involvement in the design process the design has been amended to ensure that the arboricultural impacts are acceptable.

Documents provided

- 1.4 This report has been prepared with reference to the following supplied information:
 - Existing plans by architect R Savage Associates
 - proposed plans by architect R Savage Associates
 - Existing rear, front and side elevations by architect R Savage Associates

Methodology

1.5 The methodology used in the preparation of this report is based on the principles of British Standard BS5837:2005 *Trees in relation to construction*. The trees and other significant vegetation on and around the site have been surveyed using the recommendations of BS5837:2005. Following the arboricultural survey the above and below ground constraints were presented to the development team to aid design.

1.6 The proposed layout has been assessed in relation to the impacts of trees on structures and vice versa with regard to the above and below ground constraints as well as the planning policy and legal constraints in relation to trees.

2 THE SITE AND ITS SETTING

General area description

2.1 The site consists of a semi-detached residential property, with a rear garden. The surrounding area is residential, with a mixture of mature trees

Boundaries of the site

2.2 To the north of the site is the rear garden which is bordered by the rear gardens of Green croft Gardens. To the south is a small front garden and then Aberdare residential road, to the east is 61 Aberdare Gardens, and to the west 57 Aberdare gardens.

Overview of trees on the site

2.3 The site itself has only one hawthorn tree in the front garden (T7), and a mix of other smaller, shrubs. There is a row of mature London Plane trees off site but immediately adjacent to the northern boundary of the site (T1, T2, and T3 are relevant). There are three trees adjacent to the eastern rear boundary of the site.

3 DATA COLLECTION

Site visit

- 3.1 The site was visited on 7 October 2009 when trees on and around the site were inspected from ground level. The survey methodology has followed the recommendations of British Standard BS5837:2005 *Trees in relation to construction*.
- 3.2 A topographical survey has not been available in the production of this report. The tree locations are therefore based on a measured survey where trees have been plotted in relation to fixed site features such as boundaries or buildings. The location of trees should be checked on site.

Methodology of survey

- 3.3 Each tree has been given a tree identification number for the purpose of this report. This is only a reference and the trees are not individually marked.
- 3.4 Despite being presented with a proposed site layout prior to the tree survey being undertaken, the trees over 75mm in diameter measured at 1.5m above ground level on the site were surveyed without reference to a proposed layout as detailed in paragraph 4.5 of BS5837:2005. Off site trees over 75mm diameter and within a distance equal to 12 times their diameter from the boundary (10 times their base diameter where multi-stemmed) or where their crowns overhang the site boundary have been included. Where access to off site trees was not available dimensions are estimates.
- 3.5 BS5837:2005 sets out the methodology for surveying trees on potential development sites in order to identify them within a prioritised system of retention categories summarised as:
 - **A Category** Trees of high quality and value in such a condition as to be able to make a substantial contribution for a minimum of 40 years
 - **B Category** Trees of moderate quality and value in such a condition as to make a significant contribution for a minimum 20 years
 - **C Category** Trees of low quality and value currently in adequate condition to remain until new planting could be established and expected to remain for a minimum of 10 years, or young trees with a stem diameter less than 150 mm measured at 1.5 metres above ground level.
 - **R Category** Trees in such a condition that any existing value would be lost within 10 years and which should, in the current context, be removed for reasons of sound arboricultural or forestry management.

Summary and analysis of trees

- 3.6 The location of trees and groups of trees are shown on plan 291003-P-01 at Appendix A, this plan illustrates the location of trees and the extent of the spread of their crowns.
 Dimensions, comments and information for each tree are given in the tree schedule at Appendix B.
- 3.7 The tree survey covered 7 trees. Of the trees surveyed the most common tree species is London Plane.
- 3.8 Of the trees covered in the survey there are 4 C category trees which are of low quality and value and should not be significant constraints to development.
- 3.9 There are 3 off site trees that are categorised as being B category, of moderate quality and value and would need to be considered in terms of development impact.

4 PLANNING GUIDANCE AND CONSTRAINTS

Legal protection of the trees

- 4.1 The local planning authority, Camden Borough Council, has not been approached to establish whether there is a tree preservation order protecting trees on or adjacent the site or whether the site is within a conservation area.
- 4.2 The general provisions of the Forestry Act 1967 have not been considered in this report as full planning consent is an exemption to the need for a felling licence.
- 4.3 As an arboricultural impacts assessment this report has not considered the impact of development upon the habitats associated with the trees. During the tree survey where appropriate, significant signs of in particular bats and nesting birds were considered and have been recorded where observed. This is not an ecological report and the absence of comments about birds or bats does not necessarily mean that they are not present on the site.

National policies and guidance

- 4.4 Planning policy statement 1 states at paragraph 13 (KEY PRINCIPLES): (iv) Planning policies should promote high quality inclusive design in the layout of new developments and individual buildings in terms of function and impact, not just for the short term but over the lifetime of the development. Design which fails to take the opportunities available for improving the character and quality of an area should not be accepted"
- 4.5 The British Standards Institute published BS5837:2005 in September 2005. The document was developed through consultation with engineers, architects landscape architects, central government and developers and gives clear and current best practice recommendations and guidance on the principles to be applied to achieve a satisfactory juxtaposition of trees with structures. Where development is proposed, the standard provides guidance on how to assess the value and quality of trees and to decide which trees are appropriate for retention. The surveying of trees as part of the feasibility assessment of a site is important to ensure that the trees inform the design process.
- 4.6 The structured approach to survey, assessment, design, construction and aftercare of trees within BS5837:2005 includes:
 - tree survey establish what trees are present on and adjacent to the site and to measure their dimensions;

- tree categorisation give each tree or group of trees a classification based on arboricultural, landscape and conservation values;
- tree constraints plan a plan illustrating the physical attributes of the trees and implications that they would have over the design process. The above and below ground constraints with tree retention category are shown and these are used by the design team to develop a layout based on keeping and protecting important trees;
- involvement with the design team to establish a suitable layout;
- consider trees suitable for retention based on agreed appropriate layout in the format of an arboricultural implications assessment;
- arboricultural method statement setting out clearly how the trees will be managed through the process of development. This will include a tree protection plan;
- pre-development work includes the erection of tree protective fencing to secure trees as well as the facilitation of pruning to enable access; and
- methods for the installation of new hard surfaces in proximity to trees to ensure root protection and long term health.

Regional policies and guidance

4.7 The Mayor's London Plan (2004) discusses the principles of sustainable development and incorporation of local policies within the UDP of local authorities to support this.

Local policies and guidance

- 4.8 Policy N8 of the Camden Borough UDP is relevant in considering the impacts of proposed development on trees. A copy of the full text of this policy is attached at Appendix C.
- 4.9 Supplementary Planning Guidance (SPG) 2006 has been produced by the council to support the Unitary Development Plan (UDP) and which contains more details on the importance of trees within development, the impact of proposed development, protection and replacement planting, and is relevant.
- 4.10 Guidance on basement developments and extensions to existing basements has also been published in February 2009, and is relevant to the consideration of this proposal in relation to trees.

5 DEVELOPMENT PROPOSALS

Proposed development

5.1 The layout for the proposed development is shown on plan 291003-P-02 at Appendix A and is for the demolition of the existing extension and conservatory and the construction of a replacement extension consisting of a basement and ground floor with a light well. A new patio area will also be constructed as part of the extension.

The main arboricultural impacts to be considered

- 5.2 The main arboricultural issues in respect of the proposals are as follows:
 - light and shade;
 - impact upon root protection areas

Tree works

5.3 There will be no tree works required as part of this application

6 JUXTAPOSITION OF TREES AND STRUCTURES

Above ground constraints – general

- 6.1 Above ground constraints, due to retained trees, could include shading especially to windows, the presence of branches in proximity to structures where damage may occur, as well as possible nuisances such as falling leaves, honeydew and fruit.
- 6.2 BS5837:2005 requires the consideration of constraints posed to development by the above ground parts of trees and take into account such matters as future growth of the tree and obstruction of daylight and sunlight in accordance with published guidance including that from the Building Research Establishment (BRE).

Above ground constraints – light and shade

6.3 The most significant trees are T1, T2 and T3 located on the northern boundary within a neighbouring property. The amount of separation from the proposed rear extension and the three trees is significant and given their orientation availability of daylight and shading is not considered a significant issue.

Above ground constraints – construction

6.4 The trees are located at the rear of the site away from the proposal. Construction activities will be a significant distance from the trees and the crowns pose no significant constraint to construction traffic.

Below ground constraints

- 6.5 The below ground constraints are generally summarised as the root protection area (RPA). BS5837:2005 recommendations provides a formula for calculating the RPA which indicates an area required to be protected for existing trees that are to be retained. The shape of the RPA and its exact location will depend upon arboricultural considerations including:
 - likely tolerance of the tree to root disturbance;
 - morphology and disposition of the roots when known influenced by past or existing site conditions;
 - soil type and structure; and
 - topography and drainage.

- 6.6 The purpose of the RPA is to prevent physical damage to tree roots and to prevent damage to the soil structure. Damage can be made to live roots by soil compaction, changes in soil levels or soil contamination which could reduce tree health and/or stability.
- 6.7 Development within the RPA of trees can be acceptable provided some important principles are followed and these are primarily not excavating but building above existing ground level instead, use of pile, radial or cantilever foundations, where new surfaces are introduced they should be permeable and allow air to pass to and from the soil as well as water to ensure tree roots survive. Development within the precautionary RPA must allow for and enable the future growth of the tree root, stem and branches and where new structures are constructed.
- 6.8 On this site all of the proposed development is outside of root protection areas for retained trees. It is only a small corner of the patio which will be within the RPA of a small off site tree. The amount of encroachment is negligible and will not be detrimental to the trees health or stability.

7 TREE PROTECTION

The use of planning conditions to safeguard trees

- 7.1 Section 197 of the Town and Country Planning Act 1990 places a duty on the Local Planning Authority to ensure that planning permissions are granted making adequate provision for the preservation and planting of trees by the imposition of conditions.
- 7.2 The normal requirements of planning conditions have been considered at an early stage of the process and all tree impact issues can be addressed within such a planning condition.

Physical protection

- 7.3 Trees can be readily damaged if care is not taken during development of site from demolition through construction and also landscaping. A summary of the principles to follow and methods of common damage are given at Appendix D.
- 7.4 It is important that a continuous tree protective fencing is securely fixed to a static fence around trees. The use of weld mesh fencing without a fixed base will not be acceptable and is not in accordance with BS5837:2005 recommendations.
- 7.5 The positioning of tree protective fencing should take into account the size and condition of the individual trees to be protected and the risks to their health posed by the development during and after construction. An indicative location for tree protection fencing is at Appendix A, on plan 291003-P-03.

8 SUMMARY AND CONCLUSIONS

- 8.1 British Standard BS5837:2005 contains clear and current recommendations for a best practice approach to the assessment, retention and protection of trees on development sites. The proposed development has followed this guidance by:
 - Seeking arboricultural advice to inform the layout and design of the proposed building;
 - Respecting the constraints posed to development of the site by high or moderate quality trees; and
 - Continuing to take advice on all aspects to the proposal that may impact upon trees.
- 8.2 There will be no tree works required as part of this development and all of the retained trees can be protected during the development, by appropriate tree protection and the implementation of an arboricultural method statement including site supervision, by continuing to follow the recommendations in BS5837:2005 and by compliance with suitably drafted planning conditions.

APPENDIX A: PLANS

Tree survey 291003-P-01

Proposed development 291003-P-02

Tree protection plan 291003-P-03



													nd catv	
Tel: 0845 094 3268 Fax: 0845 094 3269 www.tma-consultants.co.uk	ARBORICULTURAL & LANDSCAPE CONSULTANTS 96 GREENWAY BUSINESS CENTRE HARLOW BUSINESS PARK HARLOW ESSEX CM 1 9 5QE	Drawing No Scale 291003-P-01 1:250@A3	Date Drawn by Ocober 2009 HR	59 Aberdare Gardens	Client Mr. H Patel	Title Tree Survey	REVISIONS	· · ·	structure must be protected. All works within thes areas will require special methods of work	o B55837 Root Protection Areas Freezutionary areas within which tree roots and so	o Category R Category R Category R Category R Category R Trees in such a condition that any existing value wo be lost within 10 years and which should, in the	Trees of moderate quality and value: those in such condition as to make a significant contribution (a minimum of 20years is suggested) Category C	Category A Trees of high quality and value: in such a condition to be able to make substantial contribution (a minim of 40 years is suggested) Category B	DO NOT SCALE Use only figured dimensions BS 5837:2005 TREE RETENTION CATEGORIES



		$\left. \right\rangle$								\mathbf{k}			5				
www.tma-con	Tel: 0845 Fax: 0845	HAK ESSEX CI	96 GREENWAY B HARLOW BUS	TIM MOYA A	Drawing No 291003-P-02	Date Ocober 2009	⁹ roject 59 Aberdare Gard.	Client Mr. H Patel	Title Tree Survey ≰ Prop	REV I	- 9505/TPO) REVIS		Category R Trees in such a the loss in such a the loss tithin i i current context, arboncultural ma	Category C Trees of low qu conductor to ren established (a r young trees wit	Category B Trees of moder: conteon as to minimum of 20ye	Category A Trees of high qu to be able to m of 40 years is	00 NOT SCALE Ise only figured dimensions 35 5837:2005 TREE RETENTIC
sultants.co.uk	094 3268 094 3269	MI9 5QE	USINESS CENTRE SINESS PARK	SSOCIATES NDSCAPE CONSULTANTS	Scale 1 :250@A3	Drawn by HR	8113		osed Layout		SIONS		condition that any existing value would 3 years and which should, in the be removed for reasons of sound nagement:	ality and value: currently in adequate rain until new planting could be immoun of 10years is suggested), or n a stem diameter below 150mm.	ste quality and value: those in such a make a significant contribution (a sars is suggested)	Jality and value: in such a condition as ake substantial contribution (a minimum uggested)	IN CATEGORIES



																	India		
www.tma-consultants.co.uk	Tel: 0845 094 3268 Fax: 0845 094 3269	96 GREENWAY BUSINESS CENTRE HARLOW BUSINESS PARK HARLOW ESSEX CM I 9 5QE	TIM MOYA ASSOCIATES ARBORICULTURAL & LANDSCAPE CONSULTANTS	Drawing No Scale 291003-P-03 1:250 @A3	Date Drawn by October 2009 HR	Project 59 Aberdare Gardens	Client Mr H Patel	Title Tree Protection Plan	REVISIONS	- 9505/FP01			Tree protection zones and protective fencing	Category R Trees in such a condition that any existing value would be lost within 10 years and which should, in the current context, be removed for reasons of sound arboncultural management.	Trees of low quality and value: currently in adequate condition to remain until new planting could be established (a minimum of IOyears is suggested), or young trees with a stem diameter below ISOmm.	Category B Trees of moderate quality and value: those in such a condution as to make a significant contribution (a minimum of 20years is suggested)	0	Category A Trees of high quality and value: in such a condition as to be able to make substantial contribution (a minimum of 40 years is suggested)	DO NOT SCALE Use only figured dimensions BS 5837:2005 TREE RETENTION CATEGORIES

APPENDIX B: TREE SCHEDULE

Tree schedule 291003-PD-01

Tree No.	Species	Height (m)	Stem diameter (mm)	Branch spread N (m)	Branch spread E (m)	Branch spread S (m)	Branch spread W (m)	Clear crown (m)	Maturity	Physiological condition	Structural condition	Comments and recommendations	Estimated remaining contribution (yrs)	Retention category
T1	Platanus x hispanica (London Plane)	23	650 e	5.6	5.6	5.6	5.6	4	Mature	Good	Good	Leaf miner on leaves (Phyllonorycter platani). Recommend:	20-40	B2
T2	Platanus x hispanica (London Plane)	23	700 e	11.9	11.9	11.9	11.9	3	Mature	Good	Good	Leaf miner on leaves (Phyllonorycter platani). Recommend:	20-40	B2
Т3	Platanus x hispanica (London Plane)	23	800 e	9.5	9.5	9.5	9.5	3	Mature	Good	Fair	Leaf miner on leaves (Phyllonorycter platani). Leaning to east. Some decaying pruning wounds. Recommend:	20-40	B2
Т4	Cratageus monogyna (Hawthorn)	5	350 e				2.4	1.5	Mature	Good	Fair	Leaning to east, Ivy on lower stem. Recommend: Crown lift to 3m overhanging boundary.	20-40	C1
Т5	Cratageus monogyna (Hawthorn)	8	250 e	3.7	3.7	3.7	3.7		Mature	Good	Fair	Ivy growing throughout crown. Recommend:	10-20	C1
Т6	Sorbus torminalis (Wild Service tree)	6	300 e				2.0		Mature	Fair	Fair	Completely overgrown with Ivy. Recommend:	10-20	C1

Tree No.	Species	Height (m)	Stem diameter (mm)	Branch spread N (m)	Branch spread E (m)	Branch spread S (m)	Branch spread W (m)	Clear crown (m)	Maturity	Physiological condition	Structural condition	Comments and recommendations	Estimated remaining contribution (yrs)	Retention category
Τ7	Cratageus monogyna (Hawthorn)	6	230	4.0	4.2	4.3	0.0	3	Mature	Fair	Good	Recommend: Re-shape crown. Remove deadwood.	20-40	C1