

Pre Construction Information

Construction Information

Scope of Work Covered by this Risk Assessment

Roof renewal of church hall

Work Activity Information

General

Site Safety

All operatives, including subcontractors, working on site will be made aware of the Health and Safety risk assessments of Skyline Roofing Kingston. Instructions will be given regarding specific site conditions and procedures which must be adhered to.

Hard hats, high visibility jackets and safety footwear must be worn at all times where instructed or signed on site. This will generally be during the initial start up of the project.

All powered hand tools will be 110v or battery operated.

The relevant test certificates and identification numbers of any hired in plant will be submitted to SITE SUPERVISOR prior to use on site.

No smoking on site.

All operatives and visitors to sign in and out of the site.

Site Welfare Facilities

Site welfare will be provided by St marys church

Unloading & Storage Areas

Materials must be arranged to arrive at site only when requested by the Site supervisor.

Suppliers must be informed of the need to arrive at agreed times, this is to ensure that transport issues are kept to a minimum during the works.

Program of Works

tbc

Storage Arrangements

heras fenced off compound

Environmental Issues

All waste is to be removed by the main contractor using the skip provided and collected by a licensed

waste carrier. Duty of care tickets will be contained in this folder.

Contractor Vehicle/Traffic Arrangements

Considerations Regarding Other Site Users

Existing Structure