

PJ Turner ND.Arb Ditton Nurseries, Ditton Nurseries Driveway, Summerfield Lane, Surbiton, Surrey KT6 5DZ

Phone: 020 8393 3222 or 020 8546 9888 Email: turnertreecare@fsmail.net

Work Specification -

Kings College London Hampstead Campus **Kidderpore** Avenue Hampstead London NW3 7ST

Queen Mother Hall, Kiddrerpore Avenue -

T1: Silver Birch - Remove dead wood and prune to clear the service wires.

T2: Ornamental Cherry - Raise the crown to 3 metres over the footpath.

CFT TA: Turkey Oak - Prune to clear the Vicarage building by 2-3 metre the highway and remove dead wood. , T3: Turkey Oak – Prune to clear the Vicarage building by 2–3 metres, raise the crown to 5.5 metres over

T5: Ash tree - Remove dead wood.

T6: Ornamental Cherry - Raise the crown to 3 metres from ground level.

Kidderpore Avenue -

T7: Holly x 3 - Raise the crown over the footpath to 3 metres.

T8: Ornamental Cherry - Raise the crown to 5 metres from ground level over the highway, thin the remaining crown and remove dead wood.

T9: Maidenhair tree - Prune to clear the building by 2 metres.

T10: Purple Plum and Cotoneaster - Raise the crown to 3 metres.

TII: Turkey Oak tree - Remove dead wood and raise the crown to 5.5 metres over the highway.

T12: Ash tree - Reduce and reshape the crown by 25% and remove dead wood.

Courtyard area -

.

T13: Hornbeam - Prune to clear the building by 2.5 metres and raise the crown to 3 metres from ground level.

T14: Paulownia - Remove dead wood.

T15: Indian Bean Tree - Remove dead wood.

T16: Davidia - Prune to clear the building by 2 metres, raise the crown to 3 metres from ground level and reduce the low branch by 20%.

. . _..

T17: Ornamental Cherry - Remove dead wood and prune to clear the stairs.