



# TURNER TREE CARE

*Providing specialist care for your trees*

PJ Turner ND.Arb

Ditton Nurseries, Ditton Nurseries Driveway,  
Summerfield Lane, Surbiton, Surrey KT6 5DZ

Phone: 020 8393 3222 or 020 8546 9888 Email: [turnertreecare@fsmail.net](mailto:turnertreecare@fsmail.net)

## Work Specification -

Kings College London  
Hampstead Campus  
Kidderpore Avenue  
Hampstead  
London  
NW3 7ST

### Queen Mother Hall, Kidderpore Avenue -

T1: Silver Birch - Remove dead wood and prune to clear the service wires.

T2: Ornamental Cherry - Raise the crown to 3 metres over the footpath.

C97 TPC ← T3: Turkey Oak - Prune to clear the Vicarage building by 2-3 metres, raise the crown to 5.5 metres over the highway and remove dead wood.

C97 TPC ← T4: Beech tree - Prune to clear the Vicarage building by 2-3 metres.

T5: Ash tree - Remove dead wood.

T6: Ornamental Cherry - Raise the crown to 3 metres from ground level.

### Kidderpore Avenue -

T7: Holly x 3 - Raise the crown over the footpath to 3 metres.

T8: Ornamental Cherry - Raise the crown to 5 metres from ground level over the highway, thin the remaining crown and remove dead wood.

T9: Maidenhair tree - Prune to clear the building by 2 metres.

T10: Purple Plum and Cotoneaster - Raise the crown to 3 metres.

T11: Turkey Oak tree - Remove dead wood and raise the crown to 5.5 metres over the highway.

T12: Ash tree - Reduce and reshape the crown by 25% and remove dead wood.

Courtyard area –

T13: Hornbeam – Prune to clear the building by 2.5 metres and raise the crown to 3 metres from ground level.

T14: Paulownia – Remove dead wood.

T15: Indian Bean Tree – Remove dead wood.

T16: Davidia – Prune to clear the building by 2 metres, raise the crown to 3 metres from ground level and reduce the low branch by 20%.

T17: Ornamental Cherry – Remove dead wood and prune to clear the stairs.