



Existing ground floor extension abutts the feature red bricks with a vertical joint. It is not bonded to the main house and hides the return brick.

The 2 courses of creasing tiles is particular poor detail.

All this could be improved by setting back the side extension wall by 450mm as the suggested planning revision.

DETAIL SHOWING THE JUNCTION OF THE SIDE EXTENSION AND THE MAIN HOUSE