





- NOTES:
- 1) INTERNAL FACES OF BATHROOM STUD PARTITION TO HAVE E.M.L., CEMENT/SAND RENDER & SET, OR OTHER IMPERVIOUS FINISH AS APPROVED BY THE P.H. INSPECTOR.
 - 2) THE "MECHAVENT" PD 1A EXTRACTOR TO THE INTERNAL BATHROOM IS TO BE OPERATED OFF THE LIGHT SWITCH WITH A 20 MINUTE OVER-RUN. A 150 x 75 mm ALLOY LOUVRE VENT GRILLE IS TO BE PROVIDED IN THE BASE OF THE BATHROOM DOOR FOR AIR REPLACEMENT.
 - 3) ALL BATHS, WASH BASINS & SINKS TO HAVE 75 mm (deep seat) PVC BOTTLE TRAPS.

LONDON BOROUGH OF CAMDEN
TOWN AND COUNTRY PLANNING ACTS
13 JUN 1978
PLANS APPROVED
ON BEHALF OF THE COUNCIL
CASE COPY.

CTP/H13/7/9/26376

CONSTRUCTION	CENTRAL HEATING	GAS	MISCELLANEOUS	ELECTRICAL	OTHER
new brickwork	boiler	gas meter	extending	meter	two way
new blockwork	(wall mounted)	gas meter	clothes drier	consumer unit	intermediate
new stud	single radiator	multipoint	cooker space	mains sb + meter	pull cord
partition	double radiator	gas point	fridge space	lighting outlets	key
	towel rail		washing	ceiling	weatherproof
			machine space	wall	socket outlets (13 amp)
				fluorescent	single
				switches	double
				one way	single switched
					double switched
					extract fan
					immersion htr.
					storage heater
					thermostat
					bell push
					bell transformer
					landlord supply
					one way switch
					socket outlet
					lighting outlet

Date Revision

Pollard Thomas and Edwards

85 Colebrooke Row London N1 8AF 01-359 7121 MAR-1978 1:50

CAMDEN SQUARE


PROPOSED PLANS

24 CANTELOWES ROAD, NW1.

114 067/5

NOTES:

- 1) TIMBER BASEMENT FLOOR TO BE TAKEN UP & NEW SOLID FLOOR LAID:
100mm HARDCORE WITH SAND BUNDING.
1000 gauge "VISQUEEN" POLYTHENE D.P.M.
150mm 1:2:4 CONCRETE SLAB (WITH 50mm DEEP CAST IN DUCTS FOR PIPES)
3 COATS "TREETOL" WATER PROOFING.
50mm 1:3 CEMENT/SAND SCREED.
2mm DUNLOP "SEMPOR" TILES.
- 2) SPECIALIST SUB-CONTRACTOR TO PROVIDE A SILICONE INJECTED D.P.C. TO BRICKWORK AT GROUND LEVEL & TREAT TIMBERS PRONE TO DECAY OR INFESTATION.
- 3) NEW MANHOLES TO BE CONSTRUCTED FROM 150mm THICK CONCRETE BASE IN 225mm SOUTHWATER BRICKS LAID IN ENGLISH BOND.
100mm 3/4 CHANNEL BENDS SET IN FINE CONCRETE BENCHING.
C.I. SINGLE SEAL COVER TO PAVING LEVEL.
NEW DRAINS TO BE 100mm Ø GLAZED STONEWARE LAID TO FALL 1:60 ON A 150mm CONCRETE BED OUTSIDE THE BUILDING, AND TOTALLY ENCASED IN 150mm CONCRETE SURROUND UNDER THE BUILDING.
- 4) ALL SANITARY FITTING WASTES TO HAVE 75mm (DEEP SEAL) BOTTLE TRAPS AT OUTLET.
- 5) LEVELS FOR EXTERNAL PAVING & RAMPS TO BE AGREED ON SITE.
- 6) SEE IRONMONGERY SCHEDULE FOR SPECIAL DOOR FURNITURE.
- 7) SEE KITCHEN & BATHROOM DETAIL SKETCHES FOR FITTING DETAILS & POSITIONS.
- 8) ALL LIGHT SWITCHES, SOCKET OUTLETS, DOOR HANDLES & OPERATING LEVERS TO WINDOWS TO BE FIXED 1,040mm ABOVE FLOOR LEVEL.
- 9) RADIATOR VALVES TO BE MOUNTED AT TOP OF RADIATORS.



FLAT A · BASEMENT · 1 PERSON · 1 BEDROOM · FOR DISABLED PERSON.

LONDON BOROUGH OF CAMDEN
TOWN AND COUNTRY PLANNING ACTS
13 JUN 1978
APPROVED
ON BEHALF OF THE COUNCIL
CASE COPY.

CTP/H13/7/9/26376

NOTES
scaled dimensions are not to be taken from the drawings
dimensions must be checked on site before work is carried out or components ordered
discrepancies are to be referred to the architect for clarification

NOTES

CONSTRUCTION
new brickwork
new stud partition
225 x 150mm AIR BRICK AT HIGH LEVEL
BLACKUP FIREPLACE & FIX 225x75mm VENT AT HIGH LEVEL

CENTRAL HEATING
boiler (wall mounted)
single radiator
double radiator
towel rail
OUTLINE OF STRUCTURES TO DEMOLISH

GAS
gas meter
multipoint
gas point
RUN OF NEW DRAINS
RUN OF EXISTING DRAINS

MISCELLANEOUS
extending
clothes drier
cooker space
fridge space
washing machine space
C
F
WM


ELECTRICAL
meter
consumer unit
mains sb + meter
lighting outlets
ceiling
wall
fluorescent
switches
one way

two way
intermediate
pull cord
key
weatherproof
outlets (13 amp)
single
double
single switched
double switched

single switched
worktop level
apparatus outlets
unswitched spur
switched spur + pilot lamp
cooker control
cooker connect
fixed apparatus
extract fan

immersion htr.
storage heater
thermostat
bell push
bell
bell transformer
landlord supply
one way switch
socket outlet
lighting outlet


Pollard Thomas and Edwards
55 Colebrooke Row London N1 8AF 01-359 7121
APRIL 78 1:50
CAMDEN SQUARE
BASEMENT FLAT CONVERSION FOR DISABLED PERSON.
24 CANTLOWES ROAD. NW1.
114 067/8



LONDON BOROUGH OF CAMDEN
TOWN AND COUNCIL PLANNING ACTS
13 JUN 1978
PLANS APPROVED
ON BEHALF OF THE COUNCIL
CASE COPY.

CTP/H13/ 7/9/26376

- NOTES :
- 1) INTERNAL FACES OF BATHROOM STUD PARTITIONS TO HAVE E.M.L. CEMENT/ SAND RENDER & SET, OR OTHER IMPERVIOUS FINISH AS APPROVED BY THE P.H. INSPECTOR.
 - 2) THE 'MECHAVENT' PD IA EXTRACTOR TO THE INTERNAL BATHROOMS ARE TO BE OPERATED OFF THE LIGHT SWITCH WITH A 20 MINUTE OVER-RUN. A 150x75 mm ALLOY LOUVRE VENT GRILLE IS TO BE PROVIDED TO THE BASE OF THE DOOR FOR AIR REPLACEMENT.
 - 3) VENT DUCTS TO LOBBIES ARE TO TERMINATE AT THE CEILING OVER WITH A 225 x 150 mm PLASTER LOUVRE VENT.
 - 4) ALL BATHS, WASH BASINS & SINKS TO HAVE 75 mm (DEEP SEAL) PVC BOTTLE TRAPS.



LONDON BOROUGH OF CAMDEN
TOWN AND COUNTRY PLANNING ACTS
13 JUN 1978
PLANS ~~NOT APPROVED~~ APPROVED
ON BEHALF OF THE COUNCIL
CASE COPY

CTP/H13/7/9/26376

ELECTRICAL  meter  consumer unit  mains sb-meter  outlets  ceiling  wall  fluorescent  switches  one way	 two way  intermediate pull cord  weatherproof outlets (13 amp)  single double  single switched double switched  socket	 single switched workshop level  apparatus outlets  unswitched spur  switched spur  pilot lamp  supply control  cooker connect  fixed apparatus  extract fan	 immersion htr.  storage heater  thermostat  bell push  bell transformer  landlord  one way switch  socket outlet  lighting outlet	CONSTRUCTION  new brickwork  new blockwork  new stud partition  ab  225 x 150 mm air brick  at high level  1/2 hour fire resisting & self closing door	CENTRAL HEATING  boiler  (wall mounted)  single radiator  double radiator  towel rail	GAS  gas meter  multipoint  gas point	MISCELLANEOUS  extending clothes rail  cooker space  fridge space  washing machine space  wm
---	--	---	---	---	--	--	---

Pellard Thomas and Edwards			
85 Coplebrooke Row London N1 8AF	01-369 7121	MAR 1978	1:50
LAMDEN SQUARE PROPOSED PLANS 24 LAMPELDES ROAD, NW1.		NO	114 007/6