

5 CHALCOT SQUARE NW1 - DOOR SCHEDULE AS EXISTING AND PROPOSED

page 1 of 4

Revised October 2007 – Ground Floor DG2, DG5 and 2nd Floor D26

BASEMENT

D01	Modern glazed door to basement front, 830mm wide with fixed glazed transome and side window.	All to be removed
D02	Modern moulded door 690 x 185 x 36mm	To be removed
D03	Original door 830 x 1860 x 30mm 4 panel between front and rear rooms	To be retained
D04	Original door 800 x 1980 x 36mm 4 panel to rear bedroom	To be resited to new shower room in basement
D05	Modern flush door to rear extension area	To be replaced with D08
D06	New entrance door from front basement area	Timber framed, half glazed see Dr. No. 607/22
D07	New front bedroom room door	Timber 4 panel to match others - ½ Hr FR see Dr. No. 607/25
D08	New door to rear extension area	4 panel door to match others – ½ Hr FR – Dr. No. 607/25
D09	New sliding folding doors to new rear extension	Dark grey powder coated slim aluminum framed glazed doors as shown on rear elevation Dr. No. 607/15 + section 607/21

50 HALCOT SQUARE NW1 - DOOR SCHEDULE AS EXISTING AND PROPOSED page 2 of 4

Revised October 2007

GROUND FLOOR

DG1	Original main entrance door	To be retained
DG2	Original door to front room – 900 x 2070 x 45mm 4 panel with ogee mouldings	To be retained in original position
DG3	A non-original door to rear room previously made to match DG2 900 x 2070 x 45mm	To be retained
DG4	Original 3 door set between front and rear rooms each 700 x 2670 mm 3 panel with ogee mouldings Badly warped – do not close	To be retained
DG5	Original half glazed door to rear extension with cat flap 750 x 1950 x 30	To be retained
DG6	Modern, "Dutch" style half glazed door to garden stairs, 675 x 2040 x 45mm	To be removed. Replaced by DG9 See Dr. No. 607/25
DG7	New timer framed 4 panel door with ogee mouldings constructed to ½ Hr. FR	To replace DG5 See Dr. No. 607/26
DG8	New doors to balcony/flat roof section of new extension	Timber framed glazed french doors with transome light over. All mouldings and glazing beads to match existing window see Dr. No. 607/24
DG9	New timber half glazed door to widened rear opening	see Dr. No. 607/25

5CHALCOT SQUARE NW1 - DOOR SCHEDULE AS EXISTING AND PROPOSED page 3 of 4

Revised October 2007

1ST FLOOR

D11	Original 4 panel door to bathroom on landing The top 2 panels are glazed. 700 x 193 x 30	Retain door. Replace glass with Replace glass with solid panels
D12	Original door to front room – 910 x 2120 x 45mm 4 panel with ogee mouldings	To be retained
D13	Original door to rear room – 910 x 2120 x 45mm 4 panel with ogee mouldings	To be retained
D14	Previous replacement or added door between front and rear rooms 895 x 2120 x 45mm 4 panel with ogee mouldings and smaller architrave	To be removed

2ND FLOOR

D21	Original door to front bedroom 800 x 2030 x 37 4 panel with ogee moldings	To be retained
D22	A later addition doorway to front bedroom 710 x 1920 x 35, 4 panel, plain, no mouldings	To be removed and doorway infilled
D23	Doorway without door	
D24	New flush door door to bathroom 725 x 2030 x 42 with panel beads face fixed to one side	To be removed
D25	Original door, matching D21, which has been repositioned into modern partition forming rear dressing room/office	Remove from current position and rehang in original position i.e D23 doorway
D26	New doorway and door in wall between front and rear rooms	To match D21 & D25 see Dr. No. 607/25
D27	Modern flush door on staircase up to 3 rd floor 685 x 1860 x 33	To be removed

50 HALCOT SQUARE NW1 - DOOR SCHEDULE AS EXISTING AND PROPOSED

page 4 of 4

Revised October 2007

3RD FLOOR

D31	Original 4 panel plain door with one upper panel glazed and painted 755 x 1980 x 34	To be retained. remove glass panel and fit solid panel
D32	Original 4 panel plain door 755 x 1980 x 35	To be retained.
D33	Original 4 panel plain door 755 x 1980 x 35	To be retained.
D34	Original 4 panel plain door 755 x 1960 x 35	To be retained.

4TH FLOOR

D41	Modern flush door, top shaped to roof angles 760 X 1800 X 34mm	To be removed
-----	---	---------------