Existing stone (full width & length) adjacent works

Existing stone plinth to be carefully removed by stone work specialist

Existing bronze/brass balustrade set into stone floor to be carefully removed by specialist and set aside

Existing marble skirting board to be carefully removed by specialist and set aside

Strip out (Central Saloon):
-all fixtures and fittings
-all skirtings to wall EXCEPT at base of columns/pilasters
-all vinyl floor finishes

Existing marble skirting board to be protected during construction prior to final cleaning

CENTRAL SALOON (GALLERY 38)

GALLERIES 36/37 NOTE: [illegible] Care to be taken to avoid any damage to ceiling and lath to public below.

Stone column plinth to be carefully repaired to match original stone finish

Existing modern dry lining to be removed

Stair to mezzanine to be removed

GALLERY 40

GALLERY 41

Existing stone threshold to be protected during construction prior to final cleaning

A-A BDP-A-2000

B-B BDP-A-2000

37 GALLERY 37

38 GALLERY 38

39 GALLERY 39

Existing modern dry lining to be removed

Existing modern dry lining to be removed

Remove/fix and locate stone floor to store

BOTANICAL STAIR

E-E BDP-A-2001

F-F BDP-A-2001

Strip out (Gallery 37):
-all fixtures and fittings
-all skirtings to wall EXCEPT at base of columns/pilasters
-all vinyl floor finishes

K-K BDP-A-2002

L-L BDP-A-2002

All existing exposed & retained stonework to be protected during construction prior to final cleaning

Strip out (Gallery 38):
-all furniture, fixtures and fittings
-all finishes EXCEPT skirtings, wall and ceiling finishes, unless otherwise indicated

M-M BDP-A-2003

N-N BDP-A-2003

Existing vinyl on all original stone to be carefully removed by stonework specialist

Existing oak strip flooring to be carefully lifted by specialist, set aside/protected and reinstated following installation of building services

Existing architrave and lining to be retained and protected prior to refurbishment

Existing vinyl on all original stone to be carefully removed by stonework specialist

O-O BDP-A-2004

P-P BDP-A-2004

SCOPE OF WORK BOUNDARY

Strip out (Gallery 39):
-all furniture, fixtures and fittings
-all finishes EXCEPT skirtings, wall and ceiling finishes, unless otherwise indicated

" TO BE READ WITH METHOD STATEMENT FOR THE LIFTING OF NATURAL STONE FLOORING AND THE REINSTATEMENT AND INSTALLATION OF NATURAL STONE FLOORING "

ARY VERTICAL
N TO BE DEMOLISHED
ADJACENT
N TO BE REPAIRED
RAL ENGINEER'S

EXISTING MODERN SECONDARY CONSTRUCTION TO BE REMOVED & ADJACENT CONSTRUCTION TO BE REPAIRED TO MATCH EXISTING ADJACENT

EXISTING WALL FINISH/ DRY LINING TO BE REMOVED BACK TO BRICKWORK

EXISTING FLOOR AND SUPPORTING STRUCTURE BELOW TO BE REMOVED

EXISTING FLOOR FINISH & SUPPORTING SUBSTRATE REMOVED DOWN TO TOP OF STRUCTURE NB. SUPPORTING STRUCTURE TO BE RETAINED

BUILDERS WORK IN CONNECTION WITH BUILDING SERVICES (SEE PROPOSED ARCHITECT STRUCTURAL & M&E DRAWINGS)

BW

AREA OF EXISTING STONE TO BE CAREFULLY LIFTED BY STONE WORK SPECIALIST TO ACCESS VOID BELOW FOR SERVICES INSTALLATION. TO BE REINSTATED FOLLOWING INSTALLATION

EXISTING STONEWORK TO BE REMOVED DOWN TO TOP OF STRUCTURE

EXISTING CDM ISSUE/HAZARD FOR CONTRACTOR'S ATTENTION

A EXISTING CAST IRON GRATINGS, STONE AND BRASS FLOOR TRIM TO FLOOR DUCTS TO BE LIFTED, SET ASIDE AND PROTECTED PRIOR TO REINSTATEMENT. TEMPORARY COVER TO BE PROVIDED DURING THE WORKS.

ISSUE

-	Issue For Information	BC	JC	11/11/06
A	Issue for Tender	BC	JC	11/01/07
B	Issue for Tender	BC	JC	27/02/07

THE BRITISH MUSEUM

BDP

Building Design Partnership
Architects, Designers and Engineers
16 Brewhouse Yard, Clerkenwell
London, EC1V 4LJ
Tel +44 (0)20 7812 8000
Fax +44 (0)20 7812 8388
www.bdp.co.uk

THE BRITISH MUSEUM
The South Stair, Central Saloon and Galleries 37 to 40

Demolition, Alteration & Strip out
Level 6 (first floor)

1:100 @ A1
1:200 @ A3
10.08.06

LN08732 | GI200E-BDP-A-2260 | B

Extract from drawing (previously submitted).