

4.1	Column bases (hard limestone) Clean the stone, remove the tidemark left by the lowering of Pew platforms	16 no	
4.2	Column shafts. Clean the column shafts All to match the shaft cleaned in 1994 (C3)	18 no	
4.3	Capitals. Clean the capitals All to match the capital cleaned in 1994 (C3)	18 no	
4.4	Lintels over aisle windows (hard limestone) Clean the lintels	10 no	
	<b>NOTE:</b> The expression to match 1994 work refers only to the colour, tone and texture of 1994 work, <u>NOT</u> to the methods to be used which are subject to approval of Clause 1.2 above.		
5	<b>Stone repair</b>		
5.1	Stone repairs masonrywork to column bases to rough hewn faces of the bottom of 10 m faces to bases	10 no	
5.2	Fill in to match in stone mortar to form		
5.3	Cut away to smooth face plinth with existing		
5.4	To Aisle window lintels N & S, fill the cracks with stonedust/lime mortar	4 no	
TOTAL (ex VAT)			
end			

## St STEPHENS ROSSLYN HILL

		STONE/STONE REPLACEMENTS /STONE CLEANING /GRAFFITI & STAIN REMOVAL /Stone repairs - masonry work		
Refer to drawings		2828 132 NORTH AISLE ELEVS (N&S) DEFECTS.pdf (A1) 2828 133 SOUTH AISLE ELEVS (N&S) DEFECTS.pdf (A1) 2828 160 EW SECTIONS North Ph1.pdf (A1) 2828 161 EW SECTION South Ph1.pdf (A1) 2828 314A PLANS GF Ph2.pdf (A1) 2828 331A PLANS GF Ph3.pdf (A1)		
1	1.0	<b>Study &amp; Report</b>	Qty/rate	£
		Refer to Adriel Consultancy advice + tests (see note 4.3 below)		
	1.1	Prepare a <b>Study and Report</b> on the methods and materials to be used in the work and present it to ARP for approval of EH, LB Camden and the Trust Including adjusted costings against a <b>Contingency</b> to be included here.		2,500.00
2	2.0	<b>Stone Replacements</b>		
	2.1	<b>Mansfield stone columns</b> to the Porches, Galilee, nave and presbytery (double columns) Replace by taking out complete and inserting new stone to match the Mansfield (advise on a selection of matching red sandstone). Make good to capitals and bases.	8 no	
	2.2	Chancel marble dongles 50 x 50 shaped half spherical Cipolino marble to fit existing sockets.	60 no	
	2.2.1	Cut out and preserve for identification 60 no remnants of original marbles		
	2.2.2	Provisional sum for Analysing/matching specific marbles and the mortar mix for fixing	60 no	1,000.00
3		<b>Graffiti</b>		
	3.1	Remove graffiti from columns	6 no	
	3.2	Remove the stains from column (G3)	1 no	
	3.3	Remove the paint stains (H4)	1 no	
4		<b>Stone cleaning</b>		

RECEIVED