ST STI	EPHENS	GLAZING SCHEDULE		Jan 2007
REFERE	INCES :	1	1	
Refer to	Part 3 specification clauses : Se	ction 11: Windows		
	Part 2 specification clauses : L1			
	•	150-158 (EXTNG GLAZING) & 185-190 (PROPOSEI) GLAZING)	
Refer to	Window Masonry Schedule for r	epairs to window surrounds		
	V DESCRIPTION / CONDITION	GLAZING & FERRAMENTA	REPAIRS : Phase 2 :	TENDER
NO				
CRYPT I	LEVEL WINDOWS			
BOILER	ROOM			
WB1	SINGLE LANCET		Phase 2 work	
	window entirely missing	boarded up	New louvred access door to	
			new boiler room	
		no glass	no glass work **	
CVIOTIN				
EXISTIN	IG WC ISINGLE LANCET			
WB2	Window repaired in phase 1	window protected with stainless steel mesh panel	Remove mesh & refix on	
	Trandow repaired in priase 1	minow protected with stanliess steel mean paller	completion	
	opening casement with fixed	broken panes	replace broken panes - New	
	glazed panes over		leaded glazing L40/300:	
			opaque glass - square & diamond panes	
			diamona panos	
WB5 5.1	COMPOSITE LANCET Window repaired in phase 1	window protected with stainless steel mesh panel	Remove mesh & refix on	
J. I	window repaired in phase i	window protected with stanless steer mean panel	completion	
	opening casement	broken panes	replace broken panes - New	
	, 5		leaded glazing L40/300:	
			cathedral glass - square &	
			diamond panes	
	·			
	STAIR TURRET (EAST END)			
WB6	LANCET		Phase 2 work	-
		boarded over glazing very broken ; remove remaining	Remove boarding 1/C20	
		sections and prepare for new leaded glazing	all new cames & glazing; square panes with border	
		, , ,	New leaded glazing L40/300:	
			opaque glass	
			supply & install 1 no support	
			bar	
00/07				
CRYPT V	VESTRY ROOM			<u> </u>
10/	Window repaired in phase 1	window protected with stainless steel mesh panel	Remove mesh & refix on	
	Transformer opariou in pilase 1	window protected with stanliess steel mesh panel	completion	
7.1	LANCET	broken panes	repairs broken panes	
	opening casement with fixed	leaded : leading broken - A B N	New leaded glazing L40/300:	
	glazed panes over	- 四位地区中,	opaque glass - square panes	
		a aakt i		
	and the second se	leaded : leading broken TR REDV		
GROUN	D FLOOR LEVEL WINDOWS			
MANAGE	ER'S OFFICE		1	

۰

GLAZING SCHEDULE

Jan 2007

1

WINDOW NO	DESCRIPTION / CONDITION	GLAZING & FERRAMENTA	REPAIRS : Phase 2 :	TENDER
WG9	LANCET	window boarded over	Phase 2 work : remove boarding	
		leaded : border with squares over diamonds; glass damaged	retain - clean & repair	
		provisional allowance : to be directed once boarding removed and window can be inspected	replace 10 no diamond panes; 10 no square panes	
			New leaded glazing L40/300: opaque glass	
		opening casement with fixed light over	ease,adjust & refurbish sliding section & hopper; replace cord for hopper; repaint black gloss	
		**bars	supply & install 1 no support bar	
WG10		window boarded over	Phase 2 work : remove boarding	
		leaded : border with squares over diamonds; glass damaged	retain - clean & repair	
		provisional allowance : to be directed once boarding removed and window can be inspected	replace 10 no diamond panes; 10 no square panes	
			New leaded glazing L40/300: opaque glass	2
		opening casement with fixed light over	ease,adjust & refurbish sliding section & hopper; replace cord for hopper; repaint black gloss	
		**bars	supply & install 1 no support bar	
WG11	LANCET	window boarded over	Phase 2 work : remove boarding	
		leaded : border with squares over diamonds; glass damaged	retain - clean & repair	
2 2 2 2 2 2 2 2 2 2 2 2 2 2 2 2 2 2 2		provisional allowance : to be directed once boarding removed and window can be inspected	replace 10 no diamond panes; 10 no square panes	
			New leaded glazing L40/300: opaque glass	
			ease,adjust & refurbish sliding section & hopper; replace cord for hopper; repaint black gloss	
		**bars	supply & install 1 no support bar	
	ANSEPT EAST WINDOW ROSE OVER 2 NO LANCETS		Phase 2 work	

_	
1	
ST STEPHENS	

\$

GLAZING SCHEDULE

WINDOW NO	DESCRIPTION / CONDITION	GLAZING & FERRAMENTA	REPAIRS : Phase 2 :	TENDER
12.1	LANCET in 4 no sections	leaded : pale blue, yellow green and pink coloured glass; leaded within thin outer frame. lower & 3rd quarter are squares, 2nd & 4th quarter are diamonds, mostly intact	retain - clean & repair	
		some cracked some missing	replace 10 no diamond panes; 10 no square panes	1
			replace broken panes - New leaded glazing L40/300: opaque glass	
		3 no support bars	work on bars: mortar in securely	
12.2	LANCET in 4 no sections	leaded : pale blue, yellow green and pink coloured glass; leaded within thin outer frame. lower & 3rd quarter are squares, 2nd & 4th quarter are diamonds, mostly intact	retain - clean & repair	
		some cracked some missing	replace 10 no diamond panes; 10 no square panes	
			New leaded glazing L40/300: opaque glass	
		3 no support bars	work on bars: mortar in securely	
12.3	ROSE-CINQUEFOIL	leaded : pale coloured glass as above, in squares with border. all intact	retain - clean	
		with central horizontal support bar	work on bars: mortar in securely	
12.4-8	SEMICIRCLES (5 no)	leaded : pale coloured glass, all intact	retain - clean	
APSE NO	RTH ELEVATION			
WG13	COMPOSITE LANCET :	roses generally ok. stained glass lancet holed	Phase 2 work	
	Designer/maker Clayton & Bell 1869; EH neg ref nos 9, 11		retain - clean & repair as below	-
13.1	LANCET	stained glass : 4 figues. some bits missing in 2nd lower section. "i will lovecrown of life"	glue opaque glass shapes over missing sections; glue glass to internal face of lead cames	
		Inscription : 'Right dear in the sight of the Lord is the death of his saints'	New leaded glazing L40/300: opaque glass	
		with 5 no support bars	work on bars: mortar in securely	
13.2-6	ROSE QUATREFOIL	stained glass : all intact but fragile	clean	
13.7, .8, .9	ROSE TREFOILS (3 no)	stained glass :dark blue centre, red stained and plain etched foils	clean	
	RTH EAST ELEVATION			
WG14	COMPOSITE LANCET :		Phase 2 work	
	Designer/maker Clayton & Bell 1869; EH neg ref nos 8, 4		retain - clean & repair as below	

GLAZING SCHEDULE

Jan 2007

,

	W DESCRIPTION / CONDITION	GLAZING & FERRAMENTA	REPAIRS : Phase 2 :	TENDER
14.1	LANCET	stained glass : 4 figures; Christ & 3 possibly apostles; lowest section holed in centre	glue opaque glass shapes over missing sections; glue glass to internal face of lead cames	
		inscription : ' And to my God and your God'		
		with 5 no support bars	work on bars: mortar in securely	
14.2	LANCET	stained glass : Ih border on 3 lower 6ths damaged. centre 2 & 3 damaged. 2 figs shown	glue opaque glass shapes over missing sections; glue glass to internal face of lead cames	
		inscription : 'I ascend unto my father'	New leaded glazing L40/300: opaque glass	
		with 5 no support bars	work on bars: mortar in securely	
14.3	ROSE QUATREFOIL	stained glass : eagle in centre. all sound	clean	
14.4	ROSE TREFOIL	stained glass : all sound; angels?	clean	
14.5	ROSE TREFOIL	stained glass : all sound; angels?	clean	
14.6	TREFOIL	stained glass : all intact	clean	
14.7	TREFOIL	stained glass : all intact	clean	
APSE EA	AST ELEVATION			
WG15	COMPOSITE LANCET :	stained glass	Phase 2 work	
	Designer/maker Clayton & Bell 1869; EH neg ref nos 7,4 Window presented by Alfred		retain - clean & repair as below	
	Bell, who served on the appeal committee			
15.1	LANCET	stained glass : only top 2 sections intact.	retain & protect stained glass in place	
		partly covered with timber frame and mesh	carefully remove frame & mesh to prepare for repairs	
		with 4 no support bars lowest 5th missing	install new bar & remortar in bars securely	
		existing glazing; remove remaining sections of lead cames in lower section and prepare for new sheet glazing	retain - clean & minor repairs to upper section; make 2 no new panels for lower section in sheets of coloured glass	
			New sheet glazing L40/202: opaque glass	
15.2	LANCET	all glazing gone	silicon joint glass	
		partly covered with timber frame and mesh	carefully remove frame &	
		1	mesh to prepare for repairs	
		with 5 no support bars	remortar in bars securely	

ST STE	PHENS	GLAZING SCHEDULE		Jan 200
WINDOW	DESCRIPTION / CONDITION	GLAZING & FERRAMENTA	REPAIRS : Phase 2 :	TENDER
NO.				
		remove remaining sections of lead cames in	retain - clean & minor repairs	
		lower section and prepare for new sheet glazing	to upper section; make 3 no new panels for lower section	
			in sheets of coloured glass	
			In sheets of coloured glass	
			New sheet glazing L40/202:	
			opaque glass	
			silicon joint glass	
15.3	ROSE	all glazing gone	make new panel in plain	
			coloured glass	
		remove remaining sections of lead cames in	make 1 no new panel in single	
		lower section and prepare for new sheet glazing	sheet of coloured glass	
			New sheet glazing L40/202:	
			opaque glass	
		no support bar	install new bar & remortar in	
			bars securely	
15.49	SIXFOIL	stained glass : all intact	clean	
15.10	TREFOIL	stained glass : all intact	clean	
15.11	TREFOIL	stained glass : all intact	clean	
]
APSE SO	UTH WEST ELEVATION			-
WG16	COMPOSITE LANCET :	stained glass	Phase 2 work	
	Designer/maker Clayton & Bell		retain - clean & repair as below	
	1869; EH neg ref nos 4,5,6			
				ł
16.1	LANCET	stained glass : 3 figures: Christ, Mary & angel; small		}
		holes in lower 3 sections of glazing.	over missing sections; glue	
			glass to internal face of lead cames	
		inscription : 'he were dead yet shall he (live)'	New leaded glazing L40/300:	
			opaque glass	
		with 5 no support bars	remortar in bars securely	
16.2	LANCET	stained glass : 5 figures. small holes in 1st and 3rd	glue opaque glass shapes	
		sections of glazing.	over missing sections; glue	
			glass to internal face of lead	
			cames	
		inscription : 'He that believeth in the thought'	New leaded glazing L40/300:	
			opaque glass	
		with 5 no support bars	remortar in bars securely	
16.3	ROSE QUATREFOIL	glazing missing	make new panels in opaque	
			coloured glass	
		remove remaining sections of lead cames in	make 1 no new panel in single	
		section and prepare for new sheet glazing	sheets of coloured glass	
				ł
			centre circular pane with 4 no	
			semi circular petals	
			New sheet glazing L40/202:]
		no support bar	New sheet glazing L40/202:	
16.4	ROSE TREFOIL	no support bar stained glass : all intact	New sheet glazing L40/202:	

			Cidan	
APSE SC	UTH ELEVATION			
WG17	COMPOSITE LANCET :	stained glass	Phase 2 work	<u> </u>
	Designer/maker Clayton & Bell 1869; EH neg ref nos 5, 10		retain - clean & repair as below	<u>.</u>
17.1	LANCET	stained glass : in top 6th and partial in 5/6 section; lower 5/6ths	retain - clean & minor repairs to upper panels; make new panels for lower sections in coloured glass	
		top section of stained glass	install opaque sections of glass into missing parts to	
			New leaded glazing L40/300: opaque glass	
		partly covered with timber frame and glass	silicon joint glass carefully remove frame, glass & mesh to prepare for repairs	
		remove remaining sections of lead cames in lower section and prepare for new sheet glazing	retain - clean & minor repairs to upper section; make 3 no new panels for lower section in sheets of coloured glass	
17.26		with 5 no support bars stained glass : all intact	New sheet glazing L40/202: opaque glass silicon joint glass remortar in bars securely	
13.7, 8, 9		stained glass : all good mainly red stained and plain etched glass	clean clean	
	STAIR TURRET (EAST END)			
WG18	LANCET	leaded :	Phase 2 work	
		glass missing remove remaining sections of lead cames in lower section and prepare for new leaded glazing	all new cames & coloured glazing; square panes with border	
		one horizontal bar - centre	New leaded glazing L40/300: opaque glass remortar in bars securely	
WG19	LANCET	leaded :	Phase 2 work	
		stained glass : very damaged remove remaining sections of lead cames in lower section and prepare for new leaded glazing	all new cames & coloured glazing; square panes with border	

NO 16.6

16.7

WINDOW DESCRIPTION / CONDITION

TREFOIL

TREFOIL

GLAZING SCHEDULE

GLAZING & FERRAMENTA

stained glass : all intact

stained glass : all intact

Jan 2007

TENDER

REPAIRS : Phase 2 :

clean

clean

border

4

glazing

WINDOW NO	DESCRIPTION / CONDITION	GLAZING & FERRAMENTA	REPAIRS : Phase 2 :	TENDER
···· · ·			New leaded glazing L40/300:	- <u>†</u>
			opaque glass	
		one horizontal bar - centre	remortar in bars securely	
WG20	LANCET	leaded :	Phase 2 work	
		stained glass : very damaged		
		remove remaining sections of lead cames in	all new cames & coloured	
		lower section and prepare for new leaded glazing	glazing; square panes with border	
			New leaded glazing L40/300: opaque glass	
		one horizontal bar - centre	remortar in bars securely	
WG21	LANCET	leaded :	Phase 2 work	
		stained glass : very damaged	- 1935 2 WUR	· · ·
		remove remaining sections of lead cames in lower section and prepare for new leaded glazing	all new cames & coloured glazing; square panes with border	
			New leaded glazing L40/300: opaque glass	
		one horizontal bar - centre	remortar in bars securely	
WG22	RANSEPT EAST WINDOW ROSE OVER 2 NO LANCETS:		Phase 2 work	
	by Clayton & Bell 1874; thought to be a memorial window to Teulon			
			retain - clean whole window& repair as below	
22.1	LANCET	stained glass : top & bottom quarters have some stained glass remaining. centre gone.		
	2	partly covered with timber frame and mesh	carefully remove frame & mesh to prepare for repairs	
		existing glazing; remove remaining sections of lead cames in centre and prepare for new leaded glazing	repairs to existing panels; retain top & bottom stained glass in place; install new large pane of coloured glass in missing section	
			mortar glass into rebate in stone surround	
			silicon joint glass	
			New glazing L40/202: opaque coloured glass	
		with 2 no support bars; poss 4	mortar ends of bars securely into reveals	
22.2	LANCET	stained glass : top quarter stained glass, rest missing.		
		partly covered with timber frame and mesh	carefully remove frame & mesh to prepare for repairs	

GLAZING SCHEDULE

Jan 2007

.

WINDOW NO	DESCRIPTION / CONDITION	GLAZING & FERRAMENTA	REPAIRS : Phase 2 :	TENDER
		existing glazing; remove remaining sections of lead cames in centre and prepare for new leaded glazing	repairs to existing panels; retain top stained glass in place; install new large pane of coloured glass in missing section	
			mortar glass into rebate in stone surround	
			silicon joint glass New glazing L40/300: opaque coloured glass	
		with 3 no support bars; poss 4	remortar ends of bars securely into reveals	
22.3	ROSE	glass missing	make new panel in coloured glass	
		existing glazing; remove remaining sections of lead cames in centre and prepare for new glazing	mortar glass into rebate in stone surround	
			New glazing L40/300: opaque coloured glass	
22.4	ROSE	stained glass - angel- intact	retain - clean	
22.5	ROSE	stained glass - figure with quill feather(?)- intact	retain - clean	ſ
22.6	ROSE	glass missing	make new panel in coloured glass	
		existing glazing; remove remaining sections of lead cames in centre and prepare for new glazing	mortar glass into rebate in stone surround	
22.7	ROSE	glass missing	make new panel in coloured glass	:
		existing glazing; remove remaining sections of lead cames in centre and prepare for new glazing	mortar glass into rebate in stone surround	
22.8	ROSE	glass missing	make new panel in coloured glass	
		existing glazing; remove remaining sections of lead cames in centre and prepare for new glazing	mortar glass into rebate in stone surround	
22.9	ROSE	glass missing	make new panel in coloured glass	
		existing glazing; remove remaining sections of lead cames in centre and prepare for new glazing	mortar glass into rebate in stone surround	
22.1015	SEMICIRCLES (6 no)	all intact - stained glass	retain - clean	:
	ANSEPT SOUTH WINDOW			
WG23	LANCET WITH ROSE & FOILS OVER	stained glass	Phase 2 work	
	Designed/made by Clayton & Bell 1893		retain - clean whole window; repair as below	<u></u>
23.1	LANCET	stained glass : 'lydia' inscription. female figure top, 3 male figs below		

GLAZING SCHEDULE

WINDOW NO	DESCRIPTION / CONDITION	GLAZING & FERRAMENTA	REPAIRS : Phase 2 :	TENDER
		lower 2 portions partially damaged	glue coloured glass shapes over missing sections; glue glass to internal face of lead cames	
			New glazing L40/300: opaque coloured glass	
		with 4 no support bars	remortar ends of bars securely into reveals	
23.2	LANCET	stained glass : female figure		
		lower section missing replaced with clear glass. partly covered with timber frame and mesh	carefully remove frame & mesh to prepare for repairs	
		existing glazing; remove remaining sections of lead cames in lowest sections and prepare for new sheet glazing	repairs to existing panels; retain top stained glass in place; install new large panes of coloured glass in missing lower sections	
			mortar glass into rebate in stone surround	
			silicon joint glass	
			New glazing L40/300: opaque coloured glass	
		with 2 no support bars in upper section; 2 no missing	install 2 no new support bars; remortar ends of bars securely into reveals	
23.3	LANCET	stained glass : mate figure. taller lancet in centre.top section good		
		lower portion replaced with clear glass. partly covered with timber frame and mesh	carefully remove frame & mesh to prepare for repairs	
		existing glazing; remove remaining sections of lead cames in lowest sections and prepare for new sheet glazing	repairs to prepare for repairs repairs to existing panels; retain top stained glass in place; install new large panes of coloured glass in missing lower sections	
			mortar glass into rebate in stone surround	
			silicon joint glass New glazing L40/300: opaque	
		with 3 no support bars; 1 no missing	coloured glass install 1 no new support bars; remortar ends of bars securely into reveals	
23.4	LANCET	stained glass : female figure,	retain & protect	
		panes missing at base	glue coloured glass shapes over missing sections; glue glass to internal face of lead cames	
			New glazing L40/300: opaque coloured glass	

GLAZING SCHEDULE

Jan 2007

,

WINDOW NO	DESCRIPTION / CONDITION	GLAZING & FERRAMENTA	REPAIRS : Phase 2 :	TENDER
		lower section missing replaced with clear glass.	replace with large sheet glass	
		partly covered with timber frame and mesh	carefully remove frame & mesh to prepare for repairs	
		existing glazing; remove remaining sections of lead cames in lowest sections and prepare for new sheet glazing	repairs to existing panels; retain top stained glass in place; install new large panes of coloured glass in missing lower sections	
			mortar glass into rebate in stone surround	
			silicon joint glass New glazing L40/202: opaque coloured glass	
		with 3 no support bars in upper section; 1 no missing	install 1 no new support bars; remortar ends of bars securely into reveals	
23.5	LANCET	stained glass : female figure	retain & protect	
		lower section missing replaced with clear glass.	replace with large sheet glass	
		partly covered with timber frame and mesh	carefully remove frame & mesh to prepare for repairs	
		existing glazing; remove remaining sections of lead cames in lowest sections and prepare for new sheet glazing	repairs to existing panels; retain top stained glass in place; install new large panes of coloured glass in missing lower sections	
			mortar glass into rebate in stone surround	
			silicon joint glass New glazing L40/202: opaque coloured glass	
		with 3 no support bars in upper section; 1 no missing	install 1 no new support bars; remortar ends of bars securely into reveals	
23.6-11	ROSE-CINQFOIL	stained glass : 23.6 missing. 7-11 in good condition, green/orange border with etched leaf pattern inside, each having 4 sections and centre orange.	retain - clean & repair following closer inspection of window	
23.6	centre circle	23.6 poss opening light; missing glazing provisional allowance	remake circular opening light with steel frame and casement hinged horizontally	
			glaze in single sheet of coloured glass	
			New glazing L40/202: opaque coloured glass	

ST STEPHENS	
-------------	--

•

.

GLAZING SCHEDULE

WINDOW NO	DESCRIPTION / CONDITION	N GLAZING & FERRAMENTA	REPAIRS : Phase 2 :	TENDER
23.12	ROSE-TREFOIL	stained glass : latin words	clean	
23.13-18	ROSE-CINQFOIL	stained glass : 23.13 missing, 14-18 all in good condition. green/orange border with etched leaf pattern inside, each having 4 sections and centre orange.	retain - clean & repair following closer inspection of window	
23.13	centre circle	23.13 poss opening light; missing glazing provisional allowance	remake circular opening light with steel frame and casement hinged horizontally	
			glaze in single sheet of coloured glass	
			New glazing L40/202: opaque coloured glass	
23.19-34 23.20	ROSE-DECAFOIL	stained glass : 5 angels; 10 petals; centre 'ihl' cracked pane	clean glue coloured glass shape over missing section; glue glass to internal face of lead cames	
			New glazing L40/300: opaque coloured glass	
23.35	ROSE	stained glass : letter 'Q'	clean	
	ROSE	stained glass : letter 'A'	clean	
NG 24 - 28	SOUTH AISLE WINDOWS -	REFURBISHED IN PHASE 1	NO WORK IN PHASE 2	
SOUTH PO				
SOUTH EL NG29	ROSE WINDOW		Phase 2 work	
29.1	ROSE QUATREFOIL	leaded : with large clear pane inserted in centre. all pale coloured glass	retain - clean Remake whole panel reusing small panes; remake with 4 no square panes in centre (as W1.5): L40/300	
29.26	SEMI-CIRCLES	Leaded : intact	retain - clean	
	EVATION STAIR TURRET (ST	AIR TOWER TO WEST GALLERY)		
	LANCET		Phase 2 work	
	. =	boarded over	remove boarding	
		assumed no glazing	all new cames & glazing; square panes with border	

GLAZING SCHEDULE

,

windo w No	DESCRIPTION / CONDITION	GLAZING & FERRAMENTA	REPAIRS : Phase 2 :	TENDER
		existing glazing; remove remaining sections of lead cames in centre and prepare for new glazing	New glazing L40/300: opaque coloured glass	
		assumed no support bar	supply & install 1 no support bar	
WG33	LANCET		Phase 2 work	
		leaded : border and sq coloured glass. 2 squares broken	retain - clean	
	1	with 1 no support bar	2 no replacement square panes	
			New glazing L40/300: opaque coloured glass	
WG34	LANCET		Phase 2 work	
		leaded : border & sq panes coloured glass, sound.	retain - clean	
		with 1 no support bar		
	I LLERY STAIR TURRET: TOP			
W1.34	CIRCLES WITH SIDE PETALS		Phase 2 work	
		6 panels of centre circles and quatrefoils		
		no damage	retain & clean	
WEST GA	DOR LEVEL WINDOWS			
WEST GAI W1.1	LLERY WEST ELEVATION 3 NO LANCETS	no damage	Phase 2 work	
WEST GA	LLERY WEST ELEVATION			
WEST GAI W1.1	LLERY WEST ELEVATION 3 NO LANCETS	no damage leaded : coloured glass, border, diamonds over	Phase 2 work Phase 2 work retain - clean & repair replace 3 no diamond panes	
WEST GA W1.1 1.1	LLERY WEST ELEVATION 3 NO LANCETS	no damage leaded : coloured glass, border, diamonds over squares.(12)	Phase 2 work retain - clean & repair	
WEST GA W1.1 1.1	LLERY WEST ELEVATION 3 NO LANCETS	no damage leaded : coloured glass, border, diamonds over squares.(12)	Phase 2 work retain - clean & repair replace 3 no diamond panes replace broken panes - New leaded glazing L40/300:	
WEST GA W1.1 1.1	LLERY WEST ELEVATION 3 NO LANCETS	no damage leaded : coloured glass, border, diamonds over squares.(12) 2 missing diamonds	Phase 2 work retain - clean & repair replace 3 no diamond panes replace broken panes - New leaded glazing L40/300: opaque glass supply & install 1 no support	
WEST GA W1.1 1.1 1.1.1	LLERY WEST ELEVATION 3 NO LANCETS	no damage leaded : coloured glass, border, diamonds over squares.(12) 2 missing diamonds 2 no support bars; 1 no missing	Phase 2 work retain - clean & repair replace 3 no diamond panes replace broken panes - New leaded glazing L40/300: opaque glass supply & install 1 no support bar ease,adjust & refurbish sliding section & hopper; replace cord	
WEST GA W1.1 1.1 1.1.1 1.1.2 1.1.2 1.1.3 W1.2	3 NO LANCETS	no damage leaded : coloured glass, border, diamonds over squares.(12) 2 missing diamonds 2 no support bars; 1 no missing sliding section with internal hopper 2 no support bars	Phase 2 work retain - clean & repair replace 3 no diamond panes replace broken panes - New leaded glazing L40/300: opaque glass supply & install 1 no support bar ease,adjust & refurbish sliding section & hopper; replace cord	
WEST GA W1.1 1.1 1.1.1 1.1.2 1.1.2	LLERY WEST ELEVATION 3 NO LANCETS LANCET	no damage leaded : coloured glass, border, diamonds over squares.(12) 2 missing diamonds 2 no support bars; 1 no missing sliding section with internal hopper	Phase 2 work retain - clean & repair replace 3 no diamond panes replace broken panes - New leaded glazing L40/300: opaque glass supply & install 1 no support bar ease,adjust & refurbish sliding section & hopper; replace cord for hopper; repaint black gloss	
WEST GAI W1.1 1.1 1.1.1 1.1.2 1.1.2 1.1.3 W1.2	3 NO LANCETS	no damage leaded : coloured glass, border, diamonds over squares.(12) 2 missing diamonds 2 no support bars; 1 no missing sliding section with internal hopper 2 no support bars leaded : coloured glass, border, diamonds over	Phase 2 work retain - clean & repair replace 3 no diamond panes replace broken panes - New leaded glazing L40/300: opaque glass supply & install 1 no support bar ease,adjust & refurbish sliding section & hopper; replace cord for hopper; repaint black gloss Phase 2 work	

WINDOW NO	DESCRIPTION / CONDITION	GLAZING & FERRAMENTA	REPAIRS : Phase 2 :	TENDER
			replace broken panes - New leaded glazing L40/300: opaque glass	
		sliding section with internal hopper	ease,adjust & refurbish sliding section & hopper; replace cord for hopper; repaint black gloss	
1.2.3		2 no support bars		
		broken square panes	replace 6 no square panes replace broken panes - New leaded glazing L40/300: opaque glass	2
W1.3	3 NO LANCETS		Phase 2 work	
1.3	LANCET	leaded : coloured glass, border, 2 panes diamonds over squares.(12)	retain - clean & repair	
1.3.1		2 no support bars		
		broken square panes	replace 6 no square panes replace broken panes - New leaded glazing L40/300: opaque glass	
1.3.2		broken square panes	replace 4 no square panes replace broken panes - New leaded glazing L40/300: opaque glass	
		sliding section with internal hopper	ease,adjust & refurbish sliding section & hopper; replace cord for hopper; repaint black gloss	
1.3.3		2 no support bars		
		broken diamond panes	replace 3 no diamond panes replace broken panes - New leaded glazing L40/300: opaque glass	
NEET CAL				
	LERY NORTH ELEVATION 2 NO LANCETS		Phase 2 work	
	LANCET	leaded : coloured glass squares with border. 16 squares below diamonds, top section separate. leading bowed	retain - clean & repair	
		most squares missing	remake lower pane with square panes	
		some diamonds broken	replace 2 no diamond panes replace broken panes - New leaded glazing L40/300: opaque glass	
		with 2 no support bars		

GLAZING SCHEDULE

Jan 2007

WINDOW	DESCRIPTION / CONDITION	GLAZING & FERRAMENTA	REPAIRS : Phase 2 :	TENDER
NO				
4.2	LANCET	leaded : coloured glass squares with border. 16 squares below diamonds,	retain - clean & repair	
		most squares missing	replace 16 no square panes	
		some diamonds broken	replace 8 no diamond panes	
			replace broken panes - New	
			leaded glazing L40/300:	
			opaque glass	
		with 2 no support bars missing	supply & install 1 no support bar	
		boarded up internally	remove boarding and make	
			good	
	LLERY SOUTH ELEVATION			
W1.33	LANCET		Phase 2 work	
		leaded : opaque glass; border with diamonds over squares;	retain - clean & repair	
		glazing bowed. missing diamonds and broken	remake glazing for whole	
		squares	window	
			New leaded glazing L40/300: opaque glass	
		with hopper & sliding window	ease,adjust & refurbish sliding	
			section & hopper; replace cord	
			for hopper; repaint black gloss	
NORTH PO	 DRCH			
	EVATION			
W1.5	ROSE WINDOW (over doors)		Phase 2 work	
5.1	ROSE QUATREFOIL	leaded : opaque glass; square panes	retain - clean	
5.2-5.6	PETALS	leaded : opaque glass; border with 3 panes	retain - clean	
NORTH NA	 AVE CLERESTOREY WINDOWS	5		
W1.6	COMPOSITE LANCET		Phase 2 work	
		· · · · · · · · · · · · · · · · · · ·		· · · · · · · · · · · · · · · · · · ·
6.1	LANCET	leaded : opaque glass, 1 panel of border with	carefully remove whole pane;	
		diamonds between square panes; buckled glazing	clean & reconstruct damaged panel of border, diamonds &	
			squares; reset in place	
			New glazing L40/300: opaque	
			coloured glass	
		with 2 no support bars		

GLAZING SCHEDULE

WINDOW NO	DESCRIPTION / CONDITION	GLAZING & FERRAMENTA	REPAIRS : Phase 2 :	TENDER
6.2	LANCET	leaded : opaque glass, 1 panel of border with diamonds between square panes	carefully remove whole pane; clean & reconstruct damaged panel of border, diamonds & squares; reset in place	
			New glazing L40/300: opaque coloured glass	
		with 2 no support bars		
6.3	LANCET	leaded : opaque glass, 1 panel of border with diarnonds between square panes	carefully remove whole pane; clean & reconstruct damaged panel of border, diamonds & squares; reset in place	
			New glazing L40/300: opaque coloured glass	
		with 2 no support bars		
6.4	LANCET	leaded : opaque glass, 1 panel of border with diamonds between square panes	carefully remove whole pane; clean & reconstruct damaged panel of border, diamonds & squares; reset in place	
		with 2 per support here	New glazing L40/300: opaque coloured glass	
6.5	ROSE TREFOIL	with 2 no support bars leaded : opaque glass; square panes	clean	
6.6	ROSE QUATREFOIL	leaded : opaque glass; diamond panes with diagonal support bar	ciean	
6.7	ROSE TREFOIL	leaded : opaque glass; square panes	clean	
6.8-9	SEGMENTS	leaded: opaque glass; shaped panes	ciean	
W1.7	COMPOSITE LANCET		Phase 2 work	
7.1	LANCET	leaded : opaque glass, 1 panel of border with diamonds between square panes	carefully remove whole pane; clean & reconstruct damaged panel of border, diamonds & squares; reset in place	
			New glazing L40/300: opaque coloured glass	
7.0		with 2 no support bars		
7.2	LANCET	leaded : opaque glass, 1 panel of border with diamonds between square panes	carefully remove whole pane; clean & reconstruct damaged panel of border, diamonds & squares; reset in place	
			New glazing L40/300: opaque coloured glass	
		with 2 no support bars with hopper	refurbish hopper & vent; add cords to operate	Į

GLAZING SCHEDULE

Jan 2007

.

WINDOW NO	DESCRIPTION / CONDITION	GLAZING & FERRAMENTA	REPAIRS : Phase 2 :	TENDER
7.3	LANCET	leaded : opaque glass, 1 panel of border with diamonds between square panes	carefully remove whole pane; clean & reconstruct damaged panel of border, diamonds & squares; reset in place	
		with 2 pa support have	New glazing L40/300: opaque coloured glass	
7.4	LANCET	with 2 no support bars leaded : opaque glass, 1 panel of border with diamonds between square panes	carefully remove whole pane; clean & reconstruct damaged panel of border, diamonds & squares; reset in place	
			New glazing L40/300: opaque coloured glass	
		with 2 no support bars		\$
7.5	ROSE TREFOIL	leaded : opaque glass; diamond panes	clean	
.6	ROSE CINQUEFOIL	leaded : opaque glass; square panes	clean	
7		with 1 no support bar		
.7	ROSE TREFOIL	leaded : opaque glass; diamond panes	clean	
.8-9	SEGMENTS	leaded: opaque glass; shaped panes	clean	
V1.8	COMPOSITE LANCET WINDOW			
			Phase 2 work	
.1	LANCET	leaded : opaque glass, 1 panel of border with diamonds between square panes	retain - clean & minor repairs	
.2	LANCET	with 2 no support bars leaded : opaque glass, 1 panel of border with diamonds between square panes	retain - clean & minor repairs	
.3	LANCET	with 2 no support bars leaded : opaque glass, 1 panel of border with diamonds between square panes	retain - clean & minor repairs	
.4	LANCET	with 2 no support bars leaded : opaque glass, 1 panel of border with diamonds between square panes	retain - clean & minor repairs	
		with 2 no support bars		
5	ROSE TREFOIL	leaded : opaque glass; square panes	retain - clean & minor repairs	
6	ROSE QUATREFOIL	leaded : opaque glass; diamond panes	retain - clean & minor repairs	
		with 1 no diagonal bar		
.7	ROSE TREFOIL	leaded : opaque glass; square panes	retain - clean & minor repairs	
.8- 9	SEGMENTS	leaded: opaque glass; shaped panes	retain - clean & minor repairs	
	COMPOSITE LANCET WINDOW		Phase 2 work	
.1	LANCET	leaded : opaque glass, 1 panel of border with diamonds between square panes	retain - clean & minor repairs	- <u>12 - 11</u>

WINDOW NO	DESCRIPTION / CONDITION	GLAZING & FERRAMENTA	REPAIRS : Phase 2 :	TENDER
		with 2 no support bars		
).2	LANCET	leaded : opaque glass, 1 panel of border with diamonds between square panes	clean	
		with 2 no support bars with hopper	refurbish hopper & vent; add cords to operate	
).3	LANCET	leaded : opaque glass, 1 panel of border with diamonds between square panes	clean	
		with 2 no support bars		
9.4	LANCET	leaded : opaque glass, 1 panel of border with diamonds between square panes	clean	
		with 2 no support bars		
9.5	ROSE TREFOIL	leaded : opaque glass; diamond panes	clean	
9.6	ROSE CINQUEFOIL	leaded : opaque glass; square panes with 1 no support bar	clean	
9.7	ROSE TREFOIL	leaded : opaque glass; diamond panes	clean	
9.8-9	SEGMENTS	leaded: opaque glass; shaped panes	clean	
W1.10	COMPOSITE LANCET		Phase 2 work	
			retain, protect & clean whole	
			window	
10.1	LANCET	leaded : opaque glass, 1 panel of border with diamonds between square panes	clean	
		with 2 no support bars		
10.2	LANCET	leaded : opaque glass, 1 panel of border with diamonds between square panes	clean	
		with 2 no support bars		
10.3	LANCET	leaded : opaque glass, 1 panel of border with diamonds between square panes	clean	
		with 2 no support bars		
10.4	LANCET	leaded : opaque glass, 1 panel of border with diamonds between square panes	clean	
		with 2 no support bars		
10.5	ROSE TREFOIL	leaded : opaque glass; square panes	clean	
10.6	ROSE QUATREFOIL	leaded : opaque glass; diamond panes with diagonal support bar	clean	
10.7	ROSE TREFOIL	leaded : opaque glass; square panes	clean	
10.8-9	SEGMENTS	leaded: opaque glass; shaped panes	clean	
N1.11	COMPOSITE LANCET & ROSE WINDOW		Phase 2 work	
			retain, protect & clean whole	· · · · ·
			window	
11.1	LANCET	leaded : opaque glass; 1 panel of border with diamonds, squares, diamonds, squares; buckled at base	remake buckled sections	
		with 3 no support bars		

GLAZING SCHEDULE

WINDOW	DESCRIPTION / CONDITION	GLAZING & FERRAMENTA	REPAIRS : Phase 2 :	TENDER
0				
11.2		leaded : opaque glass; 1 panel of border with	clean	
		diamonds, squares, diamonds, squares		
		with 3 no support bars		1
11.3	LANCET	leaded : opaque glass; 1 panel of border with	clean	
		diamonds, squares, diamonds, squares		
11.4	ROSE	with 3 no support bars		
11.4		leaded : opaque glass; border with square panes with horizontal support bar	clean	
11.5-10	PETALS	leaded : opaque glass; border with square panes	clean	
11.11,	TREFOILS	leaded : opaque glass; border and circles	clean	
11.12		· · · · · · · · · · · · · · · · · · ·		1
11.13-18	SEGMENTS	leaded: opaque glass; shaped panes	clean	
W1.12	LANCETS		Phase 2 work	
2.1	LANCET	leaded : opaque glass; border & square panes	retain & clean whole window	┨──────
		with 1 no support bar		1
12.2	LANCET	leaded : opaque glass; border & square panes	retain & clean whole window	
				1
		with 1 no support bar		
W1.13	SCULPTURE	ino glass!	Phase 2 work	
	SCULPTURE			<u></u>
				1
W1.14	ROSE WINDOW	Stained glass	Phase 2 work	
	Designed either by H Holiday or		retain & clean whole window	
	Thomas Boddington			
	Made by Heaton Butler & Bayne 1870			
	1010			
14.1	ROSE SIXFOIL	stained glass figure in centre of rose with 6 leaves;		
		figure with organ; faces in 5 leaves; 1 leaf damaged		
				1
		missing section	glue coloured glass shape	
			over missing section; glue	
			glass to internal face of lead	
	ļ		New glazing L40/300: opaque coloured glass	ļ
		with 1 no horizontal support bar	<i>g,===</i>	1
14.2	PETAL SHAPE	stained glass figure of musician	clean	
14.3	PETAL SHAPE	stained glass figure of musician	clean	
14.4	PETAL SHAPE	stained glass figure of musician	clean	1
		missing section	glue coloured glass shape	
			over missing section; glue	
	ļ		glass to internal face of lead	1
			cames	}
			New glazing L40/300: opaque	
	1	1	coloured glass	
14.5	PETAL SHAPE	stained glass figure of musician		

WINDOW NO	DESCRIPTION / CONDITION	GLAZING & FERRAMENTA	REPAIRS : Phase 2 :	TENDER
		missing section	glue coloured glass shape	
			over missing section; glue	
			glass to internal face of lead cames	
			New glazing L40/300: opaque coloured glass	
14.6	PETAL SHAPE	stained glass figure of musician	clean	
14.7	PETAL SHAPE	stained glass figure of musician	clean	
14.8-13	CIRCLES (5 no)	Stained glass ; border with centre	clean	
	,			
SOUTH N	 AVE CLERESTOREY WINDOWS	3		
W1.26	COMPOSITE LANCET & ROSE			1
	WINDOW		Phase 2 work	
	Designer/maker E Priest,			
	Haverstock Hill about 1905: EH			
	neg ref no 27		retain & clean whole window	
26.1	LANCET	stained glass st peter		
		with 5 no support bars		
26.2	LANCET	stained glass st john		
		with 4 no support bars		
26.3	LANCET	stained glass st paul		
		with 5 no support bars		
26.4	ROSE CIRCLE	stained glass 'true godliness'		
26.5	PETAL	stained glass 'holy fear'		
26.6	PETAL	stained glass 'counsel'		
26.7	PETAL	stained glass 'knowledge'		
26.8	PETAL	stained glass 'wisdom'		
26.9	PETAL	stained glass 'strength'		
26.10	PETAL	stained glass 'understanding'		
26.11-16	CIRCLES (6 no.)	stained glass: border with centre		
26.17	ROSE TREFOIL	stained glass		
26.18	ROSE TREFOIL	stained glass		
W1.27	LANCETS		Phase 2 work	
27.1	LANCET	leaded : opaque glass: 1 panel of border and		
L f. (square panes	retain & clean whole window	
		with 1 no support bar		
27.2	LANCET	leaded : opaque glass: 1 panel of border and		
		square panes	retain & clean whole window	
		with 1 no support bar		ĺ
N1.28	COMPOSITE LANCET			
	WINDOW		Phase 2 work	
			retain & clean whole window	
28.1	LANCET	leaded : opaque glass, 1 panel of border with		
		diamonds between square panes		1
		with 2 no support bars		Í

GLAZING SCHEDULE

WINDOW NO	DESCRIPTION / CONDITION	GLAZING & FERRAMENTA	REPAIRS : Phase 2 :	TENDER
28.2	LANCET	leaded : opaque glass, 1 panel of border with diamonds between square panes		
		with 2 no support bars & hopper vent	refurbish hopper & vent - ease	
			& adjust; add cords to operate	
28.3	LANCET	leaded : opaque glass, 1 panel of border with		
		diamonds between square panes		
28.4	LANCET	with 2 no support bars leaded : opaque glass, 1 panel of border with		
20,4		diamonds between square panes		
		with 2 no support bars		
28.5	ROSE QUATREFOIL	leaded : opaque glass; border with square panes with horizontal bar		
28.6	ROSE TREFOIL	leaded : opaque glass; border and diamond panes		
28.7	ROSE TREFOIL	leaded : opaque glass; border and diamond panes		
28.8/9	SEGMENTS	leaded : opaque glass; shaped panes		
W1,29	COMPOSITE LANCET		Phase 2 work	
			I Hase Z Work	
			retain & clean whole window	
29.1	LANCET	leaded : opaque glass, 1 panel of border with diamonds between square panes		
		with 2 no support bars		
29.2	LANCET	leaded : opaque glass, 1 panel of border with diamonds between square panes		
		with 2 no support bars		
29.3	LANCET	leaded : opaque glass, 1 panel of border with diamonds between square panes		
	Į	with 2 no support bars		
29.4	LANCET	leaded : opaque glass, 1 panel of border with diamonds between square panes		
		with 2 no support bars		
29.5	ROSE CINQUEFOIL	leaded : opaque glass; border and diamond panes with diagonal bar		
29.6	ROSE TREFOIL	leaded : opaque glass; border with square panes		
29.7	ROSE TREFOIL	leaded : opaque glass; border with square panes		
29.8/9	SEGMENTS	leaded : opaque glass; shaped panes		
N1.30	COMPOSITE LANCET			
	WINDOW		Phase 2 work	
30.1		landed : on an on a land of harder with	retain & clean whole window	
30.1	LANCET	leaded : opaque glass, 1 panel of border with diamonds between square panes		
		with 2 no support bars		
30.2	LANCET	leaded : opaque glass, 1 panel of border with diamonds between square panes		
		with 2 no support bars		
30.3	LANCET	leaded : opaque glass, 1 panel of border with diamonds between square panes		

٠

WINDOW NO	DESCRIPTION / CONDITION	GLAZING & FERRAMENTA	REPAIRS : Phase 2 :	TENDER
NU		with 2 no support bars; hopper vent	refurbish hopper & vent - ease	
			& adjust; add cords to operate	
30.4	LANCET	leaded : opaque glass, 1 panel of border with		
		diamonds between square panes		
		with 2 no support bars	remortar bars into reveals securely	
30.5	ROSE QUATREFOIL	leaded : opaque glass; border with square panes		
		with horizontal bar		
30.6	ROSE TREFOIL	leaded : opaque glass; border and diamond panes		
30.7	ROSE TREFOIL	leaded : opaque glass; border and diamond panes		
30.8/9	SEGMENTS	leaded : opaque glass; shaped panes		
W1.31	COMPOSITE LANCET			
	WINDOW		Phase 2 work	
31.1	LANCET	leaded : opaque glass, 1 panel of border with diamonds between square panes	carefully remove whole pane; clean & reconstruct damaged panel of border, diamonds & squares; reset in place	
			New glazing L40/300: opaque coloured glass	
		with 2 no support bars		
31.2	LANCET	leaded : opaque glass, 1 panel of border with diamonds between square panes (NB BORDER APPEARS MISSING ON LH SIDE)	carefully remove whole pane; clean & reconstruct damaged panel of border, diamonds & squares; reset in place	
			New glazing L40/300: opaque coloured glass	
		with 2 no support bars		
31.3	LANCET	leaded : opaque glass, 1 panel of border with diamonds between square panes (NB BORDER APPEARS MISSING ON LH SIDE)	carefully remove whole pane; clean & reconstruct damaged panel of border, diamonds & squares; reset in place	
			New glazing L40/300: opaque coloured glass	
	1	with 2 no support bars		
31.4	LANCET	leaded : opaque glass, 1 panel of border with diamonds between square panes	carefully remove whole pane; clean & reconstruct damaged panel of border, diamonds & squares; reset in place	
			New glazing L40/300: opaque coloured glass	
		with 2 no support bars		
31.5		leaded : opaque glass; border and diamond panes with diagonal bar	clean	
1.6	ROSE TREFOIL	leaded : opaque glass; border with square panes	clean	
31.7	ROSE TREFOIL	leaded : opaque glass; border with square panes	clean	

GLAZING SCHEDULE

.

W1.32 (V 32.1 L	SEGMENTS COMPOSITE LANCET WINDOW LANCET	leaded : opaque glass; shaped panes leaded : opaque glass, 1 panel of border with diamonds between square panes with 2 no support bars leaded : opaque glass, 1 panel of border with diamonds between square panes; buckled	clean Phase 2 work carefully remove whole pane; clean & reconstruct damaged panel of border, diamonds & squares; reset in place New glazing L40/300: opaque coloured glass	
32.1 L	LANCET	diamonds between square panes with 2 no support bars leaded : opaque glass, 1 panel of border with	carefully remove whole pane; clean & reconstruct damaged panel of border, diamonds & squares; reset in place New glazing L40/300: opaque coloured glass	
		diamonds between square panes with 2 no support bars leaded : opaque glass, 1 panel of border with	clean & reconstruct damaged panel of border, diamonds & squares; reset in place New glazing L40/300: opaque coloured glass	
32.2 L	LANCET	leaded : opaque glass, 1 panel of border with	coloured glass	
32.2 L	LANCET	leaded : opaque glass, 1 panel of border with	an a faithe an ann an that	1
			carefully remove whole pane; clean & reconstruct damaged panel of border, diamonds & squares; reset in place	
			New glazing L40/300: opaque coloured glass	
		with 2 no support bars & hopper vent	refurbish hopper & vent; add cords to operate	
32.3 L	LANCET	leaded : opaque glass, 1 panel of border with diamonds between square panes; buckled	carefully remove whole pane; clean & reconstruct damaged panel of border, diamonds & squares; reset in place	
		with 2 no support bars	New glazing L40/300: opaque coloured glass	
32.4 L	LANCET	leaded : opaque glass, 1 panel of border with diamonds between square panes	carefully remove whole pane; clean & reconstruct damaged panel of border, diamonds & squares; reset in place	-
			New glazing L40/300: opaque coloured glass]
32.5 F	ROSE QUATREFOIL	with 2 no support bars leaded : opaque glass; border with square panes; buckled	clean	
32.6 F	ROSE TREFOIL	with bar leaded : opaque glass; border and diamond panes	clean	
	ROSE TREFOIL	leaded : opaque glass; border and diamond panes	clean	
32.8/9 5	SEGMENTS	leaded : opaque glass; shaped panes	clean	
WEST ELEV	/ATION			
	ROSE WINDOW	stained glass	Phase 2 work	
	Glazing designed /made by			
	Clayton & Beil 1873: EH negative ref 30		retain & clean whole window	

GLAZING SCHEDULE

WINDOW NO	DESCRIPTION / CONDITION	GLAZING & FERRAMENTA	REPAIRS : Phase 2 :	TENDER
34.1	ROSE QUATREFOIL	centre. stained glass lamb		
34.2-11		2 figures in each segment. stained glass.		
		support bar runs through narrow section of each segment		
34.12-21	10 no roses	stained glass with metal support circle		
34.12-15				
34.12-15 34.16	4 no ROSE SIXFOILS SIXFOIL	stained glass landscapes		
34.10 34.17	SIXFOIL	figure of a heron figure of a lion		
	4 no SIXFOILS	each rose shows 2 figures		
	10 no tiny rose trefoils	cautitose shows 2 ligures		
54.22-51				
	 _EVATION HIGH LEVEL WINDO\	 WS		
W1 36	2 NO LANCETS		Phase 2 work	
36.1	LANCET	leaded :	no work	
36.2	LANCET	leaded :	no work	
END				
			TOTAL	
			GRAND TOTAL	
				Ì