TREE SURVEY REPORT

Location: 25 Adamson Road, NW3 3HT

Date and time surveyed: 1st December 2006 @ 0830

SUMMARY:

A survey of trees in adjoining properties and within close proximity (6 metres) of the proposed development at the rear of the above property was undertaken on the above date.

The survey describes their current condition and recommends suitable maintenance work where appropriate. It also makes recommendations to protect the trees where they are liable to be influenced by the proposed development and to, where achievable, conform to the requirements of BS 5837: 2005 Trees in Relation to Construction.

CONDITION SURVEY:

The trees were surveyed on the date and time shown above and the tree survey assessment information for each tree describing size, condition, surroundings and other factors, is shown in *Appendix A*.

SCHEDULE OF PHOTOGRAPHS:

Photo No.	Description
1	Tree T3 from rear of house
2	Close up of tree T3 from rear of house
3	Trees T1 and T2 from rear of house
4	Close up of tree T1 from rear of house

TREE PROTECTION RECOMMENDATIONS:

Reference Standards and Regulations

BS 5837:2005

Trees in relation to construction. Recommendations

ISBN: 0580464180

Cross References: BS 3998:1989*BS 4428:1989*BS EN ISO 11091:1999*PAS 100:2005*Town and Country Planning Act 1990*Forestry Act 1967*Wildlife and Countryside Act 1981*Conservation (Natural Habitats etc.) Regulations 1994 *Countryside and Rights of Way Act 2000*Hedgerows Regulations 1997*Construction (Design and Management) Regulations (CDM) 1994*Environment Act 1994*NHBC Standards. Chapter 4.2:1999*BS 8206-2:1992*

Project References:

• Drawing Ref: EX10 and EX11 Rev: A - Edgley Design

Tree Protection Measurements - as rec. by BS 5837

Tree Number	Tree Protection Zone (TPZ) Radius	Tree Protection Zone Area
T1	6.6 metres	136.8 sq. metres
T2	5.4 metres	91.6 sq. metres
T3	9 metres	254.3 sq. metres

Effect of the Project Proposals on Trees within the survey:

The Project proposals indicate that the maximum depth of excavation will be 4.0 metres and that this will take place at no closer than 3.5 metres radius from the centre point of the three trees concerned. This falls within the TPZ as indicated above. However, providing the recommendations for protection shown below and the recommended maintenance work described are undertaken, this will mitigate the likely effect of the proposed works on the trees concerned.

Protection Recommendations:

- No materials, substances, plant or machinery are to be stored within 3.5 metres
 radius of the 3 trees identified within the survey. A suitable storage area should
 be defined within the development site and away from the tree root zones
 concerned.
- 2. Ensure there is no excavation below 300mm within 3.0 metre from main stem of all trees identified within the survey.
- 3. Only a Qualified Arborist should prune any roots in excess of 75mm that are encountered during the operations. To prevent unnecessary damage to the roots it is advised that any excavations below 300mm are carried out very carefully or by hand if at all possible.
- 4. If the root mass encountered when excavation is carried out it would be prudent to install a 'root barrier' around the external wall of the building at a distance of 500-750mm to assist in preventing potential future structural damage from tree roots.
- Interim inspection of the trees for continuing protection during the building works would be advisable and should be undertaken by a suitably qualified Arboriculturalist.
- 6. Once the building work is complete the trees should be inspected to ensure no damage has occurred, that they have responded to the mitigation work and that they are still appropriately healthy for their age.

Richard Wassell MIHort. KewDip.Hort. MArb. NEBOSH level 3.

 Beyond this the trees should also be inspected every 4 years by a suitably qualified Arboriculturalist, with appropriate management recommendations made as required.

RECOMMENDATIONS FOR MAINTENANCE:

- Tree T1 Remove all deadwood, basal growth, and Ivy and epicormic growth throughout the crown. Reduce crown on the side nearest the excavation by a maximum of 750mm back to the nearest lateral and balance the remainder. Thin crown by 10%.
- 2. Tree T2 Remove all deadwood, basal growth, and Ivy and epicormic growth throughout the crown.
- 3. Tree T3 Remove all Ivy. Re-pollard back to original pollarding points at around 8 metres.
- 4. Every 4 years carry out professional Arboricultural inspection and recommend any maintenance / future management requirements.

This report and the opinions within it have been produced without prejudice by:

Richard Wassell

19. XII. MMVI

Appendix A

TREE SURVEY INFORMATION

LOCATION: 25 Adamson Road, NW3 3HT

DATE: 1st December 2006

TREE NUMBER 1	SPECIES	Tilia X europaea	
---------------	---------	------------------	--

TREE STATISTICS:

	DD11 FF0	DUDD /	DAIT	
AGE:Circa	DBH: 550mm	DNPB: n/a	DNT:	

HEIGHT CATEGORY:

<6	6/9	9/12	12/15	15/18
18/21	21/24	24/27	27/30	>30

CROWN SPREAD CATEGORY:

<6	6/9	9/12	12/15	15/18	
18/21	21/24	24/27	27/30	>30	

TREE CONDITION:

				_
VIGOUR:	GOOD	NORMAL	POOR	

DIEBACK %	None	PREVIOUS WORK	Yes – see comments @ end
EPICORMIC GROWTH %	20	BASAL GROWTH	Yes
STEM DAMAGE	No	WIND DAMAGE	No
BREAKOUT	No	CAVITIES	None visible
FUNGAL INFECTION	None visible	INSECT	No
ROOT DAMAGE	No	RAISED BED	No
SURROUNDING AREA	0.5 m from side brick boundary wall.	CO-DOMINANT STEMS	No

RISK EVALUATION:

SUBSTANTIAL MODE		MODERAT	E	TOLERABLE
DIRECT	No		SOIL PROFILE	Not undertaken
IN-DIRECT	No		TREE ROOT	Not undertaken

ANALYSIS

AMENITY VALUE:

HIGH	MEDIUM	LOW	
MATURE SPECIMEN	Yes	UNUSUAL / RARE TREE	No
WILDLIFE VALUE	Yes	NATIVE	No
LANDSCAPE VALUE	Some	STREETCENE	No
PROMINENT POSITION	No	PART OF GROUP / AVENUE	No

DBH = diameter @ 1.5 metres above ground level

DNPB = distance to nearest point of building

DNT = distance to nearest tree

TREE STATISTIC		0	DNPB: n	10	DNT:
AGE:Circa	DBH: 45	omm	DINPB. II	/a	DN1.
HEIGHT CATEGO	RY:				
<6	8/9	9/12		12/15	15/18
18/21 2	21/24	24/27		27/30	>30
CROWN SPREAD	CATEGOR	Y:			
	3/9	9/12		12/15	15/18
18/21 2	21/24	24/27		27/30	>30
	0.450				
TREE CONDITION		NO	RMAL		POOR
VIGOUR: GOOI)	INO	RIVIAL		FOOR
DIEBACK %	Yes 10%		PREVIOUS WORK		Yes – see
					comments @ end
EPICORMIC	20)%	BASAL GROWTH		Yes
GROWTH %					
STEM DAMAGE	N	lo -	WIND D	AMAGE	No
BREAKOUT	N	lo	CAVITIE	S	None visible
FUNGAL	None	visible	INSECT		No
INFECTION			INFECT	ION	
ROOT DAMAGE	N	lo	RAISED	BED	No
SURROUNDING	0.5 m from	rear brick	CO-DO	TNANI	No
AREA	boundary v	vall.	STEMS		
DICK EVALUATIO	NNI.				
RISK EVALUATION SUBSTANTIAL		ODERATE		TOLE	RABLE
SUBSTANTIAL	IN	IODENATE	•	IOLL	IVADLL
DIRECT	IRECT No		SOIL PR	OFILE	Not undertaken
IN-DIRECT	No		TREE ROOT ANALYSIS		Not undertaken

DBH = diameter @ 1.5 metres above ground level DNPB = distance to nearest point of building

No

Yes

No

No

DNT = distance to nearest tree

MATURE

VALUE

SPECIMEN

LANDSCAPE

PROMINENT

POSITION

WILDLIFE VALUE

UNUSUAL / RARE

PART OF GROUP /

STREETCENE

TREE

NATIVE

AVENUE

No

No

No

No

TREE NUMBER	3		SPECIE	S Populi	us nigra
TREE STATISTI	CS:				
AGE:Circa		750mm	DNPB: 3	3m	DNT: n/a
HEIGHT CATEO	ORY:				
<6	6/9	9/12		12/15	15/18
18/21	21/24	24/27		27/30	>30
CROWN SPREA	D CATEGO	ORY:			
<6	6/9	9/12		12/15	15/18
18/21	21/24	24/27		27/30	>30
TREE CONDITION					
VIGOUR: GOO	OD	NO	RMAL		POOR
DIEDACK 0/		No	DDEVIC	LIC WORL	/ Vac and
DIEBACK %		No	PREVIC	OUS WORK	
EPICORMIC	+	20%	DACAL	GROWTH	comments @ end
GROWTH %		2070	DASAL	GROWIN	INO
STEM DAMAGE		No	WIND	AMAGE	No
BREAKOUT	•	No	CAVITIE	The state of the s	Probably @
			0		pollard points
FUNGAL	No	ne visible	INSECT		No
INFECTION			INFECT	ION	
ROOT DAMAGE		No	RAISE	BED	No
SURROUNDING		Abutting next door rear boundary brick		MINANT	No
AREA					
	wall				
RISK EVALUAT	ION:		71		
SUBSTANTIAL	IOIV.	MODERATE		TOL	ERABLE
00001/11/11/12					
DIRECT	Possi	ble – from	SOIL PF	ROFILE	Not undertaken
	pollar	d break out		entered all reservoir	
IN-DIRECT	No		TREER	OOT	Not undertaken
			ANALYS	SIS	
ABACAUTY					
AMENITY VALU	JE:	MEDIUM		LOV	Λ/
HIGH		IVIEDIOIVI		LOV	V
MATURE		Yes	LINITISTI	AL / RARE	No
SPECIMEN		100	TREE	AL / INAINE	- 140
WILDLIFE VALU	JE	Yes	NATIVE		No
LANDSCPE	110.774	Yes	STREE		No
VALUE					

DBH = diameter @ 1.5 metres above ground level DNPB = distance to nearest point of building

DNT = distance to nearest tree

PROMINENT

POSITION

No

PART OF GROUP /

AVENUE

No

MAINTENANCE RECOMMENDATIONS:

LIFT CROWN – Ht. above g.l.		REDUCE CROWN % or length	T1 by a maximum of 750mm to nearest lateral on development side of crown and balance remainder.
THIN CROWN %	T1 by 10%	DEADWOOD	T1 and T2
SCAFFOLD POLLARD – HT.		POLLARD – HT.	
RE-POLLARD – HT.	Re-pollard T3 to original pollarding points at around 8 metres.	FORMATIVE PRUNE	
FELL		GRIND STUMP	
COPPICE		REMOVE BASAL GROWTH	T1 and T2
REMOVE EPICORMIC GROWTH	T1 and T2	OTHER	Remove Ivy on T1, T2 and T3

COMMENTS:

Tree T1:

- Crown previously reduced.
- Approximately 60% lvy cover of crown.

Tree T2:

- Tree not in particularly good condition and showing dieback from the top.
- Approximately 80% lvy cover of crown.

Tree T3:

- Previously pollarded at around 8 metres with strong re-growth from that point.
- Potential for breakout of re-growth at original pollard points.
- Approximately 70% lvy cover of crown.

DBH = diameter @ 1.5 metres above ground level
DNPB = distance to nearest point of building
DNT = distance to nearest tree






Photo 1




Photo 2



Photo 3

Photo 4