revision	date	initials	description of amendments
R	8/2/99		ROSITION OF PLANT AT NORTH END OF ROOF AMENDED

GRID SETTING-OUT CRITERIA IS AS FOLLOWS :-

1. ALL DATA REFERRED TO IS TAKEN AT THIRD FLOOR LEVEL.
2. GRID LINE 4 IS ON INSIDE FACE OF COLUMNS TO FRONT ELEVATION BETWEEN GRIDS B AND G.
3. GRID LINES B TO M ARE PERPENDICULAR TO GRID LINE 4 AND ARE ON CENTRE LINES OF COLUMN FACES ON GRID LINE 4.
4. GRID LINES 2 AND 3 ARE PARALLEL TO GRID LINE 4 AND ARE ON CENTRE LINES OF COLUMN FACES ON GRID LINE A.
5. GRID LINE A IS ON INSIDE FACE OF COLUMNS AT GRID LINES 2 AND 3 AND IS NOT PARALLEL TO GRID LINE B.
6. GRID LINE 1 IS ON OUTER FACE OF BUILDING AND IS NOT PARALLEL TO GRID LINE 2.
7. GRID LINE N IS ON INSIDE FACES OF COLUMNS IN MAIN AREA.
8. SETTING OUT POINT IS AT INTERSECTION OF GRID LINES 4 AND F.

M14/14/B

R9804826R2

L9804838R2

FOR CONSTRUCTION

FOURTH FLOOR PLAN

NOTE
ALL SPOT LEVELS GIVEN ON FLAT ROOF
AREA REFER TO TOP SURFACE OF PLYWOOD DECKING

INDICATIVE PLAN ONLY

PASKIN KYRIAKIDES SANDS	project: 7-11 HERBRAND STREET						
	title: PROPOSED FOURTH FLOOR PLAN						
	scale: 1:100	date: 23/1/98	drawn:	job no.: 534	disc.: A	dwg no.: WP 206	rev.: R

7 Cliff Road Studios, London, NW1 9AN telephone: 0171 485 1114
facsimile: 0171 485 5753 modem: 0171 428 0560 email: pksarch@compuserve.com

DO NOT SCALE FROM THIS DRAWING : Verify all dimensions on site