

## 43 Belsize lane - Green Roof Specification and Maintenance

---

The green roof at 43 Belsize Lane is an extensive type comprising 30 species of sedum and wildflower. The species mix is as follows:

| Species                           |
|-----------------------------------|
| S. Acre 'Aureum'                  |
| S. Acre 'October Fest'            |
| S. Album                          |
| S. Album 'Athorum'                |
| S. Album 'Coral Carpet'           |
| S. Album 'Minima'                 |
| S. Anglicum 'Scottish'            |
| S. Delosperma 'cooperii nubigeum' |
| S. Ewersii                        |
| S. Ellacombianum                  |
| S. Fosterianum 'Oracle'           |
| S. Fosterianum 'Silver Stone'     |
| S. Hispanticum 'Glauca'           |
| S. Cyaneum 'Rose Carpet'          |
| S. Kamtschaticum                  |
| S. Lydium                         |
| S. Montanum                       |
| S. Oreganum                       |
| S. Pachyclados                    |
| S. Reflexum                       |
| S. Rupestre 'Angelina'            |
| S. Selskianum                     |
| S. Sexsaungulare                  |
| S. Spurium 'Purpur Carpet'        |
| S. Spurium 'Summer Glory'         |
| S. Spurium 'Ruby Mantle'          |
| S. Spurium 'Dragons Blood'        |
| S. Spurium 'Fulda Glut'           |
| S. Spurium 'Coccineum'            |
| S. Spathulifolium 'Purpureum'     |
| S. Spathulifolium 'Cape Bianco'   |
| Lampranthus Purple                |
| Plox Subulata                     |
| S. Spurium 'Tricolour'            |
| S. Sieboldi                       |

## **Maintenance Schedule**

During the first year, maintenance will take place at six month intervals. After the first year, annual maintenance will be carried out.

Typical procedures carried during maintenance include:

1. Removal of unwanted plant material i.e. invasive species (if required).
2. Correction of any localized plant system problems that may have occurred post installation.
3. Replacement of any naturally failed plants exceeding 5% of total plants installed.
4. Application of nutrient source.
5. Removal of dead flower heads (if required).
6. Inspection of rainwater outlet chambers and surrounding vegetation breaks.
7. Replenishment of any areas of settled substrate.

Sedum Green Roof

Part of the Heseltine Carp Group

Lower Leigh farm, Tokes Lane,  
East Knoyle, Salisbury, Wilts SP3 6BZ  
01747 830176