



Method Statement

Project Paddington Trail

Contractor 3D Eye Limited on Behalf of Premier Communication

Location of Work - Various Locations

Site Contact - TBC

Rig date - Week of 20th October 2014

Description and sequence of work

Delivery and installation of Bear statues to various locations

Delivery by Vehicle to various locations of Bear Statue
Delivery by Vehicle to various locations of weighting for Bear Statue
Crews of 2 or more to attend the various locations by vehicles.
Crews to manually lift and move Bear Statue to final location
Crews to remove the access panel with cordless driver
Crews to manually lift and place weights into Bear Statue plinth
Crews to replace access panel.
Crews to make visual safety checks before leaving site.

Paddington Bear statue

Bear statues and weights will be delivered by vehicles to various locations where installation crews of 2 or more people in vehicles will meet the delivery vehicles. Locations will have been predetermined and assessed for suitability. Access will be clear and suitable for manual handling of the statues from delivery vehicle to final location. Location ground should be level. The installation crew will unload the Statue manually and transfer onto a trolley for transport to the installation locations. The statue will be manually located. The crew will return to the delivery vehicle and manually load the concrete weights on a trolley for transport to the location of the statue. The statue plinth has a removable panel which is removed using a cordless driver and security tip. Weights and then placed inside the plinth and the access panel replaced with cordless driver and security tips. Crews will then visually check the statue before leaving site and moving to the next location to repeat the process.

Tools and materials:

Hand tools
Cordless driver
Trolleys
Bear Statue on plinth
Concrete weights

Method Statement prepared by: Ben Comley

Date: 03.07.2014