


## Notes:

- THIS DRAWING IS TO BE READ IN CONJUNCTION WITH ALL MECHANICAL, ELECTRICAL AND PUBLIC HEALTH SERVICES DRAWINGS FOR THIS CONTRACT.
- ALL MECHANICAL SERVICES TO BE INSTALLED IN ACCORDANCE WITH THE RELEVANT ENGINEERING SPECIFICATION.
- 3. REFER TO ARCHITECTS DRAWINGS FOR POSITIONS OF ALL DIFFUSERS AND GRILLES.
- 4. ALL CONDENSATE LINES WITHIN FALSE CEILING & FLOOR VOIDS SHALL BE INSTALLED TO A MINIMUM FALL OF 1:100.
- 5. ALL CONDENSATE PIPEWORK TO BE LAGGED AS PER SPECIFICATION.
- 6. ALL FIRE DAMPERS AND VCD'S TO BE PROVIDED WITH ADJACENT ACCESS PANELS.
- ALL FIXING TYPES/METHOD TO BE AGREED WITH THE STRUCTURAL ENGINEER PRIOR TO COMMENCING OF INSTALLATION.
- 8. DRAIN COCKS SHALL BE PROVIDED AT LOW POINTS.
- 9. PIPEWORK JOINTS SHALL BE MINIMISED WHERE RUNNING WITHIN FLOOR VOIDS.
- PIPEWORK TO BE INSULATED WHERE RUNNING WITHIN VOIDS OR CONCEALED IN RISERS.
- GAS SERVICES DISTRIBUTION TO BE INSTALLED IN ACCORDANCE WITH GAS SAFETY REGULATIONS.
- 12. ALL RADIATORS IN BUILDING 15 CONNECTED TO THE CONDENSER CIRCUIT PIPEWORK.



## chris evans consulting building services designers

27- 33 Brighton Road Redhill | Surrey | RH1 6PP www.chrisevansconsulting.co.uk

Client

**BEDFORD ESTATES** 

itect

**DLG ARCHITECTS** 

Proj

15 BEDFORD SQUARE LONDON

Title

FIRST FLOOR MECHANICAL SERVICES LAYOUT

 NOV 13
 1:50 @ A1
 MS
 IR

 Drg. No.
 Rev.

TENDER 0945

0945 / 15 / 303