

Project Title	10 Ferdenand Street	
Location:		
Client:		
Correspondence File:		

ESTIMATED/MEASURED BILL OF QUANTITIES

ITEM	DESCRIPTION	QUANTITY	UNIT	TOTAL
200.003	Take up or down and remove to tip off site precast concrete or york stone paving slabs any size type including fiber reinforced up to 65mm thick	29.80	m2	
200.019	Take up or down and set aside for reuse granite flat, edge or standard profile bus boarder kerb	9.73	m	
200.021	Take up or down and remove to tip off site granite flat, edge or standard profile bus boarder kerb	6.94	m	
600.001	Excavation of any material in footways, verges and other pedestrian areas	14.28	m3	
600.007	Extra over excavation for excavation in hard material in footways, verges and other pedestrian areas	14.28	m3	
600.012	Disposal of any material.(except class U1B and U2 material)	14.28	m3	
1100.001	Granite flat kerb 300x200mm, 'fine picked' finish, laid straight or curved exceeding 12 metres radius	9.69	m	
1100.031	Remove from set aside area and relay flat granite kerb, laid straight or curved exceeding 12 metres radius	9.73	m	
1100.058	65mm thick fibre reinforced Artificial stone paving, any size BS A or B on existing base or base measured separately and sand bedding 30mm thick	59.48	m2	
1100.081	150mm ST1 concrete base in footways	59.48	m2	

Contractor Adjustment	0%	
Baxter Increase	4.66%	
Contingencies	15%	

Grand Total			£6,878.09
--------------------	--	--	------------------

Produced By:		Date	
Checked by:		Date	
Approved by:		Date	
Revision:		Date	