TREES

	Name	Girth	Height
T1	Liquidamber Styraciflua	30-35cm	min. 6m
T2	Liquidamber Styraciflua	20-25cm	min. 4.5m
T3	Sorbus aria 'Luescens'	20-25cm	min 4.5m
T4	Prunus serrulata 'Kanzan'	20-25cm	min. 4m
T5	Pyrus Calleryana 'Chantilcleer'	20-25cm	min. 4.5m
T6	Acer platanoides 'Emerald Queen'	20-25cm	min. 4.5m
T7	Prunus avium 'Plena'	20-25cm	min. 4m
T8	Tilia cordata 'Greenspire'	20-25cm	min. 4.5m
T9	Carpinus betulus 'Frans Fontane'	20-25cm	min. 4.5m
T10	Sorbus aucuparia	20-25cm	min. 4m
T11	Acer platanoides	20-25cm	min. 4.5m

All trees to be underground guyed and installed with aeration and irrigation pipes

PLANTING

	Name	Size	Density	%age
H1	Prunus lusitanica	1,1m	7/ lin, m double staggered row	100%
PL1	Alchemilia mollis	1,5-2l	8/m2	10%
	Anemone x Hybida 'Honerine Jobert'	3-4l	5/m2	10%
	Cornus stolonifera 'Flavireama'	5l	5/m2	100%
	Heuchera 'Chocolte ruffles'	1,5-2l	8/m2	15%
	Miscantus sinensis 'Zebrinus'	3l	4/m2	15%
	Perovskia 'Blue spire'	3l	6/m2	15%
	Rudbeckia fulgida	1,5-2l	8/m2	15%
	Salvia x sylvestris 'Mainacht'	1,5-2l	8/m2	10%
	Stipa tenuissima	3l	6/m2	15%
	Allium 'Globemaster'	8+ (topsize)	15 m/2	
	Narcissus sp.	7+ (topsize)	30/m2	
PL2	Alchemilia mollis	1,5-2l	8 m/2	10%
	Carex comans	2l	10/m2	15%
	Cornus sanguinea 'Midwinter fire'	5l	5/m2	100%
	Geranium 'Phaeum'	3-4l	6/m2	5%
	Luzula sylvatica 'Marginata'	2l	6m/2	10%
	Vinca minor 'Alba'	1,5-2l	8/m2	10%
PL3	Anemone x Hybida 'Honerine Jobert'	3-4l	5 m/2	10%
	Cornus stolonifera 'Flavireama'	5l	5/m2	100%
	Deschampsia cespitosa	3-4l	6/m2	5%
	Euphorbia aygdaloides var. Robbiae	3l	5/m2	5%
	Lavandula angustifolia	3l	7/m2	
	Rudbeckia fulgida	1,5-2l	8/m2	15%
	Sedum x telephium 'Autumn Joy'	3l	6/m2	
	Salvia x sylvestris 'Mainacht'	1,5-2l	8/m2	10%
	Stipa tenuissima	3l	6/m2	15%
	Allium 'Globemaster'	8+ (topsize)	15 m/2	
	Narcissus sp.	7+ (topsize)	25/m2	
PL4	Anemone nemrosa	1,5-2l	8/m2	5%
	Asplenium scolopendrium	2l	6m/2	15%
	Dryopteris filix-mas	2l	6m/2	15%
	Euphorbia aygdaloides var. Robbiae	3l	5/m2	5%
	Geranium 'Phaeum'	1,5-2l	6/m2	10%
	Luzula sylvatica 'Marginata'	2l	6m/2	10%
	Liriope muscari	2l	6/m2	10%
	Polystichum aculeatum	2l	6/m2	10%
	Vinca minor 'Alba'	1,5-2l	8/m2	20%
	Galanthus nivalis	6+ (topsize)	35/m2	
LW	Lawn			
LS	Existing lawn to be overseeded			

CLIMBERS

	Name	Size	Density
CL1	Hydrangea petiolaris	5l	1 / lin. m
CL2	Lonicera japonica 'Halliana'	3l	0.25 / lin.m
CL3	Parthenocissus henryana	3l	1 / lin.m
CL4	Hedera helix pedata	3l	0.5 / lin.m

TOPSOIL, SUBSOIL

To tree pits 650mm topsoil
450mm subsoil
min. 2.5m radius from centre of tree,
or area as shown

To hedge planting 550mm topsoil
350mm subsoil

To planting areas 450mm topsoil
350mm subsoil

To planting areas under existing trees 200mm topsoil

N.B, Tree pit to Aspen Courtyard to extend whole length and width of courtyard space, to edge of paving.

NOTES:

1. This drawing is to be read in conjunction with all relevant contract documentation from the design team, with any conflicting information to be brought to the attention of Turkington Martin Landscape Architects in writing before commencing on site.

2. The contractor is to check and verify all levels and dimensions before construction. Any discrepancies are to be brought to the attention of Turkington Martin Landscape Architects in writing before commencing on site.

3. All dimensions in mm, unless otherwise stated.

4. Do not scale from this drawing.

5. All sub base and concrete design and specification to engineer's details. All diagrams provided here are purely indicative.

6. Waterproofing of any element to be specified by others.

7. All proprietary products shall be installed in accordance with manufacturers written instructions.

8. Plant numbers are an indication only and plants should be ordered to suit site areas in accordance with scheduled plant densities.

9. Any proposed plant substitution shall be agreed with the landscape architect prior to ordering.

DATE	DRAWN	DESCRIPTION OF REVISION	REVISION LETTER	CHECKED BY
20140603	TS	Building footprint updated	B	-
20140501	TS	Building footprint updated	A	-

turkington martin

36-40 York Way, London, N1 9AB
T: (+44) 020 7843 3170
E: studio@turkingtonmartin.com

DRAWING STATUS :
FOR INFORMATION

CLIENT :
CAMDEN COUNCIL
EC HARRIS

PROJECT TITLE :
Maitland Park Estate

DRAWING TITLE :
Planting GA

DRAWING SCALE :	DRAWN BY :	DRAWN DATE :
1:250	AD	10.03.2014
PAPER SIZE :	CHECKED BY :	CHECKED DATE :
A1	TS	10.03.2014

DRAWING NUMBER : 122-L05
REVISION : B

Turkington Martin LANDSCAPE ARCHITECTS