

BEARING PILE TABLE						
PILE No.	S.W.L. kN	CUT OFF LEVEL	TENSION kN	SHEAR kN	TOP OF PILE CAP LEVEL	PILE CAP DEPTH
P1	300	22.250	–	–	23.200	1000
P2	300	22.250	–	–	23.200	1000
P3	650	22.250	–	–	23.200	1000
P4	650	22.250	–	–	23.200	1000
P5	450	21.800	–	–	23.750	1000
P6	450	21.800	–	–	22.750	1000
P7	200	21.800	–	–	22.750	1000
P8	200	21.800	–	–	22.750	1000
P9	650	22.250	–	–	23.200	1000
P10	650	22.250	–	–	23.200	1000
P11	300	22.250	300	–	23.200	1000
P12	750	21.800	–	–	22.750	1000
P13	750	21.800	–	–	22.750	1000
P14	200	21.800	–	–	22.750	1000
P15	200	21.800	–	–	22.750	1000
P16	1000	22.250	–	–	23.200	1000
P17	1000	22.250	–	–	23.200	1000
P18	850	21.225	–	–	22.175	1000
P19	850	21.225	–	–	22.175	1000
P20	850	21.225	–	–	22.175	1000
P21	850	21.225	–	–	22.175	1000
P22	850	21.225	–	–	22.175	1000
P23	600	21.625	–	–	22.175	600
P24	700	21.625	–	–	22.175	600
P25	600	21.625	–	–	22.175	600

BEARING PILE TABLE						
PILE No.	S.W.L. kN	CUT OFF LEVEL	TENSION kN	SHEAR kN	TOP OF PILE CAP LEVEL	PILE CAP DEPTH
P26	850	22.650	–	–	22.175	600
P27	750	22.650	–	–	22.175	600
P28	400	22.650	–	–	22.175	600
P29	600	21.225	150	–	22.175	1000
P30	600	21.225	150	–	22.175	1000
P31	750	21.225	150	–	22.175	1000
P32	950	21.225	–	–	22.175	1000
P33	700	21.225	150	–	22.175	1000
P34	450	21.625	–	–	22.175	600
P35	550	21.225	150	–	22.175	1000
P36	550	21.225	150	–	22.175	1000
P37	800	21.225	150	–	22.175	1000
P38	800	21.225	150	–	22.175	1000
P39	1000	21.225	150	–	22.175	1000
P40	1000	21.225	150	–	22.175	1000
P41	900	21.225	–	–	22.175	1000
P42	900	21.225	–	–	22.175	1000
P43	900	21.225	–	–	22.175	1000
P44	900	21.225	–	–	22.175	1000
P45	1000	21.800	–	–	22.750	1000
P46	1000	21.800	–	–	22.750	1000
P47	1000	21.800	–	–	22.750	1000
P48	1000	21.800	–	–	22.750	1000
P49	750	22.250	–	–	23.200	1000
P50	750	22.250	–	–	23.200	1000

BEARING PILE TABLE						
PILE No.	S.W.L. kN	CUT OFF LEVEL	TENSION kN	SHEAR kN	TOP OF PILE CAP LEVEL	PILE CAP DEPTH
P51	750	22.250	–	–	23.200	1000
P52	1000	22.250	–	–	23.200	1000
P53	1000	22.250	–	–	23.200	1000
P54	650	22.250	–	–	23.200	1000
P55	650	22.250	–	–	23.200	1000
P56	900	22.250	–	–	23.200	1000
P57	900	22.250	–	–	23.200	1000
P58	800	22.025	–	–	22.975	1000
P59	800	22.025	–	–	22.975	1000
P60	1000	21.225	150	–	22.175	1000
P61	1000	21.225	150	–	22.175	1000
P62	1000	21.225	150	–	22.175	1000
P63	1000	21.225	150	–	22.175	1000
P64	1000	21.225	150	–	22.175	1000
P65	1000	21.225	150	–	22.175	1000
P66						
P67						
P68						
P69						
P70						
P71						
P72						
P73						
P74						
P75						

FOR NOTES REFER TO GENERAL NOTES DRAWING 6398–GN–1.0.
ALL SETTING OUT IS TO THE C. OF COLUMNS AND SHEAR WALLS UNLESS NOTED OTHERWISE
ALL RC WALLS TO BE 200 THICK UNO.
ALL COLUMNS 600x200 UNLESS NOTED OTHERWISE.
Φ – DENOTES PENETRATION THROUGH SLAB
ALL BUILDERS WORKS HOLES ARE TO BE SET OUT ON SITE USING WALKER ASSOCIATES DRAWINGS. ANY DEVIATION FROM THIS IS TO BE HIGHLIGHTED TO WALKER ASSOCIATES A.S.A.P. IM AND E ENGINEER TO ENSURE ALL HOLES HAVE BEEN SHOWN ON WALKER ASSOCIATES DRAWINGS PRIOR TO INSTALLATION.
ALL UPSTANDS AND DOWNSTANDS DIMENSIONS ARE TO BE TAKEN FROM SSL.
NOTE: ORISGRIL OR SIMILAR APPROVED GRILLAGE TO BE CAST INTO ALL HOLES GREATER THAN 200mm SQUARE.
ALL CONCRETE TO BE SOURCED THROUGH A SUPPLIER WHO OPERATES AN ENVIRONMENTAL MANAGEMENT SYSTEM WHICH COMPLIES WITH THE REQUIREMENTS OF ISO 14001:2004
C40 – WATERPROOF CONCRETE TO BASEMENT WALLS, SLABS AND LIFT PITS. ACEC–2 DS–3
APPROXIMATE PILE DEPTH 20m BELOW GROUND LEVEL TO BE CONFIRMED BY PILING CONTRACTOR.
COLUMNS 8, 10 AND 12 ARE TO BE GRADE C50 CONCRETE.

B	11.07.14	ISSUED FOR CONSTRUCTION	PMB	WA	
A	27.06.14	UPDATED AS CLOUDED	PMB	WA	
—	17.03.14	PRELIMINARY ISSUE	PMB	WA	
REV	DATE	AMENDMENT	BY	CHKD	
STATUS		Construction			
PROJECT		Plender Street			
CLIENT					
DRAWING		Pile Load Tables			
		Block A			
DATE Jan 14		DRAWN BY PMB			
SCALES (@A1)- 1:50		CHECKED BY			
DRG NO.		6398—A—S10.1 ^B			
		Address13 Capricorn Centre Cranes Farm Road Basilston Essex SS14 3JJ Tel01268 530 590 Fax01268 28 66 28 Webwww.walker-associates.co.uk			