



Basement Impact Assessment: The Pears Building

**(Surface Water and
Groundwater)**

Basement Impact Assessment: The Pears Building

Prepared for

RFC Development Limited,
Royal Free Charity
Pond Street
London NW3 2QG

Report reference: 62361R1, October 2014
Report status: Final Report

Confidential
Prepared by
ESI Ltd

New Zealand House, 160 Abbey Foregate, Shrewsbury, SY2 6FD, UK
Tel +44(0)1743 276100 **Fax** +44 (0)1743 248600 **email** info@esinternational.com
Registered office: New Zealand House, 160 Abbey Foregate, Shrewsbury, SY2 6FD. Registered in England and Wales, number 3212832

Basement Impact Assessment: The Pears Building

This report has been prepared by ESI Ltd. (ESI) in its professional capacity as soil and groundwater specialists, with reasonable skill, care and diligence within the agreed scope and terms of contract and taking account of the manpower and resources devoted to it by agreement with its client, and is provided by ESI solely for the internal use of its client.

The advice and opinions in this report should be read and relied on only in the context of the report as a whole, taking account of the terms of reference agreed with the client. The findings are based on the information made available to ESI at the date of the report (and will have been assumed to be correct) and on current UK standards, codes, technology and practices as at that time. They do not purport to include any manner of legal advice or opinion. New information or changes in conditions and regulatory requirements may occur in future, which will change the conclusions presented here.

This report is confidential to the client. The client may submit the report to regulatory bodies, where appropriate. Should the client wish to release this report to any other third party for that party's reliance, ESI may, by prior written agreement, agree to such release, provided that it is acknowledged that ESI accepts no responsibility of any nature to any third party to whom this report or any part thereof is made known. ESI accepts no responsibility for any loss or damage incurred as a result, and the third party does not acquire any rights whatsoever, contractual or otherwise, against ESI except as expressly agreed with ESI in writing.

Confidential
Prepared by
ESI Ltd




New Zealand House, 160 Abbey Foregate, Shrewsbury, SY2 6FD, UK

Tel +44(0)1743 276100 **Fax** +44 (0)1743 248600 **email** info@esinternational.com




Registered office: New Zealand House, 160 Abbey Foregate, Shrewsbury, SY2 6FD. Registered in England and Wales, number 3212832

62361R1. Final Report

Surface Water

	Name	Signature
Author	Samson Collier	
Checked by	Helen Vonka (CIWEM)	
Reviewed by	Helen Vonka (CIWEM)	

Groundwater

	Name	Signature
Author	Samson Collier	
Checked by	Joe Gomme (CGeol)	
Reviewed by	Joe Gomme (CGeol)	

Revision record:

Issue	Report ref	Comment	Author	Checker	Reviewer	Issue date	Issued to
1	62361R1	SW & GW	SCC	HCV & JWG	HCV & JWG	21/10/2014	Nick Tibbitts, Burofour
2							

Confidential
Prepared by
ESI Ltd

New Zealand House, 160 Abbey Foregate, Shrewsbury, SY2 6FD, UK

Tel +44(0)1743 276100 Fax +44 (0)1743 248600 email info@esinternational.com

Registered office: New Zealand House, 160 Abbey Foregate, Shrewsbury, SY2 6FD. Registered in England and Wales, number 3212832

REPORT SUMMARY

The assessment findings are summarised as follows:

1. Impacts to surface water flows and related flooding	High	
	Med	
	Low	
2. Impacts to groundwater flows and related flooding	High	
	Med	
	Low	
3. Overall risk posed by the Site	High	
	Med	
	Low	

Key:

High		<i>There is a high potential risk</i>
Med		<i>There is medium potential risk</i>
Low		<i>There is a low potential risk</i>

RECOMMENDATIONS (FOR NEXT STEPS)

The development described in this report will change the proportion of impermeable surface area. However peak runoff and related flooding risk from the proposed development will not change as the entirety of the runoff from the Site is directed into the adjacent sewer pre- and post-development. It is expected that mitigation measures will be put in place to ensure that the discharge to the sewer post-development is less than the discharge to the sewer pre-development.

Two streets within 250 m of the site were subject to surface water flooding in 1975 and 2002. These are believed to be related to sewer flooding following extreme rainfall summer events; however there have been no reported incidents of sewer flooding at the site, according to Thames water.

Groundwater is present below the site within the London Clay, based on two boreholes to the south west and north east of the Site. However it is believed that the water within these boreholes is not a reflection of a water table but merely a presence of localised pockets of water within the London Clay.

Precautions should be taken against sewer flooding at this location; however it is expected that the discharge to the sewer post-development will be less than pre-development, reducing the impact on the sewer system.

CONTENTS

1	INTRODUCTION.....	1
1.1	Background.....	1
1.2	Scope of Works.....	2
1.3	Proposed Basement Works	2
2	SCREENING.....	3
3	SCOPING.....	6
4	GROUNDWATER MODELLING	7
4.1	Model run	7
5	IMPACT ASSESSMENT	9
6	CONCLUSIONS.....	10
6.1	Surface water	10
6.2	Groundwater	10
6.3	Recommendations	10
	REFERENCES	11

FIGURES

Figure 1.1 Site location	1
--------------------------------	---

APPENDICES


Appendix A.1	Current Development Plans
Appendix A.2	Proposed Development Plans
Appendix B	Site Investigation Borehole Logs
Appendix C	Thames Sewer Flooding Report
Appendix D	Site Permeability Plans – Current and Proposed

1 INTRODUCTION

1.1 Background

ESI Ltd (ESI) was commissioned by RFC Development Limited in April 2014 to undertake a Basement Impact Assessment (BIA) for the proposed development of the Pears Buildings, NW3 2QG. The site is at an elevation of between 68.5 mAOD and 77 mAOD (Site plans, Appendix A) and lies in a generally flat area with topography sloping gently up from south west to north east. It is located at the approximate national grid reference of TQ 27173 85374 in the London Borough of Camden (Figure 1.1).

Figure 1.1 Site location



This document is a desk study which considers the potential impact relating to the proposed basement development in terms of surface water and groundwater flow and flooding and complies with guidance issued by the London Borough of Camden. The other key component of the BIA (Ground Stability) is covered by the complementary report (Soil Consultants 2014). These reports will be used for submission to the Planning Authority in support of the planning application for the proposed development.

1.2 Scope of Works

The scope of works requested was an assessment of the impacts of the proposed development on surface and ground water flow, levels and drainage. This report outlines the hydrogeological conditions with relevance to construction of the basement at the property. The assessment conforms to the requirements set out by the London Borough of Camden which provides comprehensive guidance on planning applications for basement extensions. These guidelines for basement impact assessments (ARUP (2010), Camden Borough Council, (2011)) have been consulted in order to complete a screening analysis of key hydrological and hydrogeological issues that will satisfy the relevant planning requirements.

The works undertaken follow the procedure outlined below:

- 1) Screening, which aims to identify sites that are a priority for investigation;
- 2) Scoping, which uses simple calculations to demonstrate whether the potential hazards identified in the screening stage pose a risk as a result of the development, and whether the actual risk is significant;
- 3) Groundwater modelling;
- 4) Impact assessment; and
- 5) Recommendations based on the outcome of the assessment.

1.3 Proposed Basement Works

The proposed redevelopment will comprise the installation of a renewed, two-storey basement (level 00 and level 01) beneath the footprint of a new four-storey building (the Pears Building). The minimum base elevation of the proposed basement is planned to be 68.5 mAOD which is identical to the maximum depth of the current basement. Levels 00 and 01 will be extended by approximately 620 m² to the south west (current and proposed Site plans are shown in Appendix A).

2 SCREENING

The screening stage for Impact Assessment has been considered as set out in CPG4 (Camden Council, 2011) as follows.

2.1 SURFACE WATER (Surface flow and flooding screening flowchart (Figure 3, CPG4 (Camden Council, 2011)))			
Impact question	Answer	Justification	Reference
1) Is the Site within the catchment of the pond chains on Hampstead Heath?	No	The Site is not located within the catchment for any of the Hampstead Heath ponds.	Arup, 2010.
2) As part of the proposed site drainage, will surface water flows (e.g. volume of rainfall and peak run-off) be materially changed from the existing route?	No	The drain on site discharges to the adjacent sewer. There will be no additional surface water runoff caused by the proposed development so the total runoff will remain unchanged. Post-development, this runoff is likely to be diverted to the adjacent sewer although plans for on-site storage are yet to be finalised.	Site Plans (Appendix A) BDP, 2014
3) Will the proposed basement development result in a change in the proportion of hard surfaced / paved external areas?	Yes	The site is currently covered by a combination of permeable and impermeable surfaces. There will be an increase in impermeable surface area resulting from the development.	Site Plans (Appendix A).
4) Will the proposed basement result in changes to the profile of the inflows (instantaneous and long-term) of surface water being received by adjacent properties or downstream watercourses?	No	There will be an increase in impermeable surfaces after development of the Site, however all the permeable surfaces are shallow and underlain by impermeable surfaces which direct infiltrated water to join runoff from impermeable surfaces and eventually discharge into the nearby sewer. Therefore there is not expected to be any change in surface water quantity being received by adjacent properties or downstream watercourses. A tributary of the “lost” River Tyburn runs approximately 250 m to the south of the proposed development and the River Fleet runs 160 m east of the proposed development. Given that the entirety of the Site runoff is directed into the sewer pre- and post-development and that the nearby lost rivers are most likely culverted, there will be no changes to the watercourse inflows. No other surface water bodies are known to exist within 500 m of the Site.	Ordnance Survey Mapping. Barton, 1992. Site plans (Appendix A) BDP, 2014
5) Will the proposed basement result in changes to the quality of surface water being received by adjacent properties or downstream watercourses?	No	The entirety of the Site run-off is directed into the sewer pre- and post-development, therefore there will be no changes in the quality of surface water being received by adjacent properties of downstream watercourses.	BDP, 2014

6) Is the Site in an area known to be at risk from surface water flooding or is it at risk from flooding, for example because the proposed basement is below the static water level of a nearby surface water feature?	No	<p>The Site itself is considered to be at low risk of surface water flooding according to Groundsure (2014).</p> <p>According to Bakewell (2008), two streets within 250 m of the site were flooded in 1975 and 2002. The flood event in August 2002 was caused by excessive rainfall causing the main sewer system to become completely inundated. According to Hopkins Architects (2014), the peak discharge to the sewer post-development will be less than pre-development, reducing the impact on the sewer system. This will be mitigated by water storage beneath the Site.</p> <p>According to Thames Water, there is no history of sewer flooding at the site (Appendix C).</p> <p>The area is not in a zone at risk of flooding from rivers, the sea or failing reservoirs as defined by the Environment Agency (2014).</p> <p>The east side of the Site is at a moderate risk of surface water flooding according to the Environment Agency.</p>	<p>ARUP, 2010.</p> <p>Environment Agency, 2014.</p> <p>Thames Water, 2014</p> <p>Bakewell, 2008</p> <p>Groundsure Flood report, 2014</p>
--	-----------	---	--

2.2 GROUND WATER (Subterranean (ground water) flow screening chart (Figure 1, CPG4 (Camden Council, 2011))

Impact question	Answer	Justification	Reference
1a) Is the Site located directly above an aquifer?	No	<p>The Site is located upon the London Clay Formation, described by the BGS as "a sedimentary bedrock comprising bioturbated or poorly laminated, slightly calcareous, silty to very silty clay, clayey silt and sometimes silt, with some layers of sandy clay". This may contain high porosity, low permeability horizons within generally low permeability and low porosity material that is classified as Unproductive Strata by the Environment Agency.</p> <p>According to the Site investigation borehole logs (Appendix B), BH3, BH3a, BH4 and BH5 indicate a depth of Made Ground between 1 and 4 m below ground level underlain by London Clay which is present to the bottom of each borehole. The maximum depth London Clay was recorded in was BH5 (the deepest borehole) at 40 mbgl.</p>	<p>British Geological Survey, 2014.</p> <p>Environment Agency, 2014.</p> <p>Site investigation (Appendix B)</p>
1b) Will the proposed basement extend beneath the water table surface?	Yes	<p>Given the nature of the London Clay in the vicinity of the Site significant groundwater movement in the London Clay beneath the Site is unlikely. However during a site visit in October 2014 (see Appendix C), water levels in BH3 and BH5 were recorded respectively at 67.03 mAOD and 73.86 mAOD which in the latter case is higher than the base of Level 00 of the existing and proposed basements.</p>	Site investigation (Appendix B)
2) Is the Site within 100m of a watercourse, well (used/disused) or potential spring line?	No	<p>There are no existing or "lost" rivers within 100 m of the Site</p> <p>Given the local geology and topography it is unlikely that there are any springs within the vicinity of the site.</p>	<p>Ordnance Survey Mapping. 2014.</p> <p>Barton, 1992.</p>

		There are no wells within 100 m of the Site.	Arup, 2010
3) Is the Site within the catchment of the pond chains on Hampstead Heath?	No	The Site is not located within the catchment for any of the Hampstead Heath ponds.	Arup, 2010.
4) Will the proposed basement development result in a change in the proportion of hard surfaced / paved external areas?	Yes	The site is currently covered by a combination of permeable and impermeable surfaces. There will be an increase in impermeable surface area resulting from the development.	Site Plans (Appendix A)
5) As part of the Site drainage, will more surface water (e.g. rainfall and run-off) than at present be discharged to the ground (e.g. via soakaways and/or SUDS)?	No	The entirety of the run-off from the proposed development will be discharged to the adjacent sewer.	Site details provided by the BDP (2014)
6) Is the lowest point of the proposed excavation (allowing for any drainage and foundation space under the basement floor) close to, or lower than, the mean water level in any local pond or spring line.	No	The water level in Hampstead no 1 Pond located 450 m north of the Site is at a similar level to the lowest point of the basement. There are no spring lines within the vicinity of the Site	Ordnance Survey Mapping.

3 SCOPING

3.1 SURFACE WATER (Surface flow and flooding screening flowchart (Figure 3, CPG4 (Camden Council, 2011)))

Impact question	Answer	Justification	Reference
3) Will the proposed basement development result in a change in the proportion of hard surfaced / paved external areas?	Yes	<p>The site is currently covered by a combination of permeable and impermeable surfaces. There will be an increase in impermeable surface area resulting from the development.</p> <p>Despite the change of proportion in hard surfaced/paved external areas, the entirety of the rainfall falling on the site will be collected and discharged into the adjacent sewer. Even the rainfall that infiltrates through permeable surfaces will infiltrate through shallow permeable strata before being directed into the adjacent sewer.</p>	Site Plans (Appendix A)

3.2 GROUND WATER (Subterranean (ground water) flow screening chart (Figure 1, CPG4 (Camden Council, 2011)))

Impact question	Answer	Justification	Reference
1b) Will the proposed basement extend beneath the water table surface?	Yes	<p>Given the nature of the London Clay in the vicinity of the Site significant groundwater movement in the London Clay beneath the Site is unlikely. However during a site visit in October 2014 (see Appendix C), water levels in BH3 and BH5 were recorded respectively at 67.03 mAOD and 73.86 mAOD which in the latter case is higher than the Level 00 of the basement which is 68.5 mAOD. However it is likely that the water encountered in these boreholes is localised in pockets and not a reflection of a true water table beneath the Site.</p>	Site investigation (Appendix B)
4) Will the proposed basement development result in a change in the proportion of hard surfaced / paved external areas?	Yes	<p>The site is currently covered by a combination of permeable and impermeable surfaces. There will be an increase in impermeable surface area resulting from the development.</p> <p>Despite the change of proportion in hard surfaced/paved external areas, the entirety of the rainfall falling on the site will be collected and discharged into the adjacent sewer. Even the rainfall that infiltrates through permeable surfaces will infiltrate through shallow permeable strata before being directed into the adjacent sewer.</p>	Site Plans (Appendix A) BDP (2014)

4 GROUNDWATER MODELLING

A two-dimensional scoping model has been developed of the area around the Site, to estimate the magnitude of groundwater level change in the vicinity of the proposed basements at the Site. The details of the model are as follows.

The existing and proposed basements are represented in the model as a block of impermeable cells (it is reasonable to assume that it is sealed as it penetrates the whole aquifer and therefore must be constructed to limit groundwater ingress).

Model results are compared between two scenarios, with and without the proposed basement.

The conceptual model is of Made Ground overlying an essentially impermeable base (London Clay). The model has not been calibrated to groundwater level except to match approximately the observed hydraulic gradient and saturated thickness at the Site.

4.1 Model run

The model was developed using Groundwater Vistas, running MODFLOW in steady state mode. The model is made up from 22,500 cells arranged in a 150 x 150 cell grid; cell size is 1 m x 1 m. The model was run according to three scenarios: Scenario 1, Scenario 2 and Scenario 3.

4.1.1 Scenario 1 – fixed thickness

Layer	Elev mAOD	Comment
1	74.5 – 73.1	Made Ground – taken as average of site
2	73.1 – 72.55	London Clay to base of Level 01
3	72.55 – 68.5	London Clay to base of Level 00
4	68.5 – 48.1	London Clay of fixed thickness below Made Ground

Constant heads applied as a gradient calculated from the highest (worst case) levels recorded in BH3a and BH5.

Hydraulic conductivity (K) of Made Ground = 500 m/d (British Geological Survey, 2006)

K of London Clay = 0.001 m/d (Environment Agency, 2000)

K of current basement = 0.0000001 m/d

4.1.2 Scenario 2 – varied thickness

Layer	Elev mAOD	Comment
1	Varied - Digitised OS contours	Made Ground – taken as average of site (constant 1.4 m thickness)
2	Varied	London Clay to base of Level 01 (constant 0.55 thickness)
3	Varied	London Clay to base of Level 00 (constant 4.05 m thickness)
4	Varied	London Clay of fixed thickness below Made Ground (constant 20.4 m thickness)

Constant heads applied as a gradient calculated from the highest (worst case) levels recorded in BH3a and BH5.

K of Made Ground = 500 m/d

K of London Clay = 0.001 m/d NOTE: another run was completed on the model with K increased to 0.1 m/d

K of current basement = 0.0000001 m/d

4.1.3 Scenario 3 – varied thickness no made ground

Layer	Elev mAOD	Comment
1	90 mAOD to top of LC	Made ground replaced with London clay
2	Varied	London Clay to base of Level 01 (constant 0.55 thickness)
3	Varied	London Clay to base of Level 00 (constant 4.05 m thickness)
4	Varied	London Clay of fixed thickness below Made Ground (constant 20.4 m thickness)

Constant heads applied as a gradient calculated from the highest (worst case) levels recorded in BH3a and BH5.

K of London Clay = 0.001 m/d NOTE: another run completed on model with K increased to 0.1 m/d

K of current basement = 0.0000001 m/d

Numerical instability was experienced in all model runs. Convergence criteria were relaxed in an effort to stabilise the model. Despite this, none of the three approaches taken resulted in a model which converged.¹ The model instability is due to the very low permeability of the London Clay, and as a result, a simulated water table could not be established on the basis of the measured water levels.

The three scenarios selected were based on the results of the site investigation and best represented the conditions at the site. That none of the model scenarios were able to establish a water table supports the conclusion that there is not a consistent water table at the site and that the recorded water levels reflect localised pockets of water associated with fractures and sandy lenses in the Clay matrix.

¹ Model convergence indicates that the repeated calculations required in the model approach a common value, which is the modelled solution.

5 IMPACT ASSESSMENT

5.1 CONCEPTUAL UNDERSTANDING		
Geology	Superficials	No superficial deposits are known to exist at the Site (although artificial Made Ground is present).
	Bedrock	<p>The Site is located upon the London Clay Formation, described by the BGS as “a sedimentary bedrock comprising bioturbated or poorly laminated, slightly calcareous, silty to very silty clay, clayey silt and sometimes silt, with some layers of sandy clay”.</p> <p>According to the Site investigation borehole logs (Appendix B), BH3, BH3a, BH4 and BH5 indicate a depth of made ground between 1 and 4 m below ground level underlain by London Clay which is present to the bottom of each borehole. The maximum depth London Clay was recorded in was BH5 (the deepest borehole) at 40 mbgl.</p>
Aquifers	<p>The London Clay is classified as unproductive strata by the Environment Agency. The definition of this is as follows: “geological strata with low permeability that have negligible significance for water supply or river base flow”</p> <p>The borehole logs indicate that the London Clay beneath the Site contains localised lenses of fine sand and selenite crystals</p> <p>During the installation of BH3, BH3a and BH5 in June 2014, water was struck at depths of 58.2 mAOD, 58.2 mAOD² and 66.6 mAOD respectively. These rose to 67.03m AOD in BH3a and 73.86 mAOD in BH5 in October 2014 (see Appendix B). If these October levels were used to determine a groundwater level, the building would extend beneath the water table surface. However, given the nature of the London Clay beneath the Site and the conclusions of the modelling, it is believed that the water encountered in these boreholes was localised in pockets of more permeable strata. This statement is supported by the fact that no water was encountered in BH4 (see Appendix B).</p>	

Given the above conditions at the Site, it can be confirmed that the development will not have an impact on groundwater flows or groundwater levels.

² No datum was provided for BH3a, it was therefore assumed that it was the same as BH3

6 CONCLUSIONS

Potential impacts of the proposed basement development at the Pears Building have been considered as set out in the scope of works. The following summary conclusions are made.

6.1 Surface water

There is a low overall risk of surface water flooding at the Site

- The proposed development will alter the area of hard standing at the site however this will not have an impact on the volume of run-off generated by the site as the permeable areas are underlain by impermeable surfaces that direct the run-off into the local sewer. It is therefore unlikely there will be any impact to surface water flows in the surrounding area.
- There is unlikely to be any impact to flood risk in the local area.
- Two “lost” rivers run respectively 160 and 250 m to the east and south of the proposed development. Given that the entirety of the Site run-off will be directed into the adjacent sewer, there will therefore be no changes to the watercourse inflows.
- There have been reported incidents of surface water flooding within the vicinity of the site and in nearby streets, believed to be due to past sewer flooding events. However no sewer flooding incidents have been recorded at the site itself.

6.2 Groundwater

There is a low overall risk of groundwater flooding at the Site

- The proposed basement will be constructed to a depth of approximately 3.0 m below ground level (68.5 mAOD) into the underlying London Clay which is considered as unproductive strata.
- Groundwater was recorded during the site investigation in BH3 and BH5 respectively to the north east and south west of the Site. The water level in BH5 rose above Level 00 of the proposed basement in October 2014 (73.86 mAOD); however it is believed that this was localised and associated with fractures and sandy lenses within the Clay matrix.
- No water was recorded in BH4, which supports the statement that a consistent water table is not present beneath the Site.
- The overall risk from the proposed development is considered to be low, based on the absence of a groundwater table beneath the Site.

6.3 Recommendations

Precautions should be taken against sewer flooding at this location; however it is expected that mitigation measures implemented during the development will mean that the discharge to the sewer post development will be less than pre-development, reducing the impact on the sewer system.

REFERENCES

- ARUP, 2010.** Camden geological, hydrogeological and hydrological study. Ove Arup & Partners Ltd
- Bakewell, I. 2008.** North London Strategic Flood Risk Assessment
- Barton, N., 1992.** The Lost Rivers of London, revised edition. Historical Publications Ltd. London.
- BDP, 2014.** Telephone conversation with Andrew Rain on 20/08/14
- British Geological Survey, 2006.** *Guide to permeability indices*, Open Report CR/06/160N
- British Geological Survey, 2014.** Received June 2014 from <http://mapapps.bgs.ac.uk/geologyofbritain/home.html>.
- Camden Borough Council, 2011.** Camden Planning Guidance: Basements and lightwells. London Borough of Camden, CPG4.
- Environment Agency, 2000.** *The physical properties of minor aquifers in England and Wales*, Environment Agency R & D Publication 68.
- Environment Agency, 2014.** What's in your backyard website. Received from http://maps.environment-agency.gov.uk/wiyby/wiybyController?ep=maptopics&lang=_e, August 2014.
- GroundSure Flood, 2014.** Royal Free Hospital NHS Trust. London, NW3 2QG.
- London Borough of Camden, 2010.** Camden Geological, Hydrogeological and Hydrological Study.
- Hopkins Architects, 2014.** Stage C Report. RFC: The Pears building
- Ordnance survey mapping, 1:10,000.** © Crown copyright. All rights reserved. Licence number AL 100015683
- Soil Consultants Ltd, 2014.** Basement Impact Assessment: Screening and Scoping Report: "Land Stability".
- Thames Water, 2014.** Sewer Flooding History Enquiry – Royal Free Hospital. Ref: SF StH/SFH andard/2014_2783523

APPENDICES

APPENDIX A.1

Site plans before development



Note:
Some services may have been omitted due to parked vehicles.
The Ordnance Survey file is to be used as a guide only.

OS Buildings Surveyed Buildings

This survey has been orientated to the Ordnance Survey (O.S.) National Grid (OSGB36) via Global Navigational Satellite Systems (GNSS) and the O.S. Active Network (OS Net).

A true OSGB36 coordinate has been established near to the site centre via a transformation using the OSTN02 & OSMA02 transformation models.
The survey has been correlated to this point and a further one or more OSGB36 points established to create a true O.S. bearing for angle orientation.

No scale factor has been applied to the survey therefore the coordinates shown are arbitrary & not true O.S. Coordinates which have a scale factor applied.

Please refer to Survey Station Table to enable establishment of the on-site grid.

Building Survey Legend:

SHT 1.00 HHT 2.12	Sill Height from FFL Head Height from FFL.
SL 51.03m HL 52.82m	Sill Level from defined datum. Head Level from defined datum.
Susp CHt: 2.00 Struct CHt: 3.00	Suspended Ceiling Height from FFL. Structural Ceiling Height from FFL.
Susp Ceil: 30.00m Struct Ceil: 31.00m	Suspended Ceiling Level from datum. Structural Ceiling Level from datum.
IFL: 100.00m +100.00m	Internal Floor Level (General). Internal Floor Level (Specific).
Insertion Point	Insertion Point for overlay drawings of other floors or details.

Legend:

Buildings	Overhead Cables	IC	Inspection chamber	Boil	Boiler
Wall	Concrete edge	Plu	Pipe invert	IS	Internal Isolation
Arch line	Tarmac edge	Gu	Gully	BS	Blocked drain
Line marking	Glass verge	Bg	Back gully	VP	Van pipe
Drop kerb	Canopy/Overhang	DP	Down pipe	GL	Ground light
Concrete line	Target	Pipe	Pipe above ground	LS	Letter box
Station and Name	Station Level	MA	Masthead	LA	Ladder
100.000	Water level	WL	Water level	SL	Site
F1	Flood light	FL	Internal floor level	TH	Threshold
Tree / Bush / Sapling	Tree / Bush / Sapling	TL	Threshold level	SL	Step
Area of Undergrowth	Area of Undergrowth	EP	Electricity post	TH	Threshold
Woodland	Woodland	TL	Traffic light	BM	Bomb
Edge Level	Edge Level	BS	Bus stop	BT	British Telecom
Essex Level	Essex Level	BS	Bus stop	BT	British Telecom
Flat Roof Level	Flat Roof Level	SL	Step up	CH	Control box
Gate	Gate	EL	Earth rod	TT	Tackle
Water meter	Water meter	BM	Block drain	BT	British Telecom
Gas valve	Gas valve	CPS	Concrete paving slab	CVR	Cover
Iron Railings	Iron Railings	AV	Air valve	IC	Inspection chamber
Wire Mesh	Wire Mesh	ICU	Underfloor inspection	IC	Inspection chamber
Post & Rail	Post & Rail	RM	Reinforcing wall	UTL	Unable to lift
Post & Wire	Post & Wire	BB	Belted box	TCL	Tree canopy level
Chain Link	Chain Link	CTV	Cable in	G	Girth
Wooden Panels	Wooden Panels	MS	Master post	MS	Master post
Concrete Panels	Concrete Panels	Gr	Grass marker post	SL	Tree Slump
Steel Plate	Steel Plate	SL	Soft	CL	Cover level
				IS	Insertion point

Rev	Date	Description	Drawn	O. Ref.
-----	------	-------------	-------	---------

☐ Topographical Surveys ☐ Measured Building Surveys
☐ Site Engineering ☐ 3D Laser Scanning
☐ Utility / CCTV Surveys ☐ Revit & BIM Models

Rowan House
Duffield Road
Little Eaton
Derby
DE21 5DR
Tel (01332) 830044 Fax (01332) 830055
admin@greenhatch-group.co.uk
www.greenhatch-group.co.uk

St Albans Unit B, The Courtyard Alban Park St Albans Hertfordshire AL1 0LA T: (01727) 854481	Newcastle 24 Riverside Studios Ainslie Road St Albans Newcastle-U-Tyne NE4 7YL T: (01912) 736391	Poland ul. Panewnicka 91 40-701 Katowice Poland L 0048 32 202 2282 www.greenhatch.pl
--	--	---

CLIENT
Buro Four Project Services Ltd

PROJECT
Royal Free Hospital Pond Street London

TITLE
Car Park Level 01

SCALE A2@ 1: 200	DATE 30.04.14
DRAWN LR	QUALITY REF C749

Level datum OS GPS	Grid orientation OS GPS
Job number 19734	


Drawing No. 19734_02_P	Rev. 0
----------------------------------	------------------

Comments
This plan should only be used for its original purposes. Greenhatch Group accepts no responsibility for this plan if supplied to any party other than the original client.
All dimensions should be checked on site prior to design and construction.
Drainage information (where applicable) has been visually inspected from the surface and therefore should be treated as approximate only.
Notes:

Copyright Greenhatch Group, 06/07/13

APPENDIX A.2

Proposed site plans




Work Package	Cost Check	Info/Briefing	Tender	Contract	Construction

Date	Rev.	Description	Approved By
09.04.2014	A	First issue - for information and review	EF
17.04.2014	B	Second issue - for information and review	EF
22.04.2014	C	Third issue - for information and review	EF
23.04.2014	D	Car parking and stair access added	EF
08.05.2014	E	Subconsultant comments incorporated	EF

Date	Rev.	Description	Approved By

Project	The Pears Foundation Building
Subject	Level 01 Plan
Architects	Hopkins Architects Partnership LLP 27 Broadley Terrace, London, NW1 6LG T: 020 7724 1751 E: mail@hopkins.co.uk

Sort Code	Drawing Number	Rev.
A/RFRMR	SK_068	E
Date	09.04.2014	Scale 1:200 at A1



Work Package	Cost Check	Info/Briefing	Tender	Contract	Construction

Date	Rev.	Description	Approved By
16.09.2014	A	First Issue for Stage D design coordination	EF
03.10.2014	B	Stage D Submission	EF

Date	Rev.	Description	Approved By

Project	Pears Building
Subject	Long Section Section A-A
Architects	Hopkins Architects Partnership LLP 27 Broadley Terrace, London, NW1 6LG T: 020 7724 1751 E: mail@hopkins.co.uk

Sort Code	Drawing Number	Rev.
A/RFMR	4100	B
Date	16.09.2014	Scale 1:200 at A1




STAGE D

	Work Package	Cost Check	Info/Briefing	Tender	Contract	Construction	Date 16.09.2014	Rev. A	Description First issue for Stage D coordination	Approved By EF	Date	Rev.	Description	Approved By	Project	Pears Building	Sort Code	Drawing Number	Rev.
							03.10.2014	B	Stage D Submission	EF					Subject	Cross Section Section B-B	A/RFMR	4101	B
															Architects	Hopkins Architects Partnership LLP 27 Broadley Terrace, London, NW1 6LG T: 020 7724 1751 E: mail@hopkins.co.uk	Date	16.09.2014	Scale 1:200 at A1

APPENDIX B

Site Investigation BH logs



Site Layout and Investigation Locations Plan

Client: Royal Free Charity

Site: RFC – Institute of Immunology and Transplantation Phase 2

Scale: NTS

Figure No: 2

Job No: 27119

Source: BDP

BH	Installation type	Strike (mbgl)	Rise (20min) (mbgl)	Monitoring Results (mbgl)			
				16/7/14	25/7/14	3/10/14	14/10/14
BH3 (original investigation)	Not Installed	10.50	10.40	-	-	-	-
BH3A (additional borehole)	38mm standpipe (12.5mbgl)	4.20	-	NA	NA	1.89	1.42
		10.50	10.40				
BH4 (original investigation)	50mm standpipe (3.0mbgl)	Dry	Dry	Dry	Dry	Dry	Dry
BH5 (original investigation)	Vibrating wire piezometer (14mbgl)	11.20	11.10	5.31*	4.83*	No record	No record
	50mm monitoring standpipe (2.0mbgl)			Dry	Dry	Dry	Dry
	19mm monitoring pipe (11.0mbgl)			4.23	4.28	3.89	3.74

Contract: RFT Institute of Immunology and Transplantation			Client: Royal Free Charity		Borehole: BH1
Contract Ref: 27119	Start: 24.06.14 End: 25.06.14	Ground Level: 75.00	Co-ordinates: ---		Sheet: 1 of 1

Samples and In-situ Tests				Water	Backfill	Description of Strata	Reduced Level	Depth (Thickness)	Material Graphic Legend
Depth	No	Type	Results						
0.50	D1	D				MADE GROUND: Low rise vegetation over brown slightly clayey gravelly SAND. Gravel is fine to coarse angular to subrounded flint brick and concrete.	74.50	(0.50)	
1.00	D2	D				MADE GROUND: Firm to stiff brown slightly sandy slightly gravelly CLAY. Gravel is fine to coarse angular to subrounded flint brick and concrete.	74.00	(0.50)	
1.50-1.95	1	SPT	N=4			MADE GROUND: Brown locally dark brown slightly sandy slightly gravelly CLAY. Gravel is fine to coarse angular to subrounded flint brick and concrete with occasional cobbles of brick and concrete		(1.50)	
2.00	D3	D					72.50	2.50	
2.50-2.95	2	SPT	N=12			MADE GROUND: Brown very clayey gravelly SAND. Gravel is fine to coarse angular to subrounded flint brick and concrete		(1.00)	
3.00	D4	D					71.50	3.50	
3.50-3.95	3	SPT	N=6			MADE GROUND: Brown locally dark brown slightly sandy slightly gravelly CLAY. Gravel is fine to coarse angular to subrounded flint brick and concrete with occasional cobbles of brick and concrete		(3.50)	
4.00	D5	D							
4.50-4.95	U1	U ₍₁₀₀₎	17 blows						
5.00	D6	D							
5.50	D7	D							
6.00-6.45	4	SPT	N=7						
6.50	D8	D							
7.00	D9	D				MADE GROUND: Concrete			

Boring Progress and Water Observations						Chiselling / Slow Progress			General Remarks
Date	Time	Borehole Depth	Casing Depth	Borehole Diameter (mm)	Water Depth	From	To	Duration (hh:mm)	
									1. Borehole cased to 6.80m 2. Groundwater encountered at 7.00m 3. Backfilled upon completion
Method Used: Cable percussion						Plant Used: Dando 1000 (cut down)			All dimensions in metres
Drilled By: GEH						Logged By: JPearson			Scale: 1:50
Checked By: AGS									



BOREHOLE LOG

Contract: RFT Institute of Immunology and Transplantation		Client: Royal Free Charity		Borehole: BH1C	
Contract Ref: 27119		Start: 27.06.14 End: 30.06.14	Ground Level: ---	Co-ordinates: ---	Sheet: 1 of 2

Samples and In-situ Tests				Water	Backfill	Description of Strata	Reduced Level	Depth (Thickness)	Material Graphic Legend
Depth	No	Type	Results						
						Clay and brick fill		(8.30)	
						Concrete		8.30	

Boring Progress and Water Observations						Chiselling / Slow Progress			General Remarks
Date	Time	Borehole Depth	Casing Depth	Borehole Diameter (mm)	Water Depth	From	To	Duration (hh:mm)	
						All dimensions in metres			Scale: 1:50
Method Used: Cable percussion			Plant Used: Dando 1000 (cut down)			Drilled By: GEH		Logged By: JPearson	Checked By:

[illegible]

CB_LIBRARY_v8_05.GLB LibVersion: v8_05 - Core+Logs 0003 | Log CABLE PERCUSSION LOG | 27119_RFH.GPJ - v8_05 | 19/08/14 - 15:51 | CB_



BOREHOLE LOG

Contract: RFT Institute of Immunology and Transplantation		Client: Royal Free Charity		Borehole: BH1D	
Contract Ref: 27119		Start: 30.06.14 End: 30.06.14	Ground Level: ---	Co-ordinates: ---	Sheet: 1 of 2

Samples and In-situ Tests				Water	Backfill	Description of Strata	Reduced Level	Depth (Thickness)	Material Graphic Legend
Depth	No	Type	Results						
1.20	1	B				Topsoil		(3.00)	
						Clay and brick fill		3.00	
								(7.00)	

Boring Progress and Water Observations						Chiselling / Slow Progress			General Remarks	
Date	Time	Borehole Depth	Casing Depth	Borehole Diameter (mm)	Water Depth	From	To	Duration (hh:mm)		
									1. Borehole cased to 2.60m 2. Groundwater not encountered during drilling	
									All dimensions in metres	Scale: 1:50
Method Used: Cable percussion			Plant Used: Dando 1000 (cut down)			Drilled By: GEH		Logged By: JPearson	Checked By:	

[illegible]

CB_LIBRARY_v8_05.GLB LibVersion: v8_05 - Core+Logs 0003 | Log CABLE PERCUSSION LOG | 27119_RFH.GPJ - v8_05 | 19/08/14 - 15:51 | CB_








BOREHOLE LOG

Contract: RFT Institute of Immunology and Transplantation			Client: Royal Free Charity		Borehole: BH3
Contract Ref: 27119	Start: 21.06.14 End: 21.06.14	Ground Level: 68.45	Co-ordinates: ---		Sheet: 1 of 2

Samples and In-situ Tests				Water	Backfill	Description of Strata	Reduced Level	Depth (Thickness)	Material Graphic Legend
Depth	No	Type	Results						
0.50	D1	D				MADE GROUND: Compacted black sand and gravel bound layer	68.40	0.05	
						MADE GROUND: Light grey concrete composed of approximately 30% flint aggregate	68.15	0.30	
						MADE GROUND: Clay, gravel and brick fill			
1.00	D2	D				Firm brown grey silty CLAY with occasional fine gravel		(0.60)	
1.50-1.95	U1	U ₍₁₀₀₎	20 blows						
2.00	D3	D							
2.50-2.95	1	SPT	N=9					(3.30)	
3.00	D4	D				Firm to stiff dark grey brown silty CLAY (LONDON CLAY FORMATION)			
3.50-3.95	U2	U ₍₁₀₀₎	21 blows						
4.00	D5	D					64.25	4.20	
4.50-4.95	2	SPT	N=17						
5.25	D6	D							
6.00-6.45	U3	U ₍₁₀₀₎	25 blows						
6.50	D7	D						(5.80)	
7.25	D8	D							
7.50-7.95	3	SPT	N=15						
8.25	D9	D							

Boring Progress and Water Observations						Chiselling / Slow Progress			General Remarks
Date	Time	Borehole Depth	Casing Depth	Borehole Diameter (mm)	Water Depth	From	To	Duration (hh:mm)	
									1. Borehole cased to 1.50m 2. Groundwater strike at 10.50m 3. Backfilled upon completion
Method Used: Cable percussion						Plant Used: Dando 1000 (cut down)			All dimensions in metres
Drilled By: GEH						Logged By: JPearson			Scale: 1:50
Checked By: AGS									



Samples and In-situ Tests				Water	Backfill	Description of Strata	Reduced Level	Depth (Thickness)	Material Graphic Legend	
Depth	No	Type	Results							
9.00-9.45	U4	U ₍₁₀₀₎	29 blows			Firm to stiff dark grey brown silty CLAY (LONDON CLAY FORMATION) <i>(stratum copied from 4.20m from previous sheet)</i>				
9.50	D10	D						58.45	10.00	
10.25	D11	D							(1.00)	
10.50-10.95	4	SPT	N=24						57.45	11.00

CSK Environment Ltd, 18 Frogmore Road, Hemel Hempstead, Hertfordshire, HP3 9RT. Tel: 01442 437500, Fax: 01442 437550, Web: www.rsk.co.uk



BOREHOLE LOG

Contract: RFT Institute of Immunology and Transplantation			Client: Royal Free Charity		Borehole: BH4
Contract Ref: 27119	Start: 17.06.14 End: 19.06.14	Ground Level: 72.20	Co-ordinates: ---		Sheet: 1 of 3

Samples and In-situ Tests				Water	Backfill & Instrumentation	Description of Strata	Reduced Level	Depth (Thickness)	Material Graphic Legend
Depth	No	Type	Results						
0.50	B1	B				MADE GROUND: Dark brown clayey sandy GRAVEL. Gravel is fine to coarse angular to subrounded flint brick and concrete with occasional cobbles of concrete	71.50	(0.70)	
1.00	D1	D				MADE GROUND: Brown slightly clayey slightly sandy GRAVEL. Gravel is fine to coarse angular to subrounded flint brick and concrete with common cobbles of concrete and whole bricks		(1.20)	
1.50	B2	B					70.30	1.90	
2.00	D2	D				Firm to stiff light brown silty CLAY with localised lenses of fine sand and selenite crystals throughout. (LONDON CLAY FORMATION)			
2.50-3.00	U1	U ₍₁₀₀₎	21 blows						
3.50-3.95	1	SPT	N=14					(3.60)	
4.00	D3	D							
4.50-4.95	U2	U ₍₁₀₀₎	30 blows						
5.00	D4	D							
5.40	D5	D				... claystone band between 5.40m and 5.50m	66.70	5.50	
5.50-5.95	2	SPT	N=14			Firm to stiff dark grey brown silty CLAY with localised lenses of fine sand and selenite crystals throughout. (LONDON CLAY FORMATION)			
6.25	D6	D							
7.00-7.45	U3	U ₍₁₀₀₎	35 blows						
7.50	D7	D						(5.30)	
8.25	D8	D							
8.50-8.95	3	SPT	N=18						

Boring Progress and Water Observations						Chiselling / Slow Progress			General Remarks
Date	Time	Borehole Depth	Casing Depth	Borehole Diameter (mm)	Water Depth	From	To	Duration (hh:mm)	
									1. Borehole cased to 1.50m 2. Water not encountered during drilling 3. 50mm diameter installation to 2.80m
									All dimensions in metres
									Scale: 1:50
Method Used: Cable percussion			Plant Used: Dando 1000 (cut down)			Drilled By: GEH		Logged By: JPearson	Checked By:



BOREHOLE LOG

Contract: RFT Institute of Immunology and Transplantation			Client: Royal Free Charity		Borehole: BH4
Contract Ref: 27119	Start: 17.06.14 End: 19.06.14	Ground Level: 72.20	Co-ordinates: ---		Sheet: 2 of 3

Samples and In-situ Tests				Water	Backfill & Instru- mentation	Description of Strata	Reduced Level	Depth (Thick- ness)	Material Graphic Legend
Depth	No	Type	Results						
9.25	D9	D				Firm to stiff dark grey brown silty CLAY with localised lenses of fine sand and selenite crystals throughout. (LONDON CLAY FORMATION) <i>(stratum copied from 5.50m from previous sheet)</i>			
10.00-10.45	U4	U ₍₁₀₀₎	39 blows						
10.50	D10	D					61.40	10.80	
11.25	D11	D				Stiff to very stiff dark grey brown silty CLAY with rare lenses of fine sand and selenite crystals throughout. (LONDON CLAY FORMATION)			
11.50-11.95	4	SPT	N=26						
12.25	D12	D							
13.00-13.45	U5	U ₍₁₀₀₎	46 blows						
13.50	D13	D							
14.25	D14	D							
14.50-14.95	5	SPT	N=28						
15.25	D15	D							
16.00-16.45	U6	U ₍₁₀₀₎	46 blows						
16.50	D16	D							
17.25	D17	D							
17.50-17.95	6	SPT	N=30					(14.20)	

Boring Progress and Water Observations						Chiselling / Slow Progress			General Remarks	
Date	Time	Borehole Depth	Casing Depth	Borehole Diameter (mm)	Water Depth	From	To	Duration (hh:mm)		
									</	



BOREHOLE LOG

Contract: RFT Institute of Immunology and Transplantation			Client: Royal Free Charity		Borehole: BH4
Contract Ref: 27119	Start: 17.06.14 End: 19.06.14	Ground Level: 72.20	Co-ordinates: ---		Sheet: 3 of 3

Samples and In-situ Tests				Water	Backfill & Instrumentation	Description of Strata	Reduced Level	Depth (Thickness)	Material Graphic Legend
Depth	No	Type	Results						
19.00-19.45	U7	U ₍₁₀₀₎	49 blows			Stiff to very stiff dark grey brown silty CLAY with rare lenses of fine sand and selenite crystals throughout. (LONDON CLAY FORMATION) (stratum copied from 10.80m from previous sheet)			
19.50	D18	D							
20.25	D19	D							
20.50-20.95	7	SPT	N=32						
21.25	D20	D							
22.00-22.45	U8	U ₍₁₀₀₎	51 blows						
22.50	D21	D							
23.50-23.95	8	SPT	N=36						
24.25	D22	D							
24.50-24.95	U9	U ₍₁₀₀₎	54 blows						
25.00	D23	D					47.20	25.00	

Boring Progress and Water Observations						Chiselling / Slow Progress			General Remarks	
Date	Time	Borehole Depth	Casing Depth	Borehole Diameter (mm)	Water Depth	From	To	Duration (hh:mm)		



BOREHOLE LOG

Contract: RFT Institute of Immunology and Transplantation			Client: Royal Free Charity		Borehole: BH5
Contract Ref: 27119	Start: 01.07.14 End: 04.07.14	Ground Level: 77.60	Co-ordinates: ---		Sheet: 1 of 5

Samples and In-situ Tests				Water	Backfill & Instrumentation	Description of Strata	Reduced Level	Depth (Thickness)	Material Graphic Legend
Depth	No	Type	Results						
						MADE GROUND: Low rise vegetation over brown slightly clayey gravelly SAND. Gravel is fine to coarse angular to subrounded flint brick and concrete.	77.40	0.20	
						MADE GROUND: Dark brown slightly gravelly CLAY. Gravel is fine to coarse angular to subrounded flint brick and concrete with occasional cobbles of brick and concrete		(1.00)	
							76.40	1.20	
1.20	B1	B	N=16			Firm to stiff light brown silty CLAY with localised lenses of fine sand and selenite crystals throughout. (LONDON CLAY FORMATION)			
1.50-1.95	1	SPT							
2.50-3.00	U1	U	N=12						
3.20	D1	D							
3.50-3.95	2	SPT							
4.30	D2	D	N=10						
4.50-5.00	U2	U							
5.20	D3	D							
5.50-5.95	3	SPT							
6.50	D4	D							
7.50-8.00	U3	U							
							68.60	9.00	

Boring Progress and Water Observations						Chiselling / Slow Progress			General Remarks
Date	Time	Borehole Depth	Casing Depth	Borehole Diameter (mm)	Water Depth	From	To	Duration (hh:mm)	
									1. Borehole cased to 12.05m 2. Groundwater strike at 11.20m 3. Vibrating Wire Piezometer installed at 14.00m depth 4. 19mm diameter standpipe installed to 11.00m 5. 50mm diameter standpipe installed to 2.00m
Method Used: Cable percussion						Plant Used: Dando 1000 (cut down)			All dimensions in metres
Drilled By: GEH						Logged By: JPearson			Scale: 1:50
Checked By: AGS									



BOREHOLE LOG

Contract: RFT Institute of Immunology and Transplantation			Client: Royal Free Charity		Borehole: BH5
Contract Ref: 27119	Start: 01.07.14 End: 04.07.14	Ground Level: 77.60	Co-ordinates: ---		Sheet: 2 of 5




Samples and In-situ Tests				Water	Backfill & Instru- mentation	Description of Strata	Reduced Level	Depth (Thick- ness)	Material Graphic Legend
Depth	No	Type	Results						
9.00-9.45	4	SPT	N=28			Stiff to very stiff dark grey brown silty CLAY with rare lenses of fine sand and selenite crystals throughout. (LONDON CLAY FORMATION)			
9.80	D5	D							
10.50-11.00	U4	U							
11.50	D6	D							
12.00-12.45	5	SPT	N=31						
14.00-14.45	U5	U ₍₁₀₀₎	31 blows						
14.50	D8	D							
15.25	D9	D							
15.50-15.95	6	SPT	N=28						
16.25	D10	D							
17.00-17.45	U6	U ₍₁₀₀₎	34 blows						
17.50	D11	D							

Boring Progress and Water Observations						Chiselling / Slow Progress			General Remarks		
Date	Time	Borehole Depth	Casing Depth	Borehole Diameter (mm)	Water Depth	From	To	Duration (hh:mm)			
Method Used: Cable percussion						Plant Used: Dando 1000 (cut down)		Drilled By: GEH		Logged By: JPearson	Checked By: AGS



BOREHOLE LOG

Contract: RFT Institute of Immunology and Transplantation			Client: Royal Free Charity		Borehole: BH5
Contract Ref: 27119	Start: 01.07.14 End: 04.07.14	Ground Level: 77.60	Co-ordinates: ---		Sheet: 3 of 5





Samples and In-situ Tests				Water	Backfill & Instru- mentation	Description of Strata	Reduced Level	Depth (Thick- ness)	Material Graphic Legend
Depth	No	Type	Results						
18.25	D12	D	N=29		Stiff to very stiff dark grey brown silty CLAY with rare lenses of fine sand and selenite crystals throughout. (LONDON CLAY FORMATION) (stratum copied from 9.00m from previous sheet)			(31.00)	
18.50-18.95	7	SPT							
19.25	D13	D							
20.00-20.45	U7	U ₍₁₀₀₎							
20.50	D14	D							
21.25	D15	D							
21.50-21.95	8	SPT	N=34						
22.25	D16	D							
23.00-23.45	U8	U ₍₁₀₀₎	41 blows						
23.50	D17	D							
24.00	D18	D							
24.25	D19	D							
24.50-24.95	9	SPT	N=37						
25.25	D20	D							
26.00-26.45	U9	U ₍₁₀₀₎	46 blows						
26.50	D21	D							

Boring Progress and Water Observations						Chiselling / Slow Progress			General Remarks		
Date	Time	Borehole Depth	Casing Depth	Borehole Diameter (mm)	Water Depth	From	To	Duration (hh:mm)			
Method Used: Cable percussion						Plant Used: Dando 1000 (cut down)		Drilled By: GEH		Logged By: JPearson	Checked By: AGS



BOREHOLE LOG

Contract: RFT Institute of Immunology and Transplantation			Client: Royal Free Charity		Borehole: BH5
Contract Ref: 27119	Start: 01.07.14 End: 04.07.14	Ground Level: 77.60	Co-ordinates: ---		Sheet: 4 of 5

Samples and In-situ Tests				Water	Backfill & Instru- mentation	Description of Strata	Reduced Level	Depth (Thick- ness)	Material Graphic Legend
Depth	No	Type	Results						
27.25	D22	D	N=39		Stiff to very stiff dark grey brown silty CLAY with rare lenses of fine sand and selenite crystals throughout. (LONDON CLAY FORMATION) (stratum copied from 9.00m from previous sheet)				
27.50-27.95	10	SPT							
28.25	D23	D							
29.00-29.45	U10	U ₍₁₀₀₎	50 blows						
29.50	D24	D							
30.25	D25	D							
30.50-30.95	11	SPT	N=40						
31.25	D26	D							
32.00-32.45	U11	U ₍₁₀₀₎							
32.50	D27	D	50 blows						
33.25	D28	D							
33.50-33.95	12	SPT							
34.25	D29	D	N=41						
35.00-35.45	U12	U ₍₁₀₀₎							
35.50	D30	D							

Boring Progress and Water Observations						Chiselling / Slow Progress			General Remarks	
Date	Time	Borehole Depth	Casing Depth	Borehole Diameter (mm)	Water Depth	From	To	Duration (hh:mm)		



BOREHOLE LOG


Contract: RFT Institute of Immunology and Transplantation			Client: Royal Free Charity		Borehole: BH5
Contract Ref: 27119	Start: 01.07.14 End: 04.07.14	Ground Level: 77.60	Co-ordinates: ---		Sheet: 5 of 5

Samples and In-situ Tests				Water	Backfill & Instrumentation	Description of Strata	Reduced Level	Depth (Thickness)	Material Graphic Legend
Depth	No	Type	Results						
36.25	D31	D	N=47			Stiff to very stiff dark grey brown silty CLAY with rare lenses of fine sand and selenite crystals throughout. (LONDON CLAY FORMATION) (stratum copied from 9.00m from previous sheet)			
36.50-36.95	13	SPT							
37.25	D32	D	62 blows						
38.00-38.45	U13	U ₍₁₀₀₎							
38.50	D33	D							
39.25	D34	D	N=90*						
39.50-39.80	14	SPT							
						. . . claystone band between 39.80m and 40.00m	37.60	40.00	

Boring Progress and Water Observations						Chiselling / Slow Progress			General Remarks	
Date	Time	Borehole Depth	Casing Depth	Borehole Diameter (mm)	Water Depth	From	To	Duration (hh:mm)		

Contract: RFT Institute of Immunology and Transplantation			Client: Royal Free Charity		Borehole: BH3A
Contract Ref: 27119	Start: 12.09.14 End: 13.09.14	Ground Level: ---	Co-ordinates: ---		Sheet: 1 of 3

Samples and In-situ Tests				Water	Backfill & Instrumentation	Description of Strata	Reduced Level	Depth (Thickness)	Material Graphic Legend
Depth	No	Type	Results						
0.50	B1	B				MADE GROUND: Weak black tar bound MACADAM.		0.12	
						MADE GROUND: Weak light brownish grey (unreinforced) CONCRETE. 30-40% aggregate of angular to well rounded fine to medium flint.		0.45	
1.00-1.45	U1	U	19 blows			MADE GROUND: Grey slightly sandy gravelly CLAY. Sand is fine to coarse. Gravel is angular to subrounded fine to coarse of concrete and flint.		0.90	
2.00-2.45	1	SPT	N=6			Firm to stiff brown locally fissured silty CLAY. Frequent relict rootlets with local blue grey gleying. Occasional clusters of fine to coarse sand sized selenite crystals. Fissures are extremely closely to closely spaced. (WEATHERED LONDON CLAY FORMATION)			
2.50	D1	D							
3.00-3.45	U2	U	23 blows						
4.00-4.45	2	SPT	N=11					(6.10)	
4.50	D2	D							
5.00-5.45	U3	U	25 blows						
6.00	D3	D							
6.50-6.95	3	SPT	N=12						
7.50	D4	D				... at 6.80m becoming brownish grey		7.00	
8.00-8.45	U4	U	34 blows			Firm to stiff indistinctly fissured dark greyish brown silty CLAY. Fissures are randomly orientated. (LONDON CLAY FORMATION)			
								(4.00)	


Boring Progress and Water Observations						Chiselling / Slow Progress			General Remarks		
Date	Time	Borehole Depth	Casing Depth	Borehole Diameter (mm)	Water Depth	From	To	Duration (hh:mm)			
			- -		4.20 10.50						
Method Used: Cable percussion						Plant Used: Cable tool rig			All dimensions in metres		Scale: 1:50
Drilled By: GEH			Logged By: TJohnson			Checked By: AGS					






BOREHOLE LOG

Contract: RFT Institute of Immunology and Transplantation			Client: Royal Free Charity		Borehole: BH3A
Contract Ref: 27119	Start: 12.09.14 End: 13.09.14	Ground Level: ---	Co-ordinates: ---		Sheet: 2 of 3

Samples and In-situ Tests				Water	Backfill & Instrumentation	Description of Strata	Reduced Level	Depth (Thickness)	Material Graphic Legend
Depth	No	Type	Results						
9.25	D5	D	N=19			Firm to stiff indistinctly fissured dark greyish brown silty CLAY. Fissures are randomly orientated. (LONDON CLAY FORMATION) (stratum copied from 7.00m from previous sheet) ... at 9.80 to 9.90m locally sandy ... at 10.50m CLAYSTONE			
9.50-9.95	4	SPT							
10.25	D6	D	43 blows			Stiff to very stiff dark grey silty CLAY. Occasional lenses of fine slightly micaceous silty sand.		11.00	
11.00-11.45	U5	U							
12.25	D7	D	N=23						
12.50-12.95	5	SPT							
15.50-15.95	6	SPT	N=25					(14.00)	

Boring Progress and Water Observations						Chiselling / Slow Progress			General Remarks		
Date	Time	Borehole Depth	Casing Depth	Borehole Diameter (mm)	Water Depth	From	To	Duration (hh:mm)			
Method Used: Cable percussion						Plant Used: Cable tool rig			All dimensions in metres		Scale: 1:50
Drilled By: GEH			Logged By: TJohnson			Checked By:					



Samples and In-situ Tests				Water	Backfill & Instrumentation	Description of Strata	Reduced Level	Depth (Thick ness)	Material Graphic Legend
Depth	No	Type	Results						
18.50-18.95	7	SPT	N=29			Stiff to very stiff dark grey silty CLAY. Occasional lenses of fine slightly micaceous silty sand. <i>(stratum copied from 11.00m from previous sheet)</i>			
21.50-21.95	8	SPT	N=34						
24.50-24.95	9	SPT	N=43						
						Terminated at 25.00m.		25.00	

CB.LIBRARY_v8_05.GLB LibVersion: v8_05 - Core+Logs 0003 | Log CABLE PERCUSSION LOG | 27119 RFH.GPJ_-v8_05 | 25/09/14 - 14:38 | CB.



WINDOW SAMPLE LOG

Contract: RFT Institute of Immunology and Transplantation		Client: Royal Free Charity		Window Sample: WS1	
Contract Ref: 27119		Start: 18.06.14 End: 18.06.14		Ground Level: --- Co-ordinates: ---	
Sheet: 1 of 1					

Progress	Samples / Tests				Water	Backfill	Description of Strata	Depth (Thickness)	Material Graphic Legend
Window Run	Depth	No	Type	Results					
	0.20	1	ES	Tub+J+VL			MADE GROUND: Soft brown slightly sandy slightly gravelly CLAY. Gravel is fine to coarse angular to subrounded flint brick concrete and bituminous material with occasional cobble clast of concrete and whole bricks	(0.85)	
	0.50	2	ES	Tub+J+VL				0.85	
	0.90	3	ES	Tub+J+VL			MADE GROUND: Dark brown grey slightly clayey gravelly SAND. Gravel is fine to coarse angular to subrounded flint brick concrete and bituminous material with common cobble clast of concrete and brick	(0.45)	
							MADE GROUND: Light orange brown slightly sandy slightly gravelly CLAY. Gravel is fine to coarse angular to subrounded flint brick concrete and bituminous material with occasional cobble clast of concrete and brick	(0.70)	
								2.00	

Drilling Progress and Water Observations						General Remarks	
Date	Time	Borehole Depth (m)	Casing Depth (m)	Borehole Diameter (mm)	Water Depth (m)		
						1. Groundwater was not encountered 2. Backfilled and compacted using arisings	
All dimensions in metres						Scale:	1:25
Method Used:	Tracked window sampling		Plant Used:	Archway Competitor		Drilled By:	???
						Logged By:	JPearson
						Checked By:	AGS

[illegible]

GINT LIBRARY_v8_05.GLB LibVersion: v8_05 - Lib0004 PriVersion: v8_05 - Core+Logs 0003 | Log WINDOW SAMPLE LOG | 27119_RFH.GPJ - v8_05 | 15/07/14 - 16:00 | JP.
RISK Environment Ltd, 18 Frogmore Road, Hemel Hempstead, Hertfordshire, HP3 9RT. Tel: 01442 437500, Fax: 01442 437550, Web: www.risk.co.uk.



WINDOW SAMPLE LOG

Contract: RFT Institute of Immunology and Transplantation			Client: Royal Free Charity		Window Sample: WS3
Contract Ref: 27119	Start: 18.06.14 End: 18.06.14	Ground Level: ---	Co-ordinates: ---		Sheet: 1 of 1

Progress	Samples / Tests				Water	Backfill	Description of Strata	Depth (Thickness)	Material Graphic Legend
Window Run	Depth	No	Type	Results					
							MADE GROUND: Compacted black sand and gravel bound layer	0.05	
	0.20	1	ES	Tub+J+VL			MADE GROUND: Light brown slightly silty gravelly SAND with common rootlets at the top of the unit. Gravel is fine to coarse angular to subrounded brick concrete and flint with occasional whole brick and cobble clasts of concrete.	(0.95)	
	0.50	2	ES	Tub+J+VL				1.00	
	1.10	3	ES	Tub+J+VL			MADE GROUND: Firm light brown mottled grey silty CLAY with occasional pocket of gravelly sand. Gravel is fine to coarse angular to subrounded brick concrete and flint	(0.60)	
							Firm to stiff light brown mottled grey silty CLAY with occasional pocket of slightly gravelly sand.	1.60	
								(2.40)	
								4.00	

Drilling Progress and Water Observations						General Remarks	
Date	Time	Borehole Depth (m)	Casing Depth (m)	Borehole Diameter (mm)	Water Depth (m)		
						1. Groundwater was not encountered 2. Backfilled and compacted using arisings	
All dimensions in metres						Scale:	1:25
Method Used:	Tracked window sampling		Plant Used:	Archway Competitor		Drilled By:	???
						Logged By:	JPearson
						Checked By:	AGS



WINDOW SAMPLE LOG

Contract: RFT Institute of Immunology and Transplantation			Client: Royal Free Charity		Window Sample: WS4
Contract Ref: 27119	Start: 18.06.14 End: 18.06.14	Ground Level: ---	Co-ordinates: ---		Sheet: 1 of 1

Progress		Samples / Tests			Water	Backfill	Description of Strata	Depth (Thickness)	Material Graphic Legend
Window Run	Depth	No	Type	Results					
	0.20	1	ES	Tub+J+VL			MADE GROUND: Low rise vegetation over brown slightly clayey gravelly SAND. Gravel is fine to coarse angular to subrounded flint brick and concrete.	(0.60)	
	0.40	2	ES	Tub+J+VL				0.60	
	0.80	3	ES	Tub+J+VL			MADE GROUND: Firm to stiff brown slightly sandy slightly gravelly CLAY. Gravel is fine to coarse angular to subrounded flint brick and concrete with occasional fragments of rubber and metal	(1.10)	
	1.60	4	ES	Tub+J+VL				1.70	
							MADE GROUND: Brown locally clayey sandy GRAVEL. Gravel is fine to coarse angular to subrounded flint brick and concrete.	1.80	

Drilling Progress and Water Observations						General Remarks
Date	Time	Borehole Depth (m)	Casing Depth (m)	Borehole Diameter (mm)	Water Depth (m)	
						1. Groundwater was not encountered 2. Backfilled and compacted using arisings



WINDOW SAMPLE LOG

Contract: RFT Institute of Immunology and Transplantation		Client: Royal Free Charity		Window Sample: WS5	
Contract Ref: 27119		Start: 18.06.14 End: 18.06.14		Ground Level: --- Co-ordinates: ---	
				Sheet: 1 of 1	




Progress	Samples / Tests				Water	Backfill	Description of Strata	Depth (Thickness)	Material Graphic Legend
Window Run	Depth	No	Type	Results					
	0.20	1	ES	Tub+J+VL			MADE GROUND: Low rise vegetation over brown slightly clayey gravelly SAND. Gravel is fine to coarse angular to subrounded flint brick and concrete.	(0.80)	
	0.50	2	ES	Tub+J+VL				0.80	
	0.90	3	ES	Tub+J+VL			MADE GROUND: Firm to stiff brown slightly sandy slightly gravelly CLAY. Gravel is fine to coarse angular to subrounded flint brick and concrete.	(0.90)	
	1.70	4	ES	Tub+J+VL			MADE GROUND: Brown locally clayey sandy GRAVEL. Gravel is fine to coarse angular to subrounded flint brick and concrete with occasional fragment of metal.	1.70 1.80	

Drilling Progress and Water Observations						General Remarks			
Date	Time	Borehole Depth (m)	Casing Depth (m)	Borehole Diameter (mm)	Water Depth (m)				
						1. Groundwater was not encountered 2. Backfilled and compacted using arisings			
						All dimensions in metres		Scale:	1:25
Method Used:	Tracked window sampling		Plant Used:	Archway Competitor		Drilled By:	???	Logged By:	JPearson
						Checked By:			

[illegible]

GINT LIBRARY_v8_05.GLB LibVersion: v8_05 - Lib0004 PriVersion: v8_05 - Core+Logs 0003 | Log WINDOW SAMPLE LOG | 27119_RFH.GPJ - v8_05 | 15/07/14 - 16:00 | JP.
RISK Environment Ltd, 18 Frogmore Road, Hemel Hempstead, Hertfordshire, HP3 9RT. Tel: 01442 437500, Fax: 01442 437550, Web: www.risk.co.uk.



Samples and In-situ Tests				Water	Backfill	Description of Strata	Depth (Thick ness)	Material Graphic Legend
Depth	No	Type	Results					
0.20	1	ES	Tub+J+VL			MADE GROUND: Soft dark brown sandy slightly gravelly CLAY with fragments of wood and rootlets throughout. Gravel is fine to coarse angular to subrounded flint brick concrete and bituminous material with occasional cobble clast of concrete and brick	(0.30) 0.30	
0.40	2	ES	Tub+J+VL			MADE GROUND: Soft brown slightly sandy slightly gravelly CLAY. Gravel is fine to coarse angular to subrounded flint brick concrete and bituminous material with occasional cobble clast of concrete and whole bricks	(0.30) 0.60	
1.00	3	ES	Tub+J+VL			MADE GROUND: Dark brown clayey gravelly SAND with occasional fragment of metal plastic and wire. Gravel is fine to coarse angular to subrounded flint brick concrete and bituminous material with common cobble clast of concrete and whole bricks	(0.80) 1.40	
1.50	4	ES	Tub+J+VL			MADE GROUND: Light orange brown silty slightly gravelly CLAY. Gravel is fine to coarse angular to subrounded flint brick concrete and bituminous material with occasional cobble clast of concrete and brick	(0.75) 2.15	

1. Pit remained generally stable although some minor pit instability was encountered
2. Groundwater was not encountered
3. Backfilled and compacted using arisings

RSK ENVIRONMENT LTD
v8_05 - Lib0004
v8_05 - Core+Logs 0003
Log TRIAL PIT LOG - NO PLAN
27119_RFH.GPJ - v8_05
15/07/14 - 16:01
JP.
RSC Environment Ltd, 18 Frogmore Road, Hemel Hempstead, Hertfordshire, HP3 9RT. Tel: 01442 437550, Fax: 01442 437550, Web: www.rsk.co.uk

[illegible]

1. Pit remained stable throughout
2. Groundwater was not encountered
3. Backfilled and compacted using arisings

All dimensions in metres	Scale:	1:25
--------------------------	--------	-------------

RSK ENVIRONMENT LTD
v8_05 - Lib0004 PriVersion: v8_05 - Core+Logs 0003 | Log TRIAL PIT LOG - NO PLAN | 27119_RFH.GPJ - v8_05 | 15/07/14 - 16:01 | JP.
Hemel Hempstead, Hertfordshire, HP3 9RT. Tel: 01442 437550, Fax: 01442 437550, Web: www.rsk.co.uk

[illegible]

1. Pit remained stable throughout
2. Groundwater was not encountered
3. Backfilled and compacted using arisings

All dimensions in metres	Scale:	1:25
--------------------------	--------	-------------

JP. RSK Environment Ltd, 18 Frogmore Road, Hemel Hempstead, Hertfordshire, HP3 9RT. Tel: 01442 437500, Fax: 01442 437550, Web: www.rsk.co.uk

APPENDIX C

Thames Water Sewer Flooding Enquiry

Sewer Flooding

History Enquiry



Thames Water Property Searches

Vastern Road

Search address supplied Royal Free Hampstead Nhs Trust
Royal Free Hospital
Pond Street
London
NW3 2QG

Your reference 62361R1

Our reference SFH/SFH Standard/2014_2783523

Received date 5 June 2014

Search date 5 June 2014

Thames Water Utilities Ltd

Property Searches
PO Box 3189
Slough SL1 4WW

DX 151280 Slough 13

T 0118 925 1504
E searches@thameswater.co.uk
I www.thameswater-propertysearches.co.uk

Registered in England and Wales
No. 2366661, Registered office
Clearwater Court, Vastern Road
Reading RG1 8DB

Sewer Flooding

History Enquiry



Search address supplied: Royal Free Hampstead Nhs Trust, Royal Free Hospital, Pond Street, London, NW3 2QG

This search is recommended to check for any sewer flooding in a specific address or area

TWUL, trading as Property Searches, are responsible in respect of the following:-

- (i) any negligent or incorrect entry in the records searched;
- (ii) any negligent or incorrect interpretation of the records searched;
- (iii) and any negligent or incorrect recording of that interpretation in the search report
- (iv) compensation payments

Thames Water Utilities Ltd

Property Searches
PO Box 3189
Slough SL1 4WW

DX 151280 Slough 13

T 0118 925 1504
E searches@thameswater.co.uk
I www.thameswater-propertysearches.co.uk

Registered in England and Wales
No. 2366661, Registered office
Clearwater Court, Vastern Road
Reading RG1 8DB

Sewer Flooding

History Enquiry



History of Sewer Flooding

Is the requested address or area at risk of flooding due to overloaded public sewers?

The flooding records held by Thames Water indicate that there have been no incidents of flooding in the requested area as a result of surcharging public sewers.

For your guidance:

- A sewer is “overloaded” when the flow from a storm is unable to pass through it due to a permanent problem (e.g. flat gradient, small diameter). Flooding as a result of temporary problems such as blockages, siltation, collapses and equipment or operational failures are excluded.
- “Internal flooding” from public sewers is defined as flooding, which enters a building or passes below a suspended floor. For reporting purposes, buildings are restricted to those normally occupied and used for residential, public, commercial, business or industrial purposes.
- “At Risk” properties are those that the water company is required to include in the Regulatory Register that is presented annually to the Director General of Water Services. These are defined as properties that have suffered, or are likely to suffer, internal flooding from public foul, combined or surface water sewers due to overloading of the sewerage system more frequently than the relevant reference period (either once or twice in ten years) as determined by the Company’s reporting procedure.
- Flooding as a result of storm events proven to be exceptional and beyond the reference period of one in ten years are not included on the At Risk Register.
- Properties may be at risk of flooding but not included on the Register where flooding incidents have not been reported to the Company.
- Public Sewers are defined as those for which the Company holds statutory responsibility under the Water Industry Act 1991.
- It should be noted that flooding can occur from private sewers and drains which are not the responsibility of the Company. This report excludes flooding from private sewers and drains and the Company makes no comment upon this matter.
- For further information please contact Thames Water on Tel: 0845 9200 800 or website www.thameswater.co.uk

Thames Water Utilities Ltd

Property Searches
PO Box 3189
Slough SL1 4WW


DX 151280 Slough 13

T 0118 925 1504
E searches@thameswater.co.uk
I www.thameswater-propertysearches.co.uk

Registered in England and Wales
No. 2366661, Registered office
Clearwater Court, Vastern Road
Reading RG1 8DB

APPENDIX D

**Permeability plans - existing and
proposed**



Area Sq. m	Type of space
1013	Green - Permeable
183	Hard surface Impermeable
1796	Existing Building
1667	Road




BUILDING DESIGN PARTNERSHIP LTD SHALL HAVE NO RESPONSIBILITY FOR ANY USE MADE OF THIS DOCUMENT OTHER THAN FOR THAT WHICH IT WAS PREPARED AND ISSUED.
ALL DIMENSIONS SHOULD BE CHECKED ON SITE.
DO NOT SCALE FROM THIS DRAWING.
ANY DRAWING ERRORS OR DIVERGENCES SHOULD BE BROUGHT TO THE ATTENTION OF BUILDING DESIGN PARTNERSHIP LTD AT THE ADDRESS SHOWN BELOW.

NOTES

- KEY PLAN
- Site Boundary
- Existing footpath resurfaced in natural yorkstone setts
 - Existing trees retained with new understorey planting
 - Public Woodland Garden
 - Lift access to upper floor level
 - Terrace Colonade, natural yorkstone flags
 - Planted Terraces with 500mm high seating wall
 - Feature steps
 - Planting onto the Colonade level
 - Public footpath resurfaced in natural yorkstone setts
 - Hampstead Green meadow
 - Green Wall to service yard
 - Existing London Plane trees retained with understorey of proposed planting, embraced by new retaining wall.
 - Timber deck
 - Grass lawn
 - Steps and bleachers linking both gardens and providing informal seating.
 - Grass lawn
 - Bench seating against a planted wall edge
 - Raised planters with copses of Silver Birch and meadowgrass
 - Threshold of Rowland Hill Street and Rosslyn Hill resurfaced with reclaimed granite setts

- Area of permeable landscape to natural ground
- Area of impermeable Landscape via outlets to sewer

REVISION/DESCRIPTION	DATE	BY	CHKD BY	APPD BY
	KM	MS		22.05.14



BDP.

16 Brewhouse Yard
Clerkenwell
London, EC1V 4LJ
United Kingdom

T +44 (0)20 7812 8000
F +44 (0)20 7812 8399

www.bdp.com

PROJECT TITLE	The Pears Foundation Building
PROJECT NUMBER	P2005878
DRAWING TITLE	Landscape Masterplan Permeable & Impermeable Zones
DRAWING NO	(90)LP002
SCALE	1:200@A1
DATE	22.05.2014
REVISION	-