



Carefully demolished existing brick pier cleaning and keeping existing bricks for reuse. Replace broken bricks with new secondhand to match. Rebuild with traditional line mortar to match existing.

SINCLAIRJOHNSTON

Consulting Civil & Structural Engineers

93 Great Suffolk Street
London SE1 0BX
T: 020 7593 1900
F: 020 7593 1910
www.sinclairjohnston.co.uk

Hampstead Hill School
Pond Street

Remeadial Works

Rev	Date	Issued	Amendment
—	01.10.14	GPB	Issued for Approval
Status SCHEME DESIGN			
Drawn G Barbe			
Scale 1:20 at A3			
Project No./Drawing No.			Rev
8374/SK2			—