



Landmark Trees

ARBORICULTURAL IMPACT ASSESSMENT REPORT:

23 Downside Crescent
Belsize Park
London
NW3 2AN

REPORT PREPARED FOR:

Kelli and Robert Callow
36 Constantine Road
London
NW3 2NG

REPORT PREPARED BY

Adam Hollis
MSc ARB MICFor FArbor A MRICS C Env

Ref: BDA/23DWN/AIA/01

Date: 17th October 2014

The content and format of this report are for the exclusive use of the client. It may not be sold, lent, hired out or divulged to any third party, not directly involved in the subject matter without Landmark Trees' written consent

Web: www.landmarktrees.co.uk
e-mail: info@landmarktrees.co.uk
Tel: 0207 851 4544

London Office: 20 Broadwick Street, London, W1F 8HT

Registered Office: Grange Cottage, All Cannings, Devizes, Wiltshire, SN10 3NR

Landmark Trees is the trading name of Landmark trees Ltd. Registered in Wales. Reg No. 3882076



Section	Content	Page N°
1.0	SUMMARY	5
2.0	INTRODUCTION	6
3.0	OBSERVATIONS	8
4.0	DEVELOPMENT CONSTRAINTS	10
5.0	ARBORICULTURAL IMPACTS	13
6.0	DISCUSSION	14
7.0	CONCLUSION	16
8.0	RECOMMENDATIONS	17
9.0	REFERENCES	19

Appendices

APPENDIX 1	Survey Data	20
APPENDIX 2	Recommended Tree Works	22
APPENDIX 3	Tree Constraints Plan	24
APPENDIX 4	Impact Assessment Plan	26

Caveats

This report is primarily an arboricultural report. Whilst comments relating to matters involving built structures or soil data may appear, any opinion thus expressed should be viewed as qualified, and confirmation from an appropriately qualified professional sought. Such points are usually clearly identified within the body of the report. It is not a full safety survey or subsidence risk assessment survey. These services can be provided but a further fee would be payable. Where matters of tree condition with a safety implication are noted during a survey they will of course appear in the report.

A tree survey is generally considered invalid in planning terms after 2 years, but changes in tree condition may occur at any time, particularly after acute (e.g. storm events) or prolonged (e.g. drought) environmental stresses or injuries (e.g. root severance). Routine surveys at different times of the year and within two - three years of each other (subject to the incidence of the above stresses) are recommended for the health and safety management of trees remote from highways or busy access routes. Annual surveys are recommended for the latter.

Tree works recommendations are found in the Appendices to this report. It is assumed, unless otherwise stated ("ASAP" or "Option to") that all husbandry recommendations will be carried out within 6 months of the report's first issue. Clearly, works required to facilitate development will not be required if the application is shelved or refused. However, necessary husbandry work should not be shelved with the application and should be brought to the attention of the person responsible, by the applicant, if different. Under the Occupiers Liability Act of 1957, the owner (or his agent) of a tree is charged with the due care of protecting persons and property from foreseeable damage and injury.' He is responsible for damage and/or nuisance arising from all parts of the tree, including roots and branches, regardless of the property on which they occur. He also has a duty under The Health and Safety at Work Act 1974 to provide a safe place of work, during construction. Tree works should only be carried out with local authority consent, where applicable.

Inherent in a tree survey is assessment of the risk associated with trees close to people and their property. Most human activities involve a degree of risk, such risks being commonly accepted if the associated benefits are perceived to be commensurate.

Risks associated with trees tend to increase with the age of the trees concerned, but so do many of the benefits. It will be appreciated, and deemed to be accepted by the client, that the formulation of recommendations for all management of trees will be guided by the cost-benefit analysis (in terms of amenity), of tree work that would remove all risk of tree related damage.

Prior to the commencement of any tree works, an ecological assessment of specific trees may be required to ascertain whether protected species (e.g. bats, badgers and invertebrates etc.) may be affected.

Tree Constraints & Protection Overview

Client:	Kelli and Robert Callow	Case Ref:	BDA/23DWN/AIA/01
Local Authority:	LB Camden	Date:	17/10/14
Site Address: 23 Downside Crescent, Belsize Park, London NW3 2AN			
Proposal: A new basement and single storey ground floor extension			
Report Checklist	Y/N		Y/N
Arboricultural constraints on site	Y	Trees removal proposed	N
Tree Survey	Y	Topographical Survey	Y
BS5837 Report	Y	Conservation Area	Y
Tree Preservation Orders	N/k		
Tree Protection Plan:	N/a	(Include in future method statement)	
Tree Constraints Plan:	Y		
Arboricultural Impact Assessment:	Y		
Site Layout			
Site Visit	Y	Date: 09/10/14	Access Full/Partial/None F
Trees on Site	Y	Off-site Trees	Y
Trees affected by development	Y	O/s trees affected by development	Y
Tree replacement proposed:	N	On or off-site trees indirectly affected by development	N
Trees with the potential to be affected			
<p>Very low impact to off-site T1 from basement piling line – boundary wall and existing hard standing likely to have limited rooting within development area. Manual excavation of piling line within RPA as a precautionary measure only (note further investigation of current condition recommended – third party ownership). Benefit to RPA if shed and associated hard standing removed with care. Any further hard landscaping to be no dig.</p> <p>Potentially positive impact for T6 from the removal of shed/hard standing noted above for T1.</p>			
Comments			
Recommended works for 2 onsite trees (T3 and T5) and one off-site tree (T1) regardless of development, but also pertinent to maintaining a safe work site.			
Recommendations			
1	Proposal will mean the loss of important trees (TPO/CA)		N
2	Proposal has sufficient amelioration for tree loss		N/a
3	Proposals provide adequate tree protection measures		Y
4	Proposal will mean retained trees are too close to buildings		N
5	Specialist demolition / construction techniques required		Y
6	The Proposal will result in significant root damage to retained trees		N
7	Further investigation of tree condition recommended		Y

RPA= Root Protection Area

TPP= Tree Protection Plan

AMS= Arboricultural Method Statement

AIA = Arboricultural Implication Assessment

BS5837: 2012 'Trees in relation to design, demolition and construction – Recommendations'

Arboricultural Impact Assessment Report: 23 Downside Crescent, Belsize Park, London NW3 2AN

Prepared for: Kelli and Robert Callow, 36 Constantine Road, London NW3 2NG

Prepared by: Adam Hollis of Landmark Trees, 20 Broadwick Street, London W1F 8HT

1. SUMMARY

- 1.1 This report comprises an arboricultural impact assessment of the proposals for 23 Downside Crescent, Belsize Park, London NW3 2AN, reviewing any conflicts between the proposals and material tree constraints identified in our survey.
- 1.2 There are 6 trees surveyed on or around the site, of which 2 are B category *(Moderate Quality), 3 are C category *(Low Quality) and 1 is U category *(Unsuitable for Retention). In theory, only moderate quality trees and above are significant material constraints on development. However, the low quality trees would comprise a constraint in aggregate, in terms of any collective loss / removal, where replacement planting would be appropriate. In this instance, no such collective impact is proposed.
- 1.3 The principal primary impacts in the current proposals are very low, comprising the minor encroachment to the theoretical RPA of the off-site poplar, T1, from the basement piling line; the boundary wall and existing hard standing may well have limited rooting within the small area of theoretical RPA affected by the proposed development. If not, poplar is a very robust species. Manual excavation of the piling line to 750mm depth within the RPA has been proposed as a precautionary measure only. If there is rooting within the site from T1, there will be some benefit to the RPA if the existing shed and associated hard standing removed with care by hand. Any further hard landscaping within the theoretical RPA of T1 should be constructed using no dig techniques with porous surfacing. It is also important to note that this tree has a broken canopy profile and is therefore vulnerable to wind snap; further investigation of current condition by the third-party owners has been recommended. There is little point specifying tree protection measures, if the tree has to be felled. Conversely, the engineer is advised to consider the very real possibility of this tree being felled and any heave potential arising in the surrounding soil.
- 1.4 The careful removal of the shed/hard standing will also have a potentially positive impact for T6, providing the tree is protected and the soil beneath the structures left undisturbed.
- 1.5 There will be negligible secondary impacts, comprising organic deposition only from the trees and remaining as it is today.
- 1.6 The site has potential for development without impacting significantly on the wider tree population or local landscape. Thus, with suitable mitigation and supervision the scheme is recommended to planning.

* British Standards Institute: Trees in relation to design, demolition and construction BS 5837: 2012 HMSO, London

2. INTRODUCTION

2.1 Terms of reference

- | | |
|-------|---|
| 2.1.1 | LANDMARK TREES were asked by Kelli and Robert Callow to provide a survey and an arboricultural impact assessment of proposals for the site: 23 Downside Crescent, Belsize Park, London NW3 2AN. The report is to accompany a planning application. |
| 2.1.2 | The proposals are for a new basement and single storey ground floor extension to the existing residential property. This report will assess the impact on the trees and their constraints, identified in our survey. Although the proposals were known at the time of the survey, Landmark Trees endeavour to survey each site blind, working from a topographical survey, wherever possible, with the constraints plan informing their evolution. |
| 2.1.3 | I am a Registered Consultant and Fellow of the Arboricultural Association and a Chartered Forester, with a Masters Degree in Arboriculture and 25 years' experience of the landscape industry - including the Forestry Commission and Agricultural Development and Advisory Service. I am a UK Registered Expert Witness, trained in single and joint expert witness duties. I am also Chairman of the UK & I Regional Plant Appraisal Committee, inaugurated to promote international standards of valuation in arboriculture. |

2.2 Drawings supplied

- | | |
|-------|--|
| 2.2.1 | <p>The drawings supplied by the client and relied upon by Landmark Trees in the formulation of our survey plans are:</p> <p>Existing site survey: BO-23DC_G</p> <p>Proposals: D3102 RevP2-Proposed Ground Floor Plan</p> |
|-------|--|

2.3 Scope of survey

- | | |
|-------|--|
| 2.3.1 | As Landmark Trees' (LT) arboricultural consultant, I surveyed the trees on site on 9 th October 2014, recording relevant qualitative data in order to assess both their suitability for retention and their constraints upon the site, in accordance with British Standard 5837:2012 Trees in relation to design, demolition and construction – Recommendations [BS5837:2012]. |
| 2.3.2 | Our survey of the trees, the soils and any other factors, is of a preliminary nature. The trees were SURVEYED on the basis of the Visual Tree Assessment method expounded by Mattheck and Breloer (The Body Language of Trees, DoE booklet Research for Amenity Trees No. 4, 1994). LT have not taken any samples for analysis and the trees were not climbed, but inspected from ground level. |
| 2.3.3 | A tree survey is generally considered invalid in planning terms after 2 years, but changes in tree condition may occur at any time, particularly after acute (e.g. storm events) or prolonged (e.g. drought) environmental stresses or injuries (e.g. root severance). Routine surveys at different times of the year and within two - three years of each other (subject to the incidence of the above stresses) are recommended for the health and safety management of trees remote from highways or busy access routes. Annual surveys are recommended for the latter. |
| 2.3.4 | The survey does not cover the arrangements that may be required in connection with the laying or removal of underground services. |

2.4 Survey data & report layout

- | | |
|-------|---|
| 2.4.1 | Detailed records of individual trees are given in the survey schedule in Appendix 1 to this report. |
| 2.4.2 | A site plan identifying the surveyed trees, based on the client's drawings / topographical survey is provided in Appendix 3. |
| 2.4.3 | This plan also serves as the Tree Constraints Plan with the theoretical Recommended Protection Areas (RPA's), tree canopies and shade constraints, (from BS5837: 2012) overlain onto it. These constraints are then overlain in turn onto the client's proposals to create an Arboricultural Impact Assessment Plan in Appendix 4. General observations and discussion follow, below. |

3.0 OBSERVATIONS

3.1 Site description



Photograph 1: Rear view of 23 Downside Crescent, Belsize Park, London NW3 2AN

- | | |
|-------|---|
| 3.1.1 | The site currently comprises an existing residential dwelling, situated on the north western side of Downside Crescent. The property has a courtyard garden to the front, and a rear garden with an outbuilding and existing hard landscaping (see photograph 1 above). |
| 3.1.2 | The site is relatively level. |
| 3.1.3 | In terms of the British Geological Survey, the site overlies the London Clay Formation (see indicated location on Fig.1 plan extract below). The associated soils are generally, highly shrinkable clay; e.g. slowly permeable seasonally waterlogged fine loam over clay. Such highly plastic soils are prone to movement: subsidence and heave. The actual distribution of the soil series are not as clearly defined on the ground as on plan and there may be anomalies in the actual composition of clay, silt and sand content. |
| 3.1.4 | Clay soils are prone to compaction during development with damage to soil structure potentially having a serious impact on tree health. The design of foundations near problematic tree species will also need to take into consideration subsidence risk. Further advice from the relevant experts on the specific soil properties can be sought as necessary. |




Figure 1: Extract from the BGS Geology of Britain Viewer

3.2 Subject trees

- 3.2.1 Of the 6 surveyed trees 2 are B category (Moderate Quality), 3 are C category (Low Quality) and 1 is U category (Unsuitable for Retention).
- 3.2.2 The tree species found on site or adjacent to the site comprise Japanese maple, flowering cherry, Lombardy poplar, horse chestnut, Leyland cypress and sycamore.
- 3.2.3 In terms of age demographics there is a preponderance of early mature trees with a post mature (T1) and a semi-mature tree (T6) also in the population.

- 3.2.4 Full details of the surveyed trees can be found in Appendix 1 of this report.
- 3.2.5 There are recommended works for good husbandry including the need to fell the category U tree T5. It is also recommended that further investigation is required for the broken canopy profile of T1 which is currently vulnerable to wind snap, and further investigation of the canker/bleeding on T3; both T1 and T3 are third party trees. These works are listed in Appendix 2.

3.3 Planning Status

- 3.3.1 We are not aware of the existence of any Tree Preservation Orders, but understand the site stands within the Parkhill Conservation Area, which will affect the subject trees: it is a criminal offence to prune, damage or fell such trees without permission from the local authority.

4.0 DEVELOPMENT CONSTRAINTS

4.1 Primary constraints

- 4.1.1 BS5837: 2012 gives Recommended Protection Areas (RPA's) for any given tree size. The individual RPA's are calculated in the Tree Schedule in Appendix 1 to this report, or rather the notional radius of that RPA, based on a circular protection zone. The prescribed radius is 12-x stem diameter at 1.5m above ground level, except where composite formulae are used in the case of multi-stemmed trees.
- 4.1.2 Circular RPA's are appropriate for individual specimen trees grown freely, but where there is ground disturbance, the morphology of the RPA can be modified to an alternative polygon, as shown in the diagram below (Figure 2). Alternatively, one need principally remember that RPA's are area-based and not linear – notional rather than fixed entities. **No modifications have been made in this instance (please see overleaf).**




Figure 2 – Generic BS 5837 RPA Adjustments

- 4.1.3 In BS5837, paragraph 4.6.2 states that RPA's should reflect the morphology and disposition of the roots; where pre-existing site conditions or other factors indicate that rooting has occurred asymmetrically, a polygon of equivalent area should be produced. Modifications to the shape of the RPA should reflect a soundly based arboricultural assessment of likely root distribution. Not infrequently, LT are requested by LPA Tree Officers to modify the RPA's to reflect their assumptions that e.g. a road will have drastically limited root growth.

- 4.1.4 Such assumptions cannot be proved without prior site investigations / trial pits. Where it is not always possible to conduct site investigations (e.g. below busy roads), we can always look to the published science. There seems little support for the popular myth that roads and services will curb root growth: research for the International Society of Arboriculture by Kopinga J (ISA 1994), found that “a constant high moisture content of the soil directly underneath the pavement surface can be considered as a major soil factor in attracting the trees’ roots to develop there.” By contrast, grass in lawns may actively antagonise tree roots with natural pathogens. Similarly, Professor F Miller (ISA 1994) found that service trenches at > 3m distances from trees had minimal impact on growth or crown shape.
- 4.1.5 A key misunderstanding, even among professionals, is that we conflate the RPA with the actual root system: RPA's are *prima facie* a notion / convention / treaty and almost entirely theoretical, but readily calculable. Conversely roots are a "known unknown," spatial entity that we predict at our folly. Yet, many are quick to do so.
- 4.1.6 LT favour the neutrality of a circular RPA, because in a difference of opinion, the tree officer will always have the prerogative to dictate the final modification of shape. With the best will in the world, the free allowance of modifications will tend to lead to inequitable outcomes, prejudicing the applicant and the practice is in our view, best avoided. The neutral circle dispenses with this inequity.
- 4.1.7 Ultimately, the point of the circular RPA is to illustrate areas of concern. The purpose of this report is to consider areas of concern (not to modify them to suit our argument or findings). Therefore, no modifications are made here to the RPA's, regardless of roads etc.
- 4.1.8 The quality of trees will also be a consideration: U Category trees are discounted from the planning process in view of their limited service life. Again, Category-C trees would not normally constrain development individually, unless they provide some external screening function.
- 4.1.9 At paragraph 5.1.1. BS5837: 2012 notes that “Care should be exercised over misplaced tree preservation; attempts to retain too many or unsuitable trees on a site are liable to result in excessive pressure on the trees during demolition or construction work, or post-completion demands on their removal.”

- 4.1.10 In theory, only moderate quality trees and above are significant material constraints on development. However, the low quality trees would comprise a constraint in aggregate, in terms of any collective loss / removal, where replacement planting would be appropriate.
- 4.1.11 In this instance, the main constraints to development are the category B trees T2 (off-site) and T4 located either side of the rear boundary of the site. Provided it will not be necessary to build right up to the boundary, these trees will not significantly constrain development.

4.2 Secondary Constraints

4.2.1 The second type of constraint produced by trees that are to be retained is that the proximity of the proposed development to the trees should not threaten their future with ever increasing demands for tree surgery or felling to remove nuisance shading (Figure 3), honeydew deposition or perceived risk of harm.




Figure 3 –
Generic Shading Constraints

4.2.2 The shading constraints are crudely determined from BS5837 by drawing an arc from northwest to east of the stem base at a distance equal to the height of the tree, as shown in the diagram opposite. Shade is less of a constraint on non-residential developments, particularly where rooms are only ever temporarily occupied.




Figure 4 – Shading Arc

4.2.3 This arc (see Figure 4) represents the effects that a tree will have on layout through shade, based on shadow patterns of 1x tree height for a period May to Sept inclusive 10.00-18.00 hrs daily.

4.2.4 Assuming that they will be retained, the orientation of the on and off-site trees will ensure that shading constraints are minimal, with leaf deposition and honey-dew likely to be as it is today. The significance of these constraints will vary depending on the location and proximity to the proposed re-development.

Note: Sections 5 & 6 will now assess the impacts upon constraints identified in Section 4. Table 1 in Section 5 presents the impacts in tabular form (drawing upon survey data presented in Appendices 1 & 2). Impacts are presented in terms of whole tree removal and the effect on the landscape or partial encroachment (% of RPA) and its effect on individual tree health. Section 6 discusses the table data, elaborating upon the impacts' significance and mitigation.

Table 1: Arboricultural Impact Assessment

(Impacts assessed prior to mitigation and rated with reference to Matheny & Clark (1998))

Hide irrelevant

Show All Trees

Ref: BDA/23DWN/AIA

B.S. Cat.	Tree No.	Species	Impact	Tree / RPA Affected	Age	Growth Vitality	Species Tolerance	Impact on Tree Rating	Impact on Site Rating	Mitigation
C	1	Poplar, Lombardy	Demolition of existing shed/hard standing 10.5m2/2% Basement Construction within RPA (13.7m2/2%)	13.7 m ² 1.94 %	Post-Mature	Normal	Good	Low	N/A	Manual removal of shed and hard standing Airspade / manual excavation of piling line
C	6	Cypress, Leyland	Removal of existing shed/hard standing	1.8 m ² 17.68 %	Semi-mature	Normal	Good	Very Low	N/A	Manual removal of shed and hard standing Beneficial to the RPA if undertaken with care

6.0 DISCUSSION

6.1 Rating of Primary Impacts

6.1.1 The principal primary impacts in the current proposals are very low, comprising the minor encroachment to the theoretical RPA of the off-site poplar, T1, from the basement piling line; the boundary wall and existing hard standing may well have limited rooting within the small area of theoretical RPA affected by the proposed development. If not, poplar is a very robust species. Manual excavation of the piling line to 750mm depth within the RPA has been proposed as a precautionary measure only. If there is rooting within the site from T1, there will be some benefit to the RPA if the existing shed and associated hard standing removed with care by hand. Any further hard landscaping within the theoretical RPA of T1 should be constructed using no dig techniques with porous surfacing. It is also important to note that this tree has a broken canopy profile and is therefore vulnerable to wind snap; further investigation of current condition by the third-party owners has been recommended. There is little point specifying tree protection measures, if the tree has to be felled. Conversely, the engineer is advised to consider the very real possibility of this tree being felled and any heave potential arising in the surrounding soil.

6.1.2 The careful removal of the shed/hard standing will also have a potentially positive impact for T6, providing the tree is protected and the soil beneath the structures left undisturbed.

6.1.3 The principal of RPA encroachment is established within BS5837:2012 and supported by the source document, National Joint Utilities Guidelines 10 / Vol. 4 1995 / 2010. NJUG introduced the x12 diameter *Precautionary Zone* for supervised working and *Prohibited Zone* at a universal 1m from the base of the tree. RPA's are frequently confused with the NJUG Prohibited Zone, when they clearly correlate with the NJUG Precautionary Zone.

6.1.4 An RPA encroachment of <20% of RPA may be considered as low impact, given the permissive references to 20% RPA relocation and impermeable paving within BS5837:2012 and other published references to healthy trees tolerating up to 30-50% root severance (Coder, Helliwell and Watson in CEH 2006). The trees in question are healthy specimens of species with a good resistance to development impacts, and quite capable of tolerating these low impacts.

6.1.5 **"In practice 50% of roots can sometimes be removed with little problem**, provided there are vigorous roots elsewhere. Inevitably, this degree of root loss will temporarily slow canopy growth and even lead to some dieback" (Thomas 2000). LT do not recommend annexing such high proportions of the root system; rather that within the context of the published science, planning should not be unduly concerned by impacts that are well below the subcritical threshold – *tree health is not at stake*.

6.2 Rating of Secondary impacts

6.2.1 There will be negligible secondary impacts, comprising organic deposition only from the trees and remaining as it is today.

6.3 Mitigation of Impacts

6.3.1 All plant and vehicles engaged in demolition works should either operate outside the RPA, or should run on a temporary surface designed to protect the underlying soil structure. The demolition of the outbuilding building should proceed inwards in a “pull down” fashion. Hard surfacing can be lifted with caution by hand, ensuring that roots that may be just below the surface are not damaged.

6.3.2 The path of foundations through the theoretical RPA of T1 will be manually excavated to 750mm depth under arboricultural supervision; any roots encountered within the trenches / pits will be cleanly pruned back to an appropriate junction with a sharp pruning saw or secateurs back to a junction. Roots larger than 25mm diameter may only be cut in consultation with an arboriculturalist.

6.3.3 The replacement paving/hard landscaping will require a no-dig construction technique, either using a cellular confinement system with no fines aggregate for the sub-base or simply building upon the existing sub-base without disturbing the ground below. Choice of construction method will initially depend upon root penetration within the existing sub-grade. The key principle is not to excavate in the presence of roots and to provide a porous surface to promote healthy soil water relations for future root growth.

6.3.4 Nuisance deposition can be mitigated with regular crown cleaning and filtration traps on the guttering (see Figure 5 below). Alternatively, elements of green roof construction might be considered, where applicable.




Figure 5: Filtration traps, as shown, could be fitted on the gutters.

7.0 CONCLUSION

- 7.1 The potential impacts of development are all very low in terms of the RPA encroachments, from both the proposed demolition of the existing out building and hard standings, in addition to the proposed new basement and ground floor extension. Furthermore, the removal of the outbuilding and hardstanding from the theoretical RPA of both T1 and T6 is likely to benefit both trees.
- 7.2 The full potential of the impacts can be mitigated through precautionary measures. These measures can be elaborated in Method Statements in the discharge of planning conditions.
- 7.3 Therefore, the proposals will not have any significant impact on either the retained trees or wider landscape. Thus, with suitable mitigation and supervision the scheme is recommended to planning.

8.0 RECOMMENDATIONS

8.1 Specific Recommendations

- | | |
|-------|---|
| 8.1.1 | Current tree works recommendations are found in Appendix 2 to this report; there are no works required to facilitate development. |
|-------|---|

8.2 General Recommendations

- | | |
|-------|--|
| 8.2.1 | Any trees which are in close proximity to the proposed development should be protected with a Tree Protection Barrier (TPB). Protective barrier fencing should be installed immediately following the completion of the tree works, remaining in situ for the entire duration of the development unless otherwise agreed in writing by the council. It should be appropriate for the intensity and proximity of the development, usually comprising steel, mesh panels 2.4m in height ('Heras') and should be mounted on a scaffolding frame (shown in Fig 2 of BS5837:2012). The position of the TPB can be shown on plan as part of the discharge of conditions, once the lay out is agreed with the planning authority. The TPB should be erected prior to commencement of works, remain in its original form on-site for the duration of works and removed only upon full completion of works. |
| 8.2.2 | A TPB may no longer be required during soft landscaping work but a full arboricultural assessment must be performed prior to the undertaking of any excavations within the RPA of a tree. This will inform a decision about the requirement of protection measures. It is important that all TPBs have permanent, weatherproof notices denying access to the RPA. |
| 8.2.3 | The necessary machinery should be located above the existing grade level and work away from any retained trees. This will ensure that any spoil is removed from the RPAs. It is vital that the original soil level is not lowered as this is likely to cause damage to the shallow root systems. |
| 8.2.4 | Where sections of hard surfacing are proposed in close proximity to trees, it is recommended that "No-Dig" surfacing be employed in accordance with BS5837:2012 and 'The Principles of Arboricultural Practice: Note 1, Driveways Close to Trees, AAIS 1996 [APN1]'. |
| 8.2.5 | If the RPA of a tree is encroached by underground service routes then BS5837:2012 and NJUG VOLUME 4 provisions should be employed. If it is deemed necessary, further arboricultural advice must be sought. |
| 8.2.6 | Numerous site activities are potentially damaging to trees e.g. parking, material storage, the use of plant machinery and all other sources of soil compaction. In operating plant, particular care is required to ensure that the operational arcs of excavation and lifting machinery, including their loads, do not physically damage trees when in use. |

- 8.2.7 To enable the successful integration of the proposal with the retained trees, the following points will need to be taken into account:
- 1) Plan of underground services.
 - 2) Schedule of tree protection measures, including the management of harmful substances.
 - 3) Method statements for constructional variations regarding tree proximity (e.g. foundations, surfacing and scaffolding).
 - 4) Site logistics plan to include storage, plant parking/stationing and materials handling.
 - 5) Tree works: felling, required pruning and new planting. All works must be carried out by a competent arborist in accordance with BS3998.
 - 6) Site supervision: the Site Agent must be nominated to be responsible for all arboricultural matters on site. This person must:
 - be present on site for the majority of the time;
 - be aware of the arboricultural responsibilities;
 - have the authority to stop work that is causing, or may cause harm to any tree;
 - ensure all site operatives are aware of their responsibilities to the trees on site and the consequences of a failure to observe these responsibilities;
 - make immediate contact with the local authority and/or a retained arboriculturalist in the event of any tree related problems occurring.
- 8.2.8 These points can be resolved and approved through consultation with the planning authority via their Arboricultural Officer.
- 8.2.9 The sequence of works should be as follows:
- i) initial tree works: felling, stump grinding and pruning for working clearances;
 - ii) installation of TPB for demolition & construction;
 - iii) installation of underground services;
 - iv) installation of ground protection;
 - v) main construction;
 - vi) removal of TPB;
 - vii) soft landscaping.

9.0 REFERENCES

- Barlow JF & Harrison G. 1999. Shade By Trees, Arboricultural Practice Note 5, AAIS, Farnham, Surrey.
- British Standards Institute. 2012. Trees in Relation to Design, Demolition and Construction - Recommendations BS 5837: 2012 HMSO, London.
- Centre for Ecology & Hydrology. 2006. Tree Roots in the Built Environment, HMSO, London.
- Helliwell R (1980) Provision for New Trees; Landscape Design; July/August issue
- International Society of Arboriculture (ISA). 1994. The Landscape Below Ground. ISA, Champaign, Illinois. USA.
- Lonsdale D 1999. Research for Amenity Trees No.7: Principles of Tree Hazard Assessment and Management, HMSO, London.
- Matheny, N; Clark, J. R.1998. Trees and Development: A Technical Guide to Preservation of Trees during Land Development. ISA, Champaign, Illinois. USA.
- Mattheck C. & Breloer H. 1994. Research for Amenity Trees No.2: The Body Language of Trees, HMSO, London.
- Thomas P, 2000. Trees: Their Natural History, Cambridge University Press, Cambridge.
- Trowbridge J & Bassuk N (2004) Trees in the Urban Landscape: Site Assessment, Design, and Installation; J Wiley & Sons inc. NJ USA

APPENDIX 1

TREE SCHEDULE

Notes for Guidance:

1. Height describes the approximate height of the tree measured in metres from ground level.
2. The Crown Spread refers to the crown radius in meters from the stem centre and is expressed as an average of NSEW aspect if symmetrical.
3. Ground Clearance is the height in metres of crown clearance above adjacent ground level.
4. Stem Diameter (Dm) is the diameter of the stem measured in millimetres at 1.5m from ground level for single stemmed trees. BS 5837:2012 formula (Section 4.6) used to calculate diameter of multi-stemmed trees. Stem Diameter may be estimated where access is restricted and denoted by '#'.
5. Protection Multiplier is 12 and is the number used to calculate the tree's protection radius and area
6. Protection Radius is a radial distance measured from the trunk centre.
7. Growth Vitality - Normal growth, Moderate (below normal), Poor (sparse/weak), Dead (dead or dying tree).
8. Structural Condition - Good (no or only minor defects), Fair (remediable defects), Poor - Major defects present.
9. Landscape Contribution - High (prominent landscape feature), Medium (visible in landscape), Low (secluded/among other trees).
10. B.S. Cat refers to (British Standard 5837:2012 section 4.5) and refers to tree/group quality and value; 'A' – High, 'B' - Moderate, 'C' - Low, 'U' - Unsuitable for retention. The following colouring has been used on the site plans:
 - High Quality (A) (Green),
 - Moderate Quality (B) (Blue),
 - Low Quality (C) (Grey),
 - Unsuitable for Retention (U) (Red)
11. Sub Cat refers to the retention criteria values where 1 is Arboricultural, 2 is Landscape and 3 is Cultural including Conservational, Historic and Commemorative.
12. Useful Life is the tree's estimated remaining contribution in years.



Site: 23 Downside Crescent

Date: 9/10/14

Appendix 1

Landmark Trees Ltd

020 7851 4544

Surveyor(s): Adam Hollis

Ref: BDA_23DWN_AIA

BS5837 Tree Constraints Survey Schedule

Tree No.	English Name	Height	Crown Spread	Ground Clearance	Stem Diamete	Age Class	Protection Radius	Growth Vitality	Structural Condition	B.S. Cat	Sub Cat	Useful Life	Comments
1	Poplar, Lombardy	22	3	3.0	1250	Post-Mature	15.0	Normal	Poor	C	1	10+	Broken canopy profile Vulnerable to wind snap Remote survey only (RS)
2	Sycamore	10	3	7.5	292	Early Mature	3.5	Normal	Fair	B	2	20+	Multi stem weakness RS
3	Chestnut, Horse	14	5	3.5	618	Early Mature	7.4	Poor	Fair	C	2	10+	Canker Bleeding in lower crown
4	Maple, Japanese	7	1441	3.0	203	Early Mature	2.4	Normal	Fair	B	1	>40	Asymmetry (major) Suppressed by nearby tree
5	Cherry, Flowering	5	1221	2.0	210	Early Mature	2.5	Poor	Fair	U		<10	Canker Bleeding on lower stem Topped with dieback
6	Cypress, Leyland	5	2	1.5	150	Semi-mature	1.8	Normal	Good	C	1	>40	A tree with insignificant defects


APPENDIX 2

RECOMMENDED TREE WORKS

Notes for Guidance:

Husbandry 1 - Urgent (ASAP), 2 - Standard (within 6 months), 3 - Non-urgent (2-3 years)

- CB - Cut Back to boundary/clear from structure.
- CL# - Crown Lift to given height in meters.
- CT#% - Crown Thinning by identified %.
- CCL - Crown Clean (remove deadwood/crossing and hazardous branches and stubs).
- CR#% - Crown Reduce by given maximum % (of outermost branch & twig length)
- DWD - Remove deadwood.
- Fell - Fell to ground level.
- FInv - Further Investigation (generally with decay detection equipment).
- Pol - Pollard or re-pollard.
- Mon - Check / monitor progress of defect(s) at next consultant inspection which should be <18 months in frequented areas and <3 years in areas of more occasional use. Where clients retain their own ground staff, we recommend an annual in- house inspection and where practical, in the aftermath of extreme weather events.
- Svr Ivy / Clr Bs - Sever ivy / clear base and re-inspect base / stem for concealed defects.



Site: 23 Downside Crescent

Date: 9/10/14

Surveyor(s): Adam Hollis

Ref: BDA/23DWN/AIA

Appendix 2

Recommended Tree Works


Hide irrelevant

Show All Trees

Tree No.	English Name	B.S. Cat	Height	Ground Clearance	Crown Spread	Recommended Works	Comments/ Reasons
1	Poplar, Lombardy	C	22	3.0	3	FInv	Broken canopy profile Vulnerable to wind snap Remote survey only (RS) Recommended husbandry 2
3	Chestnut, Horse	C	14	3.5	5	FInv	Canker Bleeding in lower crown Recommended husbandry 3
5	Cherry, Flowering	U	5	2.0	1221	Fell	Canker Bleeding on lower stem Topped with dieback Recommended husbandry 3

APPENDIX 3

TREE CONSTRAINTS PLAN



Ground Floor Plan

NOTE:
This survey is of a preliminary nature. The trees were inspected from the ground only and no decay detection equipment was employed. The survey does not cover the arrangements that may be required in connection with the laying or removal of underground services.
Branch spread in nature is taken at the four cardinal points to derive an accurate representation of the crown.
Root Protection Areas (RPA) are derived from stem diameter measured at 1.5 m above adjacent ground level (taken on sloping ground on the upslope side of the tree base).



Landmark Trees
20 Broadwick Street, London, W1F 8HT
Tel: 0207 693 4544 Mobile: 07812 869828
Email: info@landmarktrees.co.uk Web: www.landmarktrees.co.uk

Drawing Title: Tree Constraints Plan	1:100@ A1
Site: 23 Downside Crescent	October 2014

Key:

- Category A
- High Quality
- Category B
- Medium Quality
- Category C
- Low Quality
- Category U
- Trees Unsuitable for Retention

Category

Root Protection Area

Tree Number


Species

Category


Tree Position Approximate (not shown on original survey)

APPENDIX 4

ARBORICULTURAL IMPACT ASSESSMENT PLAN



Proposed Ground Floor Plan



NOTES

This survey is of a preliminary nature. The trees were inspected from the ground only on the basis of the Visual Tree Assessment method. No samples were taken for analysis. No decay detection equipment was employed. The survey does not cover the arrangements that may be required in connection with the laying or removal of underground services.

Branch spread in metres is taken at the four cardinal points to derive an accurate representation of the crown.

Root Protection Areas (RPA) are derived from stem diameter measured at 1.5 m above adjacent ground level (taken on sloping ground on the upslope side of the tree base).



Landmark Trees:

Site: 23 Downside Crescent

Drawing Title: Arboricultural Impacts Assessment

October 2014

Key: Crown Spread

-
- The diagram illustrates a phylogenetic tree with several key features and a legend:
- Legend:**
 - High Quality: Green circle
 - Category B: Blue circle
 - Moderate Quality: Grey circle
 - Category C: Red circle
 - Low Quality: Red circle
 - Category U: Red circle
 - Trees Unsuitable for Retention: Green circle with diagonal lines
 - Tree Structure:**
 - Root:** Indicated by a blue dot at the base of the tree.
 - Protection Area:** A region around the root, highlighted with a green dashed line.
 - Tree Number:** A blue label '3' pointing to a specific node.
 - Species:** A blue label 'B3' pointing to a specific node.
 - Category:** A red label 'B3' pointing to a specific node.
 - Annotations:**
 - Tree Position Approximate (not shown on original survey):** A green dashed line with a green circle at the end, indicating a specific position on the tree.