DOOR	STATUS	TYPE	FIXING	FIRE RATED	HEIGHT	FINISH
D1	KEEP	SINGLE '2 PANEL'	HINGED	30 MIN	EXISTING	PAINTED LACQUER
D2	REMOVE	DOUBLE '2 PANEL'	HINGED	N A	EXISTING	PAINTED LACQUER
D3	REPLACE	SINGLE '2 PANEL'	HINGED	30 MIN	2200 mm	PAINTED LACQUER
D4	REPLACE	SINGLE '2 PANEL'	HINGED	30 MIN	2200 mm	PAINTED LACQUER
D5	REMOVE	SINGLE '2 PANEL'	HINGED	N A	EXISTING	PAINTED LACQUER
D6	REPLACE	SINGLE '2 PANEL'	HINGED	30 MIN	2200 mm	PAINTED LACQUER
D7	REPLACE	SINGLE '2 PANEL'	HINGED	30 MIN	2200 mm	PAINTED LACQUER
D8	REPLACE	SINGLE '2 PANEL'	HINGED	30 MIN	2400 MM	PAINTED LACQUER
D9	REPLACE	SINGLE '2 PANEL'	HINGED	N A	2400 MM	PAINTED LACQUER
D10	REPLACE	SINGLE '2 PANEL'	HINGED	30 MIN	2200 mm	PAINTED LACQUER
D11	REMOVE	SINGLE '2 PANEL'	HINGED	N A	EXISTING	PAINTED LACQUER
D12	REMOVE	SINGLE '2 PANEL'	HINGED	N A	EXISTING	PAINTED LACQUER
D13	REPLACE	SINGLE '2 PANEL'	HINGED	30 MIN	2200 mm	PAINTED LACQUER
D14	REPLACE	SINGLE '2 PANEL'	HINGED	N A	2200 mm	PAINTED LACQUER
D15	REPLACE	SINGLE '2 PANEL'	HINGED	N A	2200 mm	PAINTED LACQUER
D16	REPLACE	SINGLE '2 PANEL'	HINGED	N A	2200 mm	PAINTED LACQUER
D17	REPLACE	SINGLE '2 PANEL'	HINGED	30 MIN	2200 mm	PAINTED LACQUER
D18	REPLACE	SINGLE '2 PANEL'	HINGED	30 MIN	2200 mm	PAINTED LACQUER
D19	REPLACE	SINGLE '2 PANEL'	HINGED	N A	2200 mm	PAINTED LACQUER
D20	REPLACE	SINGLE '2 PANEL'	HINGED	30 MIN	2200 mm	PAINTED LACQUER
D21	REMOVE	SINGLE '2 PANEL'	HINGED	N A	EXISTING	PAINTED LACQUER
D22	REMOVE	SINGLE '2 PANEL'	HINGED	N A	EXISTING	PAINTED LACQUER
D23	REMOVE	SINGLE '2 PANEL'	HINGED	N A	EXISTING	PAINTED LACQUER
D24	REPLACE	SINGLE '2 PANEL'	HINGED	30 MIN	2200 mm	PAINTED LACQUER
D25	REPLACE	SINGLE '2 PANEL'	HINGED	N A	2200 mm	PAINTED LACQUER
D26	REPLACE	SINGLE '2 PANEL'	HINGED	30 MIN	2400 MM	PAINTED LACQUER
D27	REPLACE	SINGLE '2 PANEL'	HINGED	30 MIN	2400 MM	PAINTED LACQUER
D28	REPLACE	SINGLE '2 PANEL'	HINGED	30 MIN	2400 MM	PAINTED LACQUER
D29	REPLACE	DOUBLE CUPBOARD	HINGED	N A	2200 mm	PAINTED LACQUER
D30	REPLACE	DOUBLE CUPBOARD	HINGED	N A	2200 mm	PAINTED LACQUER
D31	REPLACE	SINGLE '2 PANEL'	HINGED	30 MIN	2200 mm	PAINTED LACQUER
D32	REPLACE	SINGLE '2 PANEL'	HINGED	30 MIN	2200 mm	PAINTED LACQUER
D33	REMOVE	SINGLE '2 PANEL'	HINGED	N A	EXISTING	PAINTED LACQUER
D33b	REMOVE	SINGLE '2 PANEL'	HINGED	N A	EXISTING	PAINTED LACQUER
D33c	REPLACE	SINGLE '2 PANEL'	HINGED	N A	EXISTING	PAINTED LACQUER
D34	NEW	DOUBLE '2 PANEL'	HINGED	30 MIN	EXISTING	PAINTED LACQUER
D35	NEW	DOUBLE '2 PANEL'	SLIDING	N A	2400 MM	PAINTED LACQUER
D36	NEW	SINGLE '2 PANEL'	HINGED	30 MIN	2400 MM	PAINTED LACQUER
D37	NEW	SINGLE '2 PANEL'	SLIDING	N A	2200 mm	PAINTED LACQUER
D38	NEW	SINGLE '2 PANEL'	SLIDING	N A	2200 mm	PAINTED LACQUER
D38b	NEW	SINGLE '2 PANEL'	HINGED	N A	2200 mm	PAINTED LACQUER
D39	NEW	SINGLE '2 PANEL'	SLIDING	N A	2200 mm	PAINTED LACQUER
D40	NEW	SINGLE '2 PANEL'	HINGED	30 MIN	2200 mm	PAINTED LACQUER
D41	NEW	SINGLE '2 PANEL'	HINGED	N A	2200 mm	PAINTED LACQUER
D42	NEW	SINGLE '2PANEL'	HINGED	30 MIN	2200 mm	PAINTED LACQUER

The content of this document is strictly CONFIDENTIAL. Any unauthorised copying, disclosure or distribution of the material and information in this document is strictly forbidden.

All measurements are to be checked and confirmed on site by the contractor.

All dimensions are in cm unless otherwise stated.

FOR INFORMATION ONLY

Rev.	Date	Reason For Issue	Check

tomèf
ARCHITECTURE
INTERIOR DESIGN

132-134 Lots Road
Unit 108
World's End Studios
SW10 0RJ London

T +44 75 3094 0005

Client
TB

Project
10 Chester Terrace

Title
Door Schedule

Job No	Originator	Scale	Number	Revision
			A4001	00
Date	Location	Drawn by		
27.11.14	—	—		