## Allies and Morrison Architects

## Kidderpore Avenue

## 809\_3TP\_MMA

Schedule of Minor Material Amendments - Planning Permission Ref : 2013/0685/P

**REVISION B** 17.12.16

	Reference code	Description of Amendment	Drawing number
00 Site			
	00.10	Tree removed from Platts lane block K elevation and replaced further South	809_01_07_100
04.01   1			
04 Block J	04.01	Terrace added at rear	900 01 07 101
	04.01	Basement extended	809_01_0 <i>7</i> _101 809_01_0 <i>7</i> _100
	04.02		
		Windows shifted slightly Window made into recess	809_00_07_407
	04.04		809_01_07_407
	04.05	Minor change to ground floor window expression	809_01_07_407
	04.06	Window recess modelling changed	809_01_07_407
	04.07	Minor changes to side elevation window location and types due to internal layout	809_01_07_407
	04.08	Door removed	809_01_07_407
05 Block K1			
	05.01	Basement reduced in size	809_01_07_100
	05.02	Central brick pier to Platts Lane widened to remove cold bridge	809_01_07_408
	05.03	Line of windows moved on each short elevation to remove cold bridging.	809_01_07_408
	05.04	Lift over-run moved and AOV shown	809_01_07_408
	05.05	Balcony at rear possibly becomes garden	809_01_07_101
06 Block K2	04.01		000 01 07 100
	06.01	Basement added	809_01_07_100
	06.02	Low level covered light well added	809_01_07_408
	06.03	Entrance moved from garden to corner	809_01_07_408
	06.04	Platts lane windows aligned	809_01_07_408
	06.05	Window removed	809_01_07_408
	06.06	Window made into recess	809_01_07_408
	06.07	Window positoins adjusted to suit internal layouts	809_01_07_408
	06.08	Window replaced with slot window	809_01_07_408
	06.09	SE corner windows reduced in size	809_01_07_408
	06.10	Wall between main K block and K2 increased to 1.8m for privacy	809_01_07_408
07 Block L,M			
	07.01	Openings shown to nearest brick dimension	809_01_07_409
	07.02	Pile line simplified	809_01_07_101
	07.03	Balconies to be drained	809_01_07_409
	07.04	Concealed gutters used rather than planted	809_01_07_409
	07.05	Gable verge detail simplified	809_01_07_409
	07.06	Front balconies stretched to suit brick dims	809_01_07_409/410
	07.07	Rear balconies stretched to suit brick dims	809_01_07_409/410
Block L			
	07.10	Substation replaced by bin store	809_01_07_101
	07.11	Side window strips moved to avoid cold bridges	809_01_07_409
	07.12 07.13	Dormer windows shifted  Level 00 window moved to align	809_01_07_409 809_01_07_409
	0/.13	Level OO Willdow Hoved to dilgit	007_01_0/_409
Block M			
	07.20	Vent outlet moved to improve smoke extraction	809_01_07_101
	07.21	Building moved back from Kiddepore Avenue by 300mm	809_01_07_109
	07.22 07.23	Dormer window positions shifted to suit internal layouts  Side window strips moved to avoid cold bridges	809_01_07_410 809_01_07_410
	0/.20	Jake williages illoved to avoid cold bilages	007_01_0/_410