



- NOTES
1. ALL DUCTWORK TO BE INSTALLED IN GALVANISED STEEL AND IN ACCORDANCE WITH DW144.
  2. ALL NEW EXTERNAL DUCTWORK SHALL BE THERMALLY INSULATED AND WEATHERPROOFED UTILISING P80 SHEETING.
  3. ALL PLANT AND DUCTWORK ON LOCATED ON THE SECOND FLOOR SHALL BE INSTALLED ON BRICK FOOT BRACKETRY AND SUPPORTS.
  4. YOU ARE ADVISED THAT THE CONTRACTOR SHALL BE RESPONSIBLE FOR THE PROVISION OF ALL NECESSARY GRILLES/FUSERS WHERE APPROPRIATE TO FACILITATE ADEQUATE DRAINAGE OF EACH SYSTEM.
  5. FIRE DAMPERS SHALL BE INSTALLED WITHIN THE THROUGH THE ROOF PENETRATIONS TO PREVENT THE PASSAGE OF FIRE THROUGH EITHER SIDE.
  6. ALL AIRWAYS SHALL BE INSTALLED COMPLETE WITH ATTENUATION.
  7. THE CONTRACTOR SHALL ALLOW FOR ALL NECESSARY SETBACKS TO THE DUCTWORK TO ALLOW FULL PENETRATION OF THE ROOF SERVICES.
  8. THE CONTRACTOR SHALL ALLOW FOR ALL NECESSARY SETBACKS TO THE DUCTWORK TO ALLOW FULL PENETRATION OF ALL PLANT ITEMS AND ANCILLARY DUCTWORK EQUIPMENT WITH ALL SYSTEMS.
  9. ALL 90° RECTANGULAR / SQUARE BENDS SHALL BE COMPLETE WITH TURNING VENTS.
  10. FINAL SELECTION (AND DIMENSIONS) OF AHU 01 AND 02 IS TO BE COMPLETED.

Ref	Date	Issued For	By	DL	DL
P1	23/01/15	ORIGINAL ISSUE	PP	DL	DL
			PP	DL	DL

FOR THE RECORD THE CONTRACTOR OF THIS DRAWING IS RESPONSIBLE FOR THE DESIGN AND CONSTRUCTION OF THE WORKS SHOWN HEREON. THE CONTRACTOR SHALL BE RESPONSIBLE FOR THE PROVISION OF ALL NECESSARY GRILLES/FUSERS WHERE APPROPRIATE TO FACILITATE ADEQUATE DRAINAGE OF EACH SYSTEM.

Client GLEEDS

Project HOLBORN POLICE STATION

Office BIRMINGHAM

Division BUILDING SERVICES

Title 1ST FLOOR FLAT ROOF PROPOSED VENTILATION WORKS

Drawn	PP	Check	DL	Date	JAN 15
Checked	DL	Scale	@ 1:50		
Approved	DL	Status	PLANNING		

