



- 1 Existing timber framed reception desk removed. New arched opening created by part-demolishing existing wall.
- 2 Existing entrance canopy including all supports, signage removed
- 3 TV removed
- 4 Stairlift and all supports removed
- 5 Wall cleared of all pictures, sockets, outlets, conduit
- 6 Suspended lights removed
- 7 Door removed (all frames surrounding door to be retained)
- 8 Existing entrance doors removed (including timber overpanel)
- 9 Fence/Gate removed
- 10 CCTV camera repositioned away from location of proposed signage
- 11 Green wall paint removed
- 12 Doors to be repainted new colour
- 13 Radiator removed

All dimensions to be checked on site

**notes**

- 06.02.15 planning issue  
 rev

**Section AA  
 Demolitions**

**title**

1403\_P\_1201  
 drawing number

