

Historical image of Hampstead General Hospital – note the basement windows and expected depth of the foundations.

Ground movement

A study of the impact of the building on ground movements and impacts on the LINAC building and St Stephen's Church has been undertaken. Refer to Geotechnical Consulting Group Report 'Notes on Movements associated with Excavation' dated January 2015. The ground heave assessment in the vicinity of the excavation indicates that there will be very little movement of the ground in the long term and so movements of buildings outside the site footprint should be negligible in the long term. The LINAC building is founded on piles and, in the long term, movements should be negligible. In considering St Stephen's Church, ground movement may be associated with unloading of the ground during excavation as well as movements of the ground retaining structures. Based on the current proposals, the analysis shows that damage to the church should not exceed damage category 0 (negligible), hairline cracks less than about 0.1mm. In developing the design proposals for the new building and temporary works, the contractor should revisit the ground movement analysis and confirm that any impacts on all adjacent buildings remain negligible.

Flood Risk

The Site lies within Environment Agency Flood Zone 1 and therefore is not at risk of fluvial flooding. There is a risk of sewer flooding at the site, as this was the cause of flooding in 1975 and 2002. The contractor should develop a sustainable drainage scheme to attenuate the additional run-off from the Site. Refer to the Flood Risk Assessment by ESI Consultants document: 62361.01.00R1, October 2014.



GEOTECHNICAL CONSULTING GROUP

52A Cromwell Road London SW7 5BE United Kingdom Tel: +44 (0) 20 7581 8348
Fax: +44 (0) 20 7584 0157
Email: admin@gcg.co.uk

Geotechnical Consulting Group LLP is a partnership registered in England No OC356005 the registered address of which is as above.

BUILDING DESIGN PARTNERSHIP

PEARS BUILDING

NOTE ON MOVEMENTS ASSOCIATED WITH EXCAVATION

REVISION 0

January 2015

1 Introduction

It is proposed to construct a new building (the Pears Building) on the Royal Free Hospital site. The new building will be partly on the site of the existing car park and partly in a currently undeveloped area. Where the new building is on the existing car park footprint, there is very little excavation required. However, the southern part of the building will require around 7m of excavation and in the areas to the north-west of the new building around 4m of excavation outside the footprint of the car park is required.

This note assesses the impact of these excavations on the LINAC building, immediately adjacent to the deeper excavation, and St Stephen's Church, to the north-west of the site.

2 Heave assessment

Ground heave in the vicinity of the excavations has been modelled using the computer program PDISP. This requires an assessment of soil stiffness parameters.

In the ground investigation (RSK, 2014), underneath a covering of Made Ground, London Clay was encountered for the full depth of the boreholes. The London Clay is likely to be relatively thick in this area of London. The ground investigation indicates that the undrained shear strength, $c_{\rm u}$, of the London Clay is around 70kPa near the surface (at around 70mOD) and increases with depth. In the PDISP analyses, the undrained stiffness, $E_{\rm u}$ of the clay has been taken to be given by $450c_{\rm u}$, increasing to 225MPa at 0mOD, which was taken to be the base of the London Clay and a rigid boundary to the analyses.

Figures 1 and 2 show contours of short term movement at the end of excavation. These are both for the same analysis, but Figure 1 shows contours of movement in the immediate vicinity of the site, while Figure 2 shows movements in the vicinity of St Stephens Church.

The proposed building will be supported on piles. Consequently, there will be very little movement of the ground in the long term and so movements of buildings outside the site footprint should be negligible in the long term.

3 Impact on buildings

3.1 LINAC building

The LINAC building is piled and the wall closest to the site currently acts as and has presumably been designed as a retaining wall for the soil which will be excavated for the new construction. The excavation may result in some small lateral movements of the building as the soil pressure is removed. It is presumed that this would simply be reversing movements that occurred in the early life of the building when the soil was placed against the wall.

The short term potential heave movements in Figure 1, suggest that the ground will try to heave by up to around 10mm immediately adjacent to the proposed development. It should be noted that elastic analyses such as those carried out here tend to exaggerate the magnitude of movements outside the immediate area of loading or unloading.

Drawings of the LINAC building do not suggest that there is any compressible/collapsible material under its basement slabs. Consequently, the potential heave will be manifest as an increase in pressure under the basement slab adjacent to the excavation. Depending on the current conditions, this may simply serve to reduce the current pile loads and result in very little movement of the building, or it could result in all of the potential heave being manifest as movement of the building.

The LINAC building substructure appears to be fairly robust and surrounded by solid concrete walls. Consequently, it is considered unlikely that the maximum 'free' heave would manifest as movement of the building and that the worst case movement might be of the order of 5mm, occurring as a tilt across the width of the building, with very little distortion. Consequently, any resulting damage to the existing building should not exceed damage category 0 (negligible) of the damage classification shown in Figure 3. The impact of the potential tilt (approximately 1:2500) on any equipment should be considered.

There will be a partial reversal of any movements following loading associated with the new building and associated earthworks. In the long term, movements should be negligible.

3.2 St Stephen's Church

Short term movements as a result of unloading due to excavation as they might apply to St Stephen's Church are shown in Figure 2. These indicate that movements should not exceed ½mm. In addition, it should be noted that elastic analyses such as those carried out here tend to exaggerate the magnitude of movements outside the immediate area of loading or unloading, so the actual movements should be even less than this.

In addition to movements associated with unloading of the ground, there is also the potential for lateral and vertical movements associated with inward movement of the ground around retaining structures. While the form of the retaining structure to be used for the proposed excavations is currently not finalised, it is useful to look at the movements around excavations in the database of observed movements in CIRIA report C580 (Gaba et al, 2003).

These indicate that horizontal and vertical movements reduce to zero within a distance of four times the excavation depth from the line of the wall. The nearest point on St Stephen's Church is around 24m from the 4m deep excavation and over 40m from the 7m deep excavation. Consequently the church is more than four times the excavation depth away from the excavation and so movements associated with the formation of the excavation should be negligible provided the excavation is well supported.

There will be a partial reversal of any movements following loading associated with the new building. In the long term, movements should be negligible.

Consequently it is considered that damage to the church should not exceed damage category 0 (negligible) of the damage classification shown in Figure 3.

4 References


RSK. 2014. RFT Institute of Immunology and Transplantation, NW3 2PF. Geoenvironmental and geotechnical site assessment. Report ref: 27119-01 (00).


Gaba, A R, Simpson, B, Powrie, W & Beadman, D R. 2003. CIRIA C580: Embedded retaining walls – guidance for economic design.

DISCLAIMER

This report (as well as any letters, information, opinions and advice provided to you) is the sole property of Geotechnical Consulting Group LLP and is and must remain strictly private and confidential at all times. The possession of this document does not, in any manner, constitute a right to reproduce or disclose the whole or any part of it to any third party. Neither the report nor any information contained in it should be used by anyone other than Building Design Partnership and can only be used by Building Design Partnership for the purpose for which it was originally proposed. Geotechnical Consulting Group LLP is not responsible for information used in this report which has been supplied to it by Building Design Partnership or any other third party. This report does not constitute or represent verification for purpose. The report should not be reproduced (in whole or in part), referred to in any other document or made available to any third party (in any format) without the prior written consent of Geotechnical Consulting Group LLP.

FIGURES





g category
a direct
1
ormal
to
may
ıks or
mm.
required.
linings.
me
tightness.
. Typical
be patched
and
eplaced.
pipes
mpaired.
r several
t and
rs and
torted,
g ² or
ng in
ıl crack
nds on
rtial or
walls
WS
ability.

 $^{^1}$ Note: Boscardin & Cording (1989) describe the damage corresponding to the tensile strain in the range 0.015 - 0.3%. as 'moderate to severe'. However, none of the cases quoted by them exhibit severe damage for this range of strains. There is therefore no evidence to suggest that tensile strains up to 0.3% will result in severe damage.

 $^{^2}$ Note: Local deviation of slope, from the horizontal or vertical, of more than 1/100 will normally be clearly visible. Overall deviations in excess of 1/150 are undesirable.



Building Design Partnership	
Pears Building	Figure
Classification of potential building damage (from Gaba et al, 2003)	3