

Schedule of removals:

- 1. Non-original door, architrave and ironmongery ironmongery
- 2. Non-original fanlight over door
- 3. Section of dado rail in dining room directly affected by removal of partition
- 4. Section of partition, highlighted above, which opening up works show is of recent construction
- 5. Section of skirting in dining room directly affected by removal of partition

Additional removals will remove one kitchen unit.

General Notes Project Address Revisions ARCHITECTS engineers drawings.5. Dimensions critical to proposed building works must be checked on site before Drawing Other notes 117 Great Western Studios tel 020 3214 3255 Demolitions building works commences, as certain assumptions have been made due to lack of accessibility and anomalies in the existing building. mail@pitmantozer.com Ground Floor Plan www.pitmantozer.com

Proposed Demolitions Plan - Ground Floor Α

3 (m)

PITMAN TOZER

65 Alfred Road London W2 5EU

