



Walls to be demolished

Refurbishment and replacement of windows to be read in Window Schedule

Refer to Schedule of Works and Design and Access Statement for further detailed description of demolition works

110mm partition walls to be removed to return to original volume

PVC porch to be removed

Section of wall to be removed

Dividing screen to be removed and re-used as screen between 0.24 and 0.37/0.38

Section of wall to be removed

Section of wall to be removed to reveal chimney breast

Section of wall to be removed

Servery hatch to be removed

Stud walls to be removed inc. sanitary

Ceiling in Classroom to be removed

Stud walls around reception to be removed

Removal of Garden Shed

Removal of boundary wall between piers

Sections of walls to be removed

