


NOTES CONT'D

14. THE MECHANICAL CONTRACTOR TO ALLOW FOR ALL NECESSARY DEVICES REQUIRED TO FULLY BALANCE THE HEATING SYSTEM, WHETHER INDICATED ON THE DRAWINGS OR NOT.
15. LOCATION OF RADIATORS TO BE FULLY ACCOMMODATED BY THE CONTRACTOR WITH THE ARCHITECTURAL LAYOUT
16. FOR FURTHER DETAILS PLEASE REFER TO HEATING INSTALLATION SCHEMATICS.
17. PIPEWORK DROPPING INSIDE PARTITION TO BE WELDED. TEES AND ELBOWS TO BE ON OUTSIDE OF PARTITIONS TO BE BOXED IN BY BUILDER.
18. ALL HOLES THROUGH WALLS/FLOORS/ROOF SHALL BE FORMED AND MADE GOOD BY THE MAIN CONTRACTOR.

NOTES

1. THIS DRAWING SHALL BE READ IN CONJUNCTION WITH THE MECHANICAL SPECIFICATION AND RELEVANT ARCHITECTS AND ENGINEER DRAWINGS.
2. DETAILED INSTALLATION DRAWINGS MUST BE PROVIDED BY THE MECHANICAL SUB-CONTRACTOR IN ACCORDANCE WITH THE SPECIFICATION.
3. ALL PIPEWORK INSTALLATIONS TO BE PRESSURE TESTED PRIOR TO OPERATION OF THE SYSTEM.
4. ALTHOUGH NOT SHOWN, AT EACH HIGH POINT, AIR VENTS SHALL BE INSTALLED AND AT EACH LOW POINT DRAIN COCKS SHALL BE INSTALLED.
5. ALL PIPEWORK THAT PASSES THROUGH FIRE BARRIER / COMPARTMENTS SHALL BE FIRE PROTECTED BY SUFFICIENT MEANS REFER TO SPECIFICATIONS.
6. BRACKETS AND SUPPORTS ARE NOT SHOWN FOR CLARITY. ALL NECESSARY SUPPORTS / BRACKETS FOR PIPEWORK, VALVES, FLANGES, UNIONS ETC. SHALL BE INCLUDED AS DESCRIBED WITHIN THE MECHANICAL SPECIFICATION.
7. THERMAL INSULATION IS NOT SHOWN FOR CLARITY. ALL NECESSARY THERMAL INSULATION SHALL BE INCLUDED AS DESCRIBED WITHIN THE MECHANICAL SPECIFICATION.
8. THIS DRAWING SHOWS DESIGN INTENT. THEY ARE NOT CONSTRUCTION DRAWINGS AND THEREFORE DO NOT SHOW ALL BENDS, TEES, SETS ETC., THAT MAY BE NECESSARY TO LOCATE SERVICES CORRECTLY TO AVOID CLASHES AND MAXIMISE MAINTENANCE ACCESS. THE CONTRACTOR IS NEVERTHELESS DEEMED TO HAVE INCLUDED ALL SUCH MATERIALS ETC. AS REQUIRED TO PRODUCE A COMPLETE FULLY CO-ORDINATED LAYOUT.
9. ALL FLOW MEASUREMENT DEVICES SHALL BE INSTALLED AT LEAST TO DIAMETERS UPSTREAM AND 5 DIAMETERS DOWNSTREAM OF ANY FITTINGS AND IN ACCORDANCE WITH MANUFACTURERS RECOMMENDATIONS.
10. THE MECHANICAL CONTRACTOR MUST ALLOW FOR ANY NECESSARY CHANGES IN PIPE SIZE FOR COMMISSIONING STATIONS.
11. THE MECHANICAL CONTRACTOR SHALL CALCULATE ANY EXPANSION REQUIREMENTS AND WHERE APPLICABLE ACCOMMODATE THIS NATURALLY WITH BENDS, SETS ETC. WHERE THIS IS NOT POSSIBLE THE MECHANICAL CONTRACTOR SHALL ALLOW FOR BELLOW, EXPANSION LOOPS AND ANCHOR POINTS.
12. THE MECHANICAL CONTRACTOR SHALL BE RESPONSIBLE FOR SURVEYING SITE AND PRODUCING FULLY DIMENSIONED WORKING / FABRICATION DRAWINGS. ALL WORKING DRAWINGS SHALL BE FULLY CO-ORDINATED WITH OTHER TRADES AND BUILDING DETAILS, INCLUDING CEILING / STEEL DETAILS.
13. ALL RADIATORS SHALL BE INSTALLED WITH TRV'S & LSTV'S TO MANUFACTURERS RECOMMENDATIONS.



- LEGEND:**
- PREWORK DROP
 - RADIATOR
 - LOW SURFACE TEMPERATURE RADIATOR
 - PREWORK AT HIGH LEVEL
 - PREWORK AT LOW LEVEL
 - UNDERFLOOR PIPEWORK
 - THERMOSTAT (WALL MOUNTED)

couchperrywilkes
Engineering change®

Birmingham | +44(0) 121 709 6000
 Nottingham | +44(0) 115 924 3434
 Cambridge | +44(0) 1480 645 7488
 Leeds | +44(0) 113 247 7070
 Bristol | +44(0) 11 315 8011
 Leicester | +44(0) 116 248 6410
 London | +44(0) 207 254 8722

CHPW.COM
 Follow us @couchperrywilkes

CLIENT
 LAUDERDALE HOUSE TRANSFORMED
 WATERLOO PARK
 GREATER LONDON

PROJECT
 MECHANICAL SERVICES
 HEATING SERVICES
 GROUND FLOOR

SCALE
 1:50 (A1)

DATE
 2015

BY
 AL GF

DRAWING NUMBER
 103286/M/101

REV
 T1

FILE: 103286-M-101