2015

(1) CAMDEN COMMERCIAL LIMITED

and

(2) NATIONAL WESTMINSTER BANK PUBLIC LIMITED COMPANY

and

(3) THE MAYOR AND BURGESSES OF THE LONDON BOROUGH OF CAMDEN

A G R E E M E N T relating to land known as

16 Rochester Mews London NW1 9JB

pursuant to Section 106 of the Town and Country Planning Act 1990 (as amended) and Section 278 of the Highways Act 1980

Andrew Maughan
Borough Solicitor
London Borough of Camden
Town Hall
Judd Street
London WC1H 9LP

Tel: 020 7974 5647 Fax: 020 7974 2962

CLS/PK/1781.88_final

THIS AGREEMENT is made the 30th day of March 2015

BETWEEN:

- CAMDEN COMMERCIAL LIMITED (registered under company number 05426080)
 whose registered office is at 14 The Drive, Buckhurst Hill, Essex, 1G9 5RB
 (hereinafter called "the Owner") of the first part
- 2. NATIONAL WESTMINSTER BANK PUBLIC LIMITED COMPANY (registered under company number of 00929027) whose registered address is at 135 Bishopsgate,

 London, EC2M 3UR (hereinafter called "the Mortgagee") of the second part
- THE MAYOR AND BURGESSES OF THE LONDON BOROUGH OF CAMDEN of Town Hall, Judd Street, London WC1H 9LP (hereinafter called "the Council") of the third part

WHEREAS

- 1.1 The Owner is registered at the Land Registry as the freehold proprietor with title absolute of the Property under title numbers LN249430 and NGL453368 subject to a charge to the Mortgagee.
- 1.2 The Owner is the freehold owner of and is interested in the Property for the purposes of Section 106 of the Act.
- 1.3 The Planning Application for the development of the Property was submitted to the Council and validated on 17th October 2014 and the Council resolved to grant permission conditionally under reference number 2014/5510/P subject to conclusion of this legal Agreement.
- 1.4 The Council is the local planning authority for the purposes of the Act for the area in which the Property is situated and considers it expedient in the interests of the proper planning of its area that the development of the Property should be restricted or regulated in accordance with this Agreement.

- 1.5 As local highway authority the Council considers the Highways Works to be carried out pursuant to this section 278 Agreement to be in the public benefit.
- 1.6 For that purpose the Owner is willing to enter into this Agreement pursuant to the provisions of Section 106 of the Act.
- 1.7 The Mortgagee as mortgagee under a legal charge registered under title numbers LN249430 and NGL453368 and dated 4th May 2005 is willing to enter into this Agreement to give its consent to the same.

2. **DEFINITIONS**

In this Agreement the following expressions (arranged in alphabetical order) shall unless the context otherwise requires have the following meanings:-

2.1	"the Act"	the Town and Country Planning Act 1990 (as amended)
2.2	"the Agreement"	this planning obligation made pursuant to Section 106 of the Act
2.3	"Business Parking Bay"	a parking place designated by the Council by an order under the Road Traffic Regulation Act

order under the Road Traπic Regulation Act
1984 or other relevant legislation for use by
businesses of the locality in which the
Development is situated

2.4 "Business Parking Permit" a parking permit issued by the Council under section 45(2) of the Road Traffic Regulation Act 1984 allowing a vehicle to park in a Business Parking Bay

2.5 "the Certificate of

Practical Completion"

the certificate issued by the Owner's contractor or architect or project manager certifying that the Development has been completed

2.6 "Construction Management Plan"

a plan setting out the measures that the Owner will adopt in undertaking the construction of the Development using good site practices in accordance with the Council's Considerate Contractor Manual to ensure the Construction Phase of the Development can be carried out safely and with minimal possible impact on and disturbance to the surrounding environment and highway network including (but not limited to):-

- (i) a statement to be submitted to Council giving details of the environmental protection highways safety and community measures proposed to be adopted by the Owner in order to mitigate and offset potential or likely effects and impacts arising from the demolition of the Existing Buildings or structures on the Property and the building out of Development:
- (ii) incorporation of the provisions set out in the First Schedule annexed hereto
- (iii) incorporation of the provisions set out in the Second Schedule annexed hereto
- (iv) proposals to ensure there are no adverse effects on the conservation area features
- (v) effects on the health and amenity of local residences site construction workers local

businesses and adjoining developments undergoing construction;

- (vi) amelioration and monitoring measures over construction traffic including procedures for notifying the owners and or occupiers of the residences and businesses in the locality in advance of major operations delivery schedules and amendments to normal traffic arrangements (if any);
- (vii) the inclusion of a waste management strategy for handling and disposing of construction waste; and
- (viii) identifying means of ensuring the provision of information to the Council and provision of a mechanism for monitoring and reviewing as required from time to time

2.7 "the Construction Phase"

the whole period between

- (i) the Implementation Date and
- (ii) the date of issue of the Certificate of Practical Completion
- 2.8 "the Council's Considerate Contractor Manual"

the document produced by the Council from time to time entitled "Guide for Contractors Working in Camden" relating to the good practice for developers engaged in building activities in the London Borough of Camden

2.9 "the Development"

demolition of existing Class B1/B8 unit and erection of a 4 storey building containing replacement business space (Class B1/B8) on

ground floor and five self-contained flats (Class C3) plus balconies on 1st-3rd floors as shown on drawing numbers Design and Access Statement Rev B dated January 2015; Lifetime Homes Statement dated August 2014 Rev C; Daylight and sunlight report by GVA dated September 2014; Energy Statement and BREEAM Preassessment report by eb7 dated 13th October 2014; FES- 001, 002, 02A, 003, 004, 005, 006, 007, 008, 06B, 07B, 08B, 10A, 012A, 014; email from agent dated 13th January 2015

2.10 "the Education Contribution"

the sum of £10,748 (ten thousand seven hundred and forty-eight pounds) to be paid by the Owner to the Council in accordance with the terms of this Agreement and to be applied by the Council in the event of receipt towards education needs arising in the London Borough of Camden

2.11 "the Existing Buildings"

the Class B1/B8 unit existing at the Property at the date hereof

2.12 "the Highways Contribution"

the sum of £2,533 (two thousand five hundred and thirty-three pounds) to be paid by the Owner to the Council in accordance with the terms of this Agreement and to be applied by the Council in event of receipt for the carrying out works to the public highway and associated measures in the vicinity of the Property such works to include the following ("the Highways Works"):

- (i) to repave the footway adjacent to the Property;
- (ii) any other works required as a direct result of the Development (such works as considered necessary by the Council)

all works will be subject to final measure and any level adjustment required and for the avoidance of doubt the Council in accepting this sum does not undertake any responsibility in connection with any required statutory undertakers works and excludes any statutory undertaker's costs

2.13	"the Implementation
Date"	

the date of implementation of the Development by the carrying out of a material operation as defined in Section 56 of the Act and references to "Implementation" and "Implement" shall be construed accordingly

2.14 "King's Cross Construction Skills Centre"

the Council's flagship skills construction training centre providing advice and information on finding work in the construction industry

2.15 "the Level Plans

plans demonstrating the levels at the interface of the Development the boundary of the Property and the Public Highway

2.16 "Local Procurement Code"

the code at the Fifth Schedule annexed hereto

2.17 "Occupation Date"

the first date when any part of the Development is occupied and the phrases "Occupy", "Occupied" and "Occupation" shall be construed accordingly

2.18 "the Parties"

the Council the Owner and the Mortgagee

2.19 "the Planning Application"

a planning application in respect of the development of the Property submitted to the Council and validated on 17th October 2014 for which a resolution to grant permission has been

passed conditionally under reference number 2014/5510/P subject to conclusion of this Agreement

2.20 "Planning Obligations Monitoring Officer"

a planning officer of the Council from time to time allocated to deal with all planning obligations pursuant to S106 of the Act to whom all notices, correspondence, approvals etc must be sent in the manner prescribed at clause 6.1 hereof

2.21 "the Planning Permission"

a planning permission granted for the Development substantially in the draft form at the Third Schedule annexed hereto

2.22 "the Property"

the land known as 16 Rochester Mews, London, NW1 9JB the same as shown edged red on the plan at the Fourth Schedule annexed hereto

2.23 "the Public Open Space Contribution"

the sum of £6,559 (six thousand five hundred and fifty-nine pounds) to be paid by Owner to the Council in accordance with the terms of this Agreement and to be applied by the Council in the event of receipt for the improvement maintenance and upkeep of existing public open spaces and/or nature conservation improvements to parks and open space and/or the obtaining of land to make public open spaces in the vicinity of the Development

2.24 "Residents Parking Bay"

a parking place designated by the Council by an order under the Road Traffic Regulation Act 1984 or other relevant legislation for use by

residents of the locality in which the Development is situated

2.25 "Residents Parking Permit"

A parking permit issued by the Council under section 45(2) of the Road Traffic Regulation Act 1984 allowing a vehicle to park in Residents Parking Bays

2.26 "the Public Highway"

any carriageway footway and/or verge adjoining the Property maintainable at public expense

2.27 "the Sustainability Plan"

a plan including a post construction review securing the incorporation of sustainability measures in the carrying out of the Development in its fabric and in its subsequent management and occupation which shall:-

- Establishment Environmental Assessment Method assessment with a target of achieving a Very Good Excellent or Outstanding rating and attaining at least 60% of the credits in each of Energy and Water and 40% of the credits in Materials categories;
- (ii) achieve at least Level 4 of the Code for Sustainable Homes attaining at least 50% of the credits in each of the Energy Water and Materials categories to be carried out by a recognised independent verification body in respect of the Property;
- (iii) include a pre-Implementation review by an appropriately qualified and recognised independent verification body in respect of the Property certifying that the measures incorporated in the Sustainability Plan are

achievable and satisfy the aims and objectives of the Council's strategic policies on sustainability contained within its Development Plan; and

(iv) measures to secure a post construction review of the Development by an appropriately qualified and recognised independent verification body in respect of the Property certifying that the measures incorporated in the Sustainability Plan have been achieved in the Development and will be maintainable in the Development's future management and occupation

NOW THIS DEED WITNESSETH as follows:-

- 3.1 This Agreement is made in pursuance of Section 106 of the Act, and is a planning obligation for the purposes of Section 106 as aforesaid, and shall be enforceable by the Council against the Owner as provided herein and against any person deriving title to any part of the Property from the Owner and insofar as it is not a planning obligation its provisions may be enforceable by the Council under any relevant statutory powers.
- 3.2 Words importing the singular shall include the plural and vice versa and any words denoting actual persons shall include companies corporations and other artificial persons.
- 3.3 Any reference to a specific statute or statutes include any statutory extension or modification amendment or re-enactment of such statute and any regulation or orders made under such statute.
- 3.4 The clause and paragraph headings do not form part of this Agreement and shall not be taken into account in its construction of interpretation.

- It is hereby agreed between the Parties that save for the provisions of clauses 1, 2, 3, 5, 6, 7 and 8 hereof all of which shall come into effect on the date hereof the covenants undertakings and obligations contained within this Agreement shall become binding upon the Owner upon the Implementation Date.
- 3.6 The Council hereby agrees to grant the Planning Permission on the date hereof.
- 3.7 The Parties save where the context states otherwise shall include their successors in title.
- 3.8 The Parties acknowledge that the Development shall be treated as being permanently designated as "car free" housing in accordance with Clause 4.1 for all relevant purposes.

4. OBLIGATIONS OF THE OWNER

The Owner hereby covenants with the Council as follows:-

4.1 CAR FREE

- 4.1.1 To ensure that prior to occupying any residential unit forming part of the Development each new resident of the Development is informed by the Owner of the Council's policy that they shall not be entitled (unless they are the holder of a disabled persons badge issued pursuant to Section 21 of the Chronically Sick and Disabled Persons Act 1970) to be granted a Residents Parking Permit to park a vehicle in a Residents Parking Bay and will not be able to buy a contract to park within any car park owned, controlled or licensed by the Council.
- 4.1.2 To ensure that prior to occupying any commercial unit in any part of the Development each new occupant of a commercial unit forming part of the Development is informed by the Owner of the Council's policy that they shall not be entitled (unless they are the holder of a disabled persons badge issued pursuant to Section 21 of the Chronically Sick and Disabled Persons Act 1970) to be granted a Business Parking Permit to park a vehicle in a Business Parking Bay and will not be able to buy a contract to park within any car park owned, controlled or licensed by the Council.

- 4.1.3 The Owner for itself and its successors in title to the Property hereby acknowledges that the provision in Clause 4.1.1 and 4.1.2 above will remain permanently.
- 4.1.4 On or prior to the Occupation Date the Owner shall inform the Council's Planning Obligations Monitoring Officer of the official unit numbers of all units forming part of the Development (as issued and agreed by the Council's Street Name and Numbering Department), identifying those units that in the Owner's opinion are affected by the Owner's obligations under Clauses 4.1.1 and 4.1.2 of this Agreement.

4.2 CONSTRUCTION MANAGEMENT PLAN

- 4.2.1 On or prior to the Implementation Date to provide the Council for approval a draft Construction Management Plan.
- 4.2.2 Not to Implement nor allow Implementation of the Development until such time as the Council has approved the Construction Management Plan as demonstrated by written notice to that effect (such approval not to be unreasonably withheld or delayed).
- 4.2.3 The Owner acknowledges and agrees that the Council will not approve the Construction Management Plan unless it demonstrates to the Council's reasonable satisfaction that the Construction Phase of the Development can be carried out safely and with minimal possible impact on and disturbance to the surrounding environment and highway network.
- 4.2.4 To ensure that throughout the Construction Phase the Development shall not be carried out otherwise than in strict accordance with the requirements of the Construction Management Plan and not to permit the carrying out of any works comprised in demolition or building out the Development at any time when the requirements of the Construction Management Plan are not being complied with and in the event of non compliance with this sub-clause the Owner shall upon notice from the Council forthwith take any steps required to remedy such non-compliance.

4.3 EDUCATION CONTRIBUTION

- 4.3.1 On or prior to the Implementation Date to pay to the Council the Education Contribution.
- 4.3.2 Not to Implement or to permit Implementation until such time as the Council has received the Education Contribution.

4.4 HIGHWAYS

- 4.4.1 On or prior to the Implementation Date to:-
 - (i) pay to the Council the Highways Contribution in full; and
 - (ii) submit to the Council the Level Plans for approval.
- 4.4.2 Not to Implement or to allow Implementation until such time as the Council has:-
 - (i) received the Highways Contribution in full; and
 - (ii) approved the Level Plans as demonstrated by written notice to that effect (such approval not to be unreasonably withheld or delayed).
- 4.4.3 For the avoidance of doubt the Owner acknowledges that the Council has the right reserved to it to construct the Public Highway to levels it considers appropriate and does not undertake any responsibility in connection with any required statutory undertakers works and that the Highways Contribution excludes any statutory undertaker's costs.
- 4.4.4 On completion of the Highway Works the Council may provide to the Owner a certificate specifying the sum ("the Certified Sum") expended by the Council in carrying out the Highway Works.
- 4.4.5 If the Certified Sum exceeds the Highway Contribution then the Owner shall within fourteen days of the issuing of the said certificate pay to the Council the amount of the excess.

4.5 LOCAL EMPLOYMENT

- 4.5.1 In carrying out the works comprised in the Construction Phase of the Development the Owner shall use its reasonable endeavours to ensure that no less than 20% of the workforce is comprised of residents of the London Borough of Camden.
- 4.5.2 In order to facilitate compliance with the requirements of sub-clause 4.9.1 hereof the Owner shall use reasonable endeavours to work in partnership with:
 - (i) King's Cross Construction Skills Centre; and
 - (ii) take the following specific measures to ensure:-
 - (a) all contractors and sub-contractors provide information about all vacancies arising as a result of the Construction Phase of the Development to King's Cross Construction Skills Centre;
 - (b) that prior to any advertisement or notice being placed with any advertising or employment agency or similar organisation for a period of at least one (1) week the King's Cross Construction Skills Centre is notified of all vacancies arising from the building contract for the Development for employees, self-employees, contractors and subcontractors;
 - (c) that at all times during the Construction Phase no less than 2 (two) work placements shall be provided at the Development always ensuring each work placement (as the case may be) shall be:-
 - (1) recruited through the King's Cross Construction Skills Centre;
 - (2) placed for a period of not less than 2 weeks; and
 - (3) paid at a rate not less than the national minimum wage.
 - (d) that King's Cross Construction Skills Centre is supplied with a full labour programme for the lifetime of the Development (with sixmonthly updates) demonstrating
 - (1) what skills and employment are needed through the life of the programme, and
 - (2) measures to ensure that these needs are met as far as possible through the provision of local labour from residents of the London Borough of Camden
 - (e) the Council is provided with a detailed six-monthly labour return for monitoring the employment and self-employment profile of all workers referred by Kings Cross Construction Skills Centre and employed during the Construction Phase.

- 4.5.3 Pursuant to Clause 4.5.2 hereof the Owner shall pay to the Council the sum of £1,500 (one thousand five hundred pounds) for work placement employed on or prior to the date each construction industry apprentice commences employment.
- 4.4.4 During the Construction Phase the Owner shall use reasonable endeavours to provide training opportunities on site for employees resident within the London Borough of Camden and to provide a six-monthly statement setting out the details of candidates employed to the Kings Cross Construction Skills Centre.

4.5 LOCAL PROCUREMENT

- 4.5.1 Prior to Implementation to agree a programme (to include liaison with the Council's procurement service known as "i-CAM2" or any successor service) during the Construction Phase to provide opportunities for local businesses to bid and or tender for the provision of goods and service to the Development in accordance with the Council's Local Procurement Code.
- 4.5.2 On or prior to Implementation to meet with the Council's Labour Market and Economy Service's Local Procurement Team at least one month in advance of tendering contracts to agree the specific steps that will be taken to give effect to the Local Procurement Code.
- 4.5.3 To ensure that throughout the Construction Phase the Development shall not be carried out otherwise than in accordance with the requirements of the Local Procurement Code and in the event of non-compliance with this sub-clause the Owner shall upon written notice from the Council forthwith take any steps reasonably required by the Council to remedy such non-compliance.
- 4.5.4 To use reasonable endeavours to provide opportunities for local businesses to bid/tender for the provision of facilities management services and other post construction supply of goods and services.

4.6 PUBLIC OPEN SPACE CONTRIBUTION

- 4.6.1 On or prior to the Implementation Date to pay to the Council the Public Open Space Contribution.
- 4.6.2 Not to Implement or to permit Implementation until such time as the Council has received the Public Open Space Contribution.

4.7 SUSTAINABILITY PLAN

- 4.7.1 On or prior to the Implementation Date to submit to the Council for approval the Sustainability Plan.
- 4.7.2 Not to Implement nor permit Implementation until the Sustainability Plan has been approved by the Council as demonstrated by written notice to that effect (such approval not to be unreasonably withheld or delayed).
- 4.7.3 Not to Occupy or permit Occupation of the Property until a satisfactory post-completion review has been submitted to and approved by the Council in writing confirming that the measures incorporated in the Sustainability Plan as approved by the Council have been incorporated into the Property.
- 4.7.4 Following the Occupation Date the Owner shall not Occupy or permit Occupation of any part of the Development at any time when the Development is not being managed in strict accordance with the Sustainability Plan as approved by the Council and shall not Occupy or permit Occupation of the Development otherwise than in strict accordance with the requirements of the Sustainability Plan.

5. NOTICE TO THE COUNCIL/OTHER MATTERS

- 5.1 The Owner shall give written notice to the Council on or prior to the Implementation Date specifying that Implementation of the Development has taken or is about to take place.
- Within seven days following completion of the Development the Owner shall certify in writing to the Planning Obligations Monitoring Officer in the manner outlined at clause 6.1 hereof quoting planning reference 2014/5510/P the date upon which the Development is ready for Occupation.

- The Owner shall act in good faith and shall co-operate with the Council to facilitate the discharge and performance of all obligations contained herein and the Owner shall comply with any reasonable requests of the Council to have access to any part of the Property or any requests to provide documentation within the Owner's possession (at the Owner's expense) for the purposes of monitoring compliance with the obligations contained herein.
- 5.4 The Owner agrees declares and covenants with the Council that it shall observe and perform the conditions restrictions and other matters mentioned herein and shall not make any claim for compensation in respect of any condition restriction or provision imposed by this Agreement and further shall indemnify the Council for any expenses or liability arising to the Council in respect of breach by the Owner of any obligations contained herein save to the extent that any act or omission of the Council its employees or agents has caused or contributed to such expenses or liability.
- If satisfied as to the compliance of the Owner in respect of any obligation in this Agreement the Council shall (if requested to do so in writing and subject to payment of a fee of £1,000 in respect of each such obligation) provide through its Head of Legal Services a formal written certification of compliance, partial compliance or ongoing compliance (as and if appropriate) with the provisions of any such obligation.

6

- Submission of any plan to the Council for approval by the Council under the terms of this Agreement shall be made by the Owner to the Council sending the full document and any appendices in electronic format to the Planning Obligations Monitoring Officer referring to the names dates and Parties to this Agreement and citing the specific clause of this Agreement to which such plan relates quoting the planning reference 2014/5510/P.
- 5.7 Payment of the financial contribution pursuant to Clause 4 of this Agreement shall be made by the Owner to the Council sending the full amount in the form of a banker's draft to the Planning Obligations Monitoring Officer referring to the names dates and Parties to this Agreement and citing the specific clause of this Agreement to which such Contribution relates quoting planning reference 2014/5510/P or by Electronic Transfer directly to the National Westminster Bank of Hampstead Village, Enfield Customer Service Centre, PO Box 145 Baird Road Middlesex EN1 1FN quoting Sort

Code 50-30-03 and London Borough of Camden General Account no. 24299480 and to inform the Planning Obligations Monitoring Officer of such payment quoting the above details as if the payment had been made by Banker's Draft.

- All consideration given in accordance with the terms of this Agreement shall be exclusive of any value added tax properly payable in respect thereof and all parties other than the Council shall pay and indemnify the Council against any such value added tax properly payable on any sums paid to the Council under this Agreement upon presentation of an appropriate value added tax invoice addressed to the Owner.
- Any sums referred to in this Agreement as payable or to be applied by any party other than the Council under this Agreement shall be paid or applied TOGETHER WITH if such payment or application is made more than three months from the date of this Agreement a further sum ("A") being equal to the original sum payable ("B") multiplied by a figure being a fraction of which the All Items of Retail Prices ("the AIIRP") figure last published by the Central Statistical Office at the date hereof is the denominator ("X") and the last AIIRP figure published before the date such payment or application is made ("Y") less the last published AIIRP figure at the date hereof ("X") is the numerator so that

$$A = B \times (Y-X)$$

- 5.10 All costs and expenses payable to the Council under this Agreement shall bear interest at the rate of 4% above the Base Rate of the National Westminster Bank plc from time to time being charged from the date such payment is due until payment is made.
- 6. IT IS HEREBY AGREED AND DECLARED by the Parties hereto that:-
- 6.1 The provisions of Section 196 of the Law of Property Act 1925 (as amended) shall apply to any notice or approval or agreement to be served under or in connection with this Agreement and any such notice or approval shall be in writing and shall specifically refer to the name, date and Parties to the Agreement and shall cite the clause of the Agreement to which it relates and in the case of notice to the Council

shall be addressed to the London Borough of Camden, Planning Obligations Officer, Urban Design and Renewal, Planning and Public Protection, Culture and Environment Directorate, Town Hall Annex, Argyle Street, London WC1H 9LP quoting the planning reference number 2014/5510/P and in the case of any notice or approval or agreement from the Council this shall be signed by a representative of the Council's Environment Department.

- 6.2 This Agreement shall be registered as a Local Land Charge.
- 6.3 The Owner agrees to pay the Council its proper and reasonable legal costs incurred in preparing this Agreement on or prior to the date of completion of the Agreement.
- Nothing contained or implied in this Agreement shall prejudice or affect the Council's powers to enforce any specific obligation term or condition nor shall anything contained or implied herein prejudice or affect any provisions, rights, powers, duties and obligations of the Council in the exercise of its functions as Local Planning Authority for the purposes of the Act or as a local authority generally and its rights, powers, duties and obligations under all public and private statutes, bye laws and regulations may be as fully and effectually exercised as if the Council were not a party to this Agreement.
- Neither the Owner the Mortgagee nor their successors in title nor any person deriving title from them shall be bound by the obligations in this Agreement in respect of any period during which it no longer has an interest in the Property but without prejudice to liability for any breach committed prior to the time it disposed of its interest.
- 6.6 For the avoidance of doubt the provisions of this Agreement (other than those contained in this sub-clause) shall not have any effect until this Agreement has been dated.
- 6.7 If the Planning Permission is quashed or revoked or otherwise withdrawn or expires before effluxion of time for the commencement of development or is modified (other than by agreement with or at the request of the Owner) this Agreement shall forthwith determine and cease to have effect and the Council will effect cancellation of all entries made in the Register of Local Land Charges in respect of this Agreement.

7. MORTGAGEE EXEMPTION

The Mortgagee hereby consents to the completion of this Agreement and for the avoidance of doubt agrees to be bound by the said obligations only in the event that it becomes a mortgagee in possession of the Property.

8. RIGHTS OF THIRD PARTIES

The Contracts (Rights of Third Parties) Act 1999 shall not apply to this Agreement.

THE FIRST SCHEDULE Construction Management Plan Air Quality and Carbon Reduction

Requirements to control and minimise NOx, PM10, CO₂ emissions from construction sites and avoid nuisance and dust complaints.

A method statement shall be prepared and adopted as part of the Construction Management Plan to minimise gaseous and particulate matter emissions generated during the Construction Phase. The method statement shall identify the specific measures which will be implemented to control air pollution emissions during each of the following stages of the Construction Phase: (a) demolition; (b) ground breaking; and (c) construction/build.

The Construction Phase shall be carried out in accordance with the Best Practise Guidance Note "Control of dust and emissions from construction and demolition" published by London Councils, 2006. The risk rating of the site shall be defined in the method statement and determined using the risk assessment methodology in the Best Practise Guidance. Techniques to control dust from construction activities and emissions from vehicles and plant, and undertake air quality monitoring, shall conform to the 'medium' or 'high' risk categories outlined in the Best Practice Guidance.

The following best practise measures shall be included as a minimum in the method statement:-

A - Techniques to control PM10 and NOx emissions from vehicles and plant

- a) Low emission plant fitted with catalysts, diesel particulate filters or similar devices shall be used;
- Plant shall be well maintained, with routine servicing of plant and non-road mobile machinery (NRMM) to be completed in accordance with the manufacturers recommendations;
- c) Avoid the use of diesel or petrol powered generators and use mains electricity or battery powered equipment;
- d) Non-road mobile machinery (NRMM) shall use ultra low sulphur tax-exempt diesel and be fitted with appropriate exhaust after-treatment such as catalysts, diesel particulate filters as stated on the approved list managed by the Energy Saving Trust. Details of the plant and control equipment shall be included in the method statement.

- e) All construction vehicles shall comply with the Euro 4 emissions standard and where possible use low emission fuels and alternative technology.
- f) Plant and vehicles shall be located way from the closest receptors or house in closed environments where possible.

B - Techniques to control dust emissions from construction and demolition

- a) Keep site fencing, barriers and scaffolding clean using wet methods;
- b) Buildings to be demolished shall be wrapped
- c) Provide easily cleaned hard standing for vehicles and clean using wet sweeping methods;
- d) Provide the use of wheel-wash facilities near the site exit. Fit wheel-washes with rumble grids to dislodge accumulated dust and mud prior to leaving the site to avoid carrying dust or mud off the site;
- e) Inspect internal haul routes for integrity and instigate necessary repairs to the surface as soon as reasonably practicable;
- f) Routinely clean the Public Highways and accesses using wet sweeping methods especially during dry periods;
- g) Impose and signpost maximum speed limits of 10 mph on surfaced haul routes and work areas within the Site;
- h) Ensure all vehicles carrying loose or potentially dusty material to or from the site are fully sheeted;
- i) Store materials with the potential to produce dust away from site boundaries;
- j) Sheet, seal or damp down stockpiles of excavated material held on site;
- k) Any loose materials bought onto the site shall be protected by appropriate covering
- The site shall be dampened down during the working day and again at the end of the day to reduce the amount that is re-suspended dust.
- m) Ensure water suppression is used during demolition operations;
- n) Ensure mobile crushing and screening plant and cement batching plant which are regulated under the Local Air Pollution Prevention and Control regime operate in compliance with a Part B Permit. This shall be submitted to the local authority prior to operation.
- Site personnel shall be trained in dust mitigation and a manager shall be present for managing dust on site.

C - Air Quality Monitoring

- a) Throughout the Construction Phase continuous particulate matter (PM10) monitoring shall be undertaken. Two instruments will be deployed at the site boundary in a transect orientated to the prevailing wind direction, with a third monitor located at the nearest sensitive receptor. One monitor shall be co-located with an anemometer.
- b) Adequate quality assurance/quality control procedures shall be in place including monitor maintenance and calibration as well and data checking. PM10 data shall be collected automatically on an hour basis.
- c) A trigger action level for PM10 concentrations of 200µg.m⁻³ (15 minute average) shall be used to identify incidences of elevated dust emissions at the site boundary. The development site shall comply with the trigger action throughout the demolition and construction phases.
- d) An on-site alert system (email or SMS) shall be in place to notify appropriate staff that the trigger action level has been reached. Immediate and appropriate measures can be put in place to rectify abnormal particulate emissions. A procedure shall be established to deal with abnormal dust emissions. All incidences of abnormal particulate emissions leading to breaches of the trigger action level, shall be documented in the site log book (date and time), with details of the action take to remediate dust emissions.
- e) An e-mail specifying details of any alert to be sent out to the Council's air quality officer as soon as practicable following any breach of the site trigger action level.
- f) An electronic report shall be submitted to the Council's air quality officer every three months summarising the following information from each monitoring site – 24 hour average PM10 concentration, date and time of any breach of the trigger action level with the 15 minute mean concentration, prevailing wind direction and details of the cause of elevated dust emissions and mitigation measures.
- g) The Council shall be notified of any changes to the location and operation of dust PM10 monitoring instrumentation.
- h) A 24-hour phone hotline shall be set up so that residents can complain about high dust or PM10 levels directly to the developer.

The following items shall be included in the method statement:

- a) A specific timetable identifying the start and finish dates of each phase, including dust generating activities and PM10 monitoring.
- b) An inventory of stationary and fugitive dust, PM10 and NOx emission sources with an explanation of how these will be mitigated in accordance with the London Council's Best Practise Guidance.
- c) A map identifying the location of dust generating activities, plant equipment associated with emissions to air and PM10 monitors.
- d) An air quality monitoring protocol prepared in accordance with the requirements of section C.

D - Techniques to reduce CO₂ emissions from construction vehicles

A commitment from the Owner that contractors' vehicles involved in construction and demolition work will adopt 'green fleet management practices' that will result in a 10% reduction in tail-pipe CO₂ emissions over the duration of the construction phase. A green fleet management plan included in the method statement identifying measures to improve vehicle efficiency and reduce CO₂ emissions from construction vehicles. This could include the use of fuel monitoring equipment in vehicles, eco-driver training, accreditation with FORS (Freight Operator Recognition Scheme run by TfL) or SAFED (Safe and Fuel Efficient Driving run by the DfT) and use of low carbon vehicles such as hybrid electric, electric and bio-methane.

THE SECOND SCHEDULE Construction Management Plan

Highway Measures

A Construction Management Plan outlines how construction work will be carried out and how this work will be serviced (e.g. delivery of materials, set down and collection of skips), with the objective of minimising traffic disruption and avoiding dangerous situations and minimising the impact on local amenity. A Construction Management Plan should cover both demolition and construction phases of development. Details of the Construction Management Plan will relate to the scale and kind and location of the development and they should assess the impact on transport and on local amenity including road user amenity. Should any one of these criteria be considered not to be relevant, then specific justification, as to why that particular criterion is not relevant, will need to be provided. The Construction Management Plan should demonstrate that the following has been considered and where necessary the impacts mitigated:

(Note the term 'vehicles' used here refers to all vehicles associated with the implementation of the development, e.g. demolition, site clearing, delivering of plant, material and construction, staff parking etc)

- A brief description of the site, surrounding area and development proposals for which a) the Construction Management Plan applies.
- Proposed start and end dates for each phase of construction. b)
- The proposed working hours within which vehicles will arrive and depart. c)
- The access arrangements for vehicles. d)
- Proposed routes for vehicles between the site and the Transport for London Road e) Network (TLRN). Consideration should also be given to weight restrictions, low bridges and cumulative affects of construction on the highway. A map of the TLRN can be downloaded from the following site:
 - http://www.tfl.gov.uk/assets/downloads/TFL Base Map Master.pdf
- Typical sizes of all vehicles and the approximate frequency and times of day when f) they will need access to the site, for each phase of construction.
- Swept path drawings for any tight manoeuvres on vehicle routes to the site. g)
- Details (including accurate scaled drawings) of any highway works necessary to h) enable construction to take place.
- Parking and loading arrangement of vehicles and delivery of materials and plant to i) the site.

- j) Details of proposed parking bays suspensions and temporary traffic management orders.
- k) Proposed overhang (if any) of the public highway (scaffolding, cranes etc.).
- l) Details of hoarding required or any other occupation of the public highway.
- m) Details of how pedestrian and cyclist safety will be maintained, including any proposed alternative routes (if necessary), and any Banksman arrangements.
- n) Details of how traffic associated with the Development will be managed in order to reduce congestion.
- o) Details of any other measures designed to reduce the impact of associated traffic (such as the use of construction material consolidation centres).
- p) Details of how any significant amounts of dirt or dust that may be spread onto the public highway will be cleaned or prevented.
- q) Details of consultation on a draft Construction Management Plan with local residents, business, local groups (e.g. residents/tenants and business associations) and Ward Councillors. Details should include who was consulted, how the consultation was conducted and the comments received in response to the consultation. In response to the comments received, the Construction Management Plan should then be amended where appropriate and where not appropriate a reason should be given why not. The revised Construction Management Plan should also include a list of all the comments received. You are advised to check your proposed approach to consultation with the Council before carrying it out.
- r) Details of any Construction Working Group that will be set up, addressing the concerns of surrounding residents, as well as contact details for the person responsible for community liaison on behalf of the developer, and how these contact details will be advertised to the community.
- Details of any schemes such as the "Considerate Contractors Scheme" that the project will be signed up to should form part of the consultation and be notified to the Council. Contractors will also be required to follow the "Guide for Contractors Working in Camden" also referred to as "Camden's Considerate Contractor's Manual"
- Details of other construction sites in the local area and how your Construction Management Plan takes into consideration the cumulative effects of construction local to your site.
- u) All contractors and sub-contractors operating HGVs must meet all of the following conditions:-

- Operators must be a member of TfL's Fleet Operator Recognition Scheme
 (www.tfl.gov.uk/fors) or similar at the Bronze level.
- 2) All drivers must have undertaken cycle awareness training such as the Safe Urban Driver module through FORS or similar.
- 3) All vehicles associated with the construction of the Development must:
 - i. Have Side Guards fitted, unless it can be demonstrated to the reasonable satisfaction of the Employer, that the Lorry will not perform the function, for which it was built, if Side Guards are fitted.
 - ii. Have a close proximity warning system fitted comprising of a front mounted, rear facing CCTV camera (or Fresnel Lens where this provides reliable alternative), a Close Proximity Sensor, an in-cab warning device (visual or audible) and an external warning device to make the road user in close proximity aware of the driver's planned manoeuvre.
 - iii. Have a Class VI Mirror
 - iv. Bear prominent signage on the rear of the vehicle to warn cyclists of the dangers of passing the vehicle on the inside.
- v) Any other relevant information with regard to traffic and transport.
- The Construction Management Plan should also include the following statement:"The agreed contents of the Construction Management Plan must be complied with
 unless otherwise agreed with the Council. The project manager shall work with the
 Council to review this Construction Management Plan if problems arise in relation to
 the construction of the Development. Any future revised plan must be approved by
 the Council and complied with thereafter."

It should be noted that any agreed Construction Management Plan does not prejudice further agreement that may be required for things such as road closures or hoarding licences

THE THIRD SCHEDULE

DRAFT PLANNING PERMISSION





Regeneration and Planning Development Management London Borough of Camden Town Hall Judd Street London WC1H 8ND

Tel 020 7974 4444 Fax 020 7974 1930 Textlink 020 7974 6866

planning@camden.gov.uk www.camden.gov.uk/planning

Application Ref: 2014/5510/P

23 March 2015

Dear Sir/Madam

BB Partnership Ltd.

17 Remington Street

The Trafalgar

London N1 8DH

FOR INFORMATION ONLY - THIS IS NOT A FORMAL DECISION

Town and Country Planning Act 1990 (as amended)

DECISION SUBJECT TO A SECTION 106 LEGAL AGREEMENT

Address:

16 Rochester Mews London NW1 9JB

Proposal:

Demolition of existing Class B1/B8 unit and erection of a 4 storey building containing replacement business space (Class B1/B8) on ground floor and five self-contained flats (Class C3) plus balconies on 1st-3rd floors.

Drawing Nos: Design and Access Statement Rev B dated January 2015; Lifetime Homes Statement dated August 2014 Rev C; Daylight and sunlight report by GVA dated September 2014; Energy Statement and BREEAM Pre-assessment report by eb7 dated 13th October 2014; FES- 001, 002, 02A, 003, 004, 005, 006, 007, 008, 06B, 07B, 08B, 10A, 012A, 014; email from agent dated 13th January 2015.

The Council has considered your application and decided to grant permission subject to the conditions and informatives (if applicable) listed below **AND** subject to the successful conclusion of a Section 106 Legal Agreement.

The matter has been referred to the Council's Legal Department and you will be contacted shortly. If you wish to discuss the matter please contact **Aidan Brookes** in the Legal Department on **020 7 974 1947**.

Once the Legal Agreement has been concluded, the formal decision letter will be sent to you.

Condition(s) and Reason(s):

1 The development hereby permitted must be begun not later than the end of three years from the date of this permission.

Reason: In order to comply with the provisions of Section 91 of the Town and Country Planning Act 1990 (as amended).

The development hereby permitted shall be carried out in accordance with the following approved plans- Design and Access Statement Rev B dated January 2015; Lifetime Homes Statement dated August 2014 Rev C; Daylight and sunlight report by GVA dated September 2014; Energy Statement and BREEAM Pre-assessment report by eb7 dated 13th October 2014; FES- 001, 002, 02A, 003, 004, 005, 006, 007, 008, 06B, 07B, 08B, 10A, 012A, 014.

Reason: For the avoidance of doubt and in the interest of proper planning.

- Detailed drawings, or samples of materials as appropriate, in respect of the following, shall be submitted to and approved in writing by the local planning authority before the relevant part of the work is begun:
 - a) Plan, elevation and section drawings, including jambs, head and cill, of all new external window and door at a scale of 1:10 with typical glazing bar details at 1:1.
 - b) Typical details of new railings and balustrade at a scale of 1:10.
 - c) Detailed elevations of all facades at scale 1:50.
 - d) Samples and details of new facing materials, including windows and door frames, glazing, balconies, balustrades, panels and brickwork with a full scale sample panel of all brickwork, demonstrating the proposed colour, texture, face-bond and pointing, and glazing elements of no less than 1m by 1m including junction with window opening.

The relevant part of the works shall be carried out in accordance with the details thus approved and all approved samples shall be retained on site during the course of the works.

Reason: To safeguard the appearance of the premises and the character of the immediate area in accordance with the requirements of policy CS14 of the London Borough of Camden Local Development Framework Core Strategy and policy DP24 of the London Borough of Camden Local Development Framework Development Policies.

4 No lights, meter boxes, flues, vents or pipes, and no telecommunications equipment, alarm boxes, television aerials, satellite dishes or rooftop railings or plant equipment shall be fixed or installed on the external face of the buildings, without the prior approval in writing of the local planning authority.

Reason: To safeguard the appearance of the premises and the character of the immediate area in accordance with the requirements of policy CS14 of the London Borough of Camden Local Development Framework Core Strategy and policy DP24

of the London Borough of Camden Local Development Framework Development Policies.

1.8 metre high privacy screens, details of which shall have been submitted to and approved in writing by the local planning authority, shall be erected on the southeast and northeast sides of the proposed rear terraces at 1st and 2nd floors and northeast side of the proposed rear terrace at 3rd floor, prior to commencement of use of the roof terrace and shall be permanently retained.

Reason: In order to prevent unreasonable overlooking of neighbouring premises in accordance with the requirements of policy CS5 of the London Borough of Camden Local Development Framework Core Strategy and policy DP26 of the London Borough of Camden Local Development Framework Development Policies.

Prior to occupation of the flats, the proposed stainwell windows on the northeast elevation shall be obscure glazed and permanently retained as such thereafter.

Reason: In order to prevent unreasonable overlooking of neighbouring premises in accordance with the requirements of policy CS5 of the London Borough of Camden Local Development Framework Core Strategy and policy DP26 of the London Borough of Camden Local Development Framework Development Policies.

Before the B1/B8 use commences, sound insulation shall be provided for the building between the commercial and residential units in accordance with a scheme to be first approved by the local planning authority in writing. The use shall thereafter not be carried out other than in accordance with the approved scheme.

Reason: To safeguard the amenities of the adjoining premises and the area generally in accordance with the requirements of policy CS5 of the London Borough of Camden Local Development Framework Core Strategy and policy DP26 of the London Borough of Camden Local Development Framework Development Policies.

Noise levels at a point 1 metre external to sensitive facades shall be at least 5dB(A) less than the existing background measurement (LA90), expressed in dB(A) when all plant/equipment (or any part of it) is in operation unless the plant/equipment hereby permitted will have a noise that has a distinguishable, discrete continuous note (whine, hiss, screech, hum) and/or if there are distinct impulses (bangs, clicks, clatters, thumps), then the noise levels from that piece of plant/equipment at any sensitive façade shall be at least 10dB(A) below the LA90, expressed in dB(A).

Reason: To safeguard the amenities of the adjoining premises and the area generally in accordance with the requirements of policy CS5 of the London Borough of Camden Local Development Framework Core Strategy and policies DP26 and DP28 of the London Borough of Camden Local Development Framework Development Policies.

- The cycle storage areas for the commercial and residential uses, as shown on the approved ground floor plan, shall be provided in their entirety prior to the first occupation of any of the new units, and permanently retained thereafter.
 - Reason: To ensure the development provides adequate cycle parking facilities in accordance with the requirements of policy CS11 of the London Borough of Camden Local Development Framework Core Strategy and policy DP17 of the London Borough of Camden Local Development Framework Development Policies.
- Prior to first occupation of the buildings, detailed plans showing the location and extent of photovoltaic cells to be installed on the building shall have been submitted to and approved by the Local Planning Authority in writing. The measures shall include the installation of a meter to monitor the energy output from the approved renewable energy systems. The cells shall be installed in full accordance with the details approved by the Local Planning Authority and permanently retained and maintained thereafter.

Reason: To ensure the development provides adequate on-site renewable energy facilities in accordance with the requirements of policy CS13 of the London Borough of Camden Local Development Framework Core Strategy and policy DP22 of the London Borough of Camden Local Development Framework Development Policies.

Informative(s):

- Your proposals may be subject to control under the Building Regulations and/or the London Buildings Acts which cover aspects including fire and emergency escape, access and facilities for people with disabilities and sound insulation between dwellings. You are advised to consult the Council's Building Control Service, Camden Town Hall, Argyle Street WC1H 8EQ, (tel: 020-7974 6941).
- Noise from demolition and construction works is subject to control under the 2 Control of Pollution Act 1974. You must carry out any building works that can be heard at the boundary of the site only between 08.00 and 18.00 hours Monday to Friday and 08.00 to 13.00 on Saturday and not at all on Sundays and Public Holidays. You are advised to consult the Council's Compliance and Enforcement team [Regulatory Services], Camden Town Hall, Argyle Street, WC1H 8EQ (Tel. website the 4444 or on 7974 020 No. http://www.camden.gov.uk/ccm/content/contacts/councilcontacts/environment/contact-the-environmental-health-team.en or seek prior approval under Section 61 of the Act if you anticipate any difficulty in carrying out construction other than within the hours stated above.
- The Mayor of London introduced a Community Infrastructure Levy (CIL) to help pay for Crossrail on 1st April 2012. Any permission granted after this time which adds more than 100sqm of new floorspace or a new dwelling will need to pay this CIL. It will be collected by Camden on behalf of the Mayor of London. Camden will be sending out liability notices setting out how much CIL will need to be paid if an affected planning application is implemented and who will be liable.

Œ

The proposed charge in Camden will be £50 per sqm on all uses except affordable housing, education, healthcare, and development by charities for their charitable purposes. You will be expected to advise us when planning permissions are implemented. Please use the forms at the link below to advise who will be paying the CIL and when the development is to commence. You can also access forms to allow you to provide us with more information which can be taken into account in your CIL calculation and to apply for relief from CIL.

http://www.planningportal.gov.uk/planning/applications/howtoapply/whattosubmit/cil

We will then issue a CIL demand notice setting out what monies needs to paid when and how to pay. Failure to notify Camden of the commencement of development will result in a surcharge of £2500 or 20% being added to the CIL payment. Other surcharges may also apply for failure to assume liability and late payment. Payments will also be subject to indexation in line with the construction costs index.

Please send CIL related documents or correspondence to CIL@Camden.gov.uk

- Your attention is drawn to the fact that there is a separate legal agreement with the Council which relates to the development for which this permission is granted. Information/drawings relating to the discharge of matters covered by the Heads of Terms of the legal agreement should be marked for the attention of the Planning Obligations Officer, Sites Team, Camden Town Hall, Argyle Street, WC1H 8EQ.
- Under Section 25 of the GLC (General Powers) Act 1983, the residential accommodation approved is not permitted for use as holiday lettings or any other form of temporary sleeping accommodation defined as being occupied by the same person(s) for a consecutive period of 90 nights or less. If any such use is intended, then a new planning application will be required which may not be approved.

In dealing with the application, the Council has sought to work with the applicant in a positive and proactive way in accordance with paragraphs 186 and 187 of the National Planning Policy Framework.

Yours faithfully

Culture and Environment Directorate




THE FOURTH SCHEDULE

THE PROPERTY



16 ROCHESTER MEWS, LONDON, NW1 9JB



Mws Dawl Skradu



THE FIFTH SCHEDULE

LOCAL PROCUREMENT CODE

1. INTRODUCTION

The use of local procurement agreements is a useful tool in helping the Council to improve economic prosperity and diversity in the local area which is a key aim of the Camden Community Strategy and the Local Development Framework (adopted November 2010). The sourcing of goods and services locally will also help to achieve a more sustainable pattern of land use and reduce the need to travel. The use of section 106 agreements/undertaking attached to the grant of planning permission will be used as a mechanism to secure appropriate levels of local procurement of goods and services.

A fuller explanation of the policy background and the justification for the use of local procurement agreements and when they will be required is contained with Sections 32 and 33 of the Camden Planning Guidance (adopted December 2006) which can be viewed on the Council's web site. This document is in line with the objectives of other organizations such as the London Development Agency and Government Office for London.

The purpose of this code is to maximise the opportunities available to Local Businesses in Camden from larger property developments taking place in Camden both during and after the construction phase. The local procurement code describes how the Owner in partnership with Camden Labour Market & Economy Service will ensure that Local Businesses benefit directly from the opportunities arising from both the Construction Phase of the Development and the end use of the Property.

The requirements of the local procurement code apply to the developer, main contractor and subcontractors appointed by them as well as tenants subsequently occupying the building. The code is designed to support developers and contractors in fulfilling their commitments to the planning agreements by clarifying what is required from the outset. Although the wording is emphatic, Camden Labour Market & Economy Service seeks to work in partnership with contractors to assist them in meeting specifications and in finding suitable local companies. They will provide a

regularly updated pre-screened directory of local companies in construction, fitting—out and furnishing trades in support of local procurement agreements.

MAIN REQUIREMENTS OF THE CODE

A) CONSTRUCTION.

We will request that the developers meet with London Borough of Camden's Labour Market & Economy Service's Local Procurement Team ("the Local Procurement Team") at least 1 month in advance of tendering contracts to clarify how the local procurement code will work and the co-operation required from the developer, main contractor and subcontractors.

The Council will seek to ensure that the developer inserts the following clauses in the tender documentation issued to the main contractor:

2.1 Actions & Responsibilities of Main Contractor

- The main contractor will provide the Local Procurement Team with information on the
 estimated timing of their procurement programme and a schedule of works packages
 to be let ("the Procurement Schedule") and to provide updates of the Procurement
 Schedule as and when it is updated or revised.
 - 2. The main contractor will work with the Local Procurement Team to: include local companies on their tender lists wherever possible and to aim to achieve the procurement of construction contracts and goods and services from companies and organisations based in Camden towards a target of 10% of the total value of the construction contract.
 - 3. The main contractor is required to provide regular monitoring information to the Local Procurement Team every six to eight weeks during the construction phase, via email, phone, fax or liaison meeting providing details of:
 - all local companies which are sent a tender enquiry or a tender invitation detailing the date and the works package or items concerned;

- the outcome of all works packages tendered where there is a local company on the tender list, stating whether the local company was unsuccessful, successful or declined to tender and the contract value in the case of a contract being awarded to a local company.
- All local wholesalers and building materials suppliers which are asked to provide prices and the value of any purchases of materials and other wholesaler supplies procured.

(The Local Procurement Team can provide a pro forma local procurement log to assist in the monitoring process)

- > Full contact details of all subcontractors appointed (whether local or from elsewhere)
- 4. The main contractor should include a written statement in the tender documentation sent out to sub-contractors informing them of their s106 requirement obligations as set out in section 2.2 below and ensure cooperation is agreed as a prerequisite to accepting sub contract tenders
- 5. The main contractor should provide an opportunity for the Local Procurement Team to brief subcontractors on the requirements of the Local Procurement code.
 - The main contractor will identify any actions that are required in order to overcome known barriers to Local Businesses to accessing their supply chain in respect of the Construction Phase.

2.2 Actions and Responsibilities of Sub-Contractors

All sub-contractors appointed will be required to work with the Local Procurement Team and to aim to achieve the procurement of construction goods and services from companies and organisations based in Camden towards a target of 10% of the total value of their construction sub-contract. (A regularly updated sub-directory of local suppliers will be supplied to subcontractors by the Local Procurement Team).

- 2. All subcontractors are required to provide regular monitoring information either to the main contractor or directly to the Local Procurement Team every six to eight weeks during the construction phase, via e-mail, phone, fax or liaison meeting providing details of:
 - All local wholesalers and building materials suppliers which are asked to provide prices and the value of any subsequent purchases of materials and other wholesaler supplies procured.
 - All local companies which are sent a tender enquiry or a tender invitation detailing the date and the works package concerned and the outcome of all subcontracts tendered.

B. <u>POST CONSTRUCTION: FITTING OUT BY TENANTS AND FACILITIES</u> <u>MANAGEMENT</u>

Fitting out by tenants

Where the tenants of a development are responsible for fitting out the building(s), we will require the developers to inform them that they also fall under the provisions of this s106 on local procurement and provide guidance in writing to their tenants setting out the above clauses contained in section 2 above, which will apply to them as the developer, their main contractor and subcontractors.

€

Facilities Management

The Owner and their agents shall use reasonable endeavours to provide opportunities for local businesses to bid/tender for the provision of facilities management services and other post construction supply of goods and services.

The Council will assist the developer, occupier and their contractors in identifying suitable local companies to bid for facilities management contracts and to source local goods and services.

IN WITNESS whereof the Council has caused its Common Seal to be hereunto affixed and the Owner and the Mortgagee have executed this instrument as their Deed the day and year first before written

EXECUTED AS A DEED BY CAMDEN COMMERCIAL LIMITED acting by a Director and its Secretary or by two Directors)))	
Director Name: (CAPITALS) Director Signature:)	STEVEN BURNEY
Director/Secretary Name (CAPITALS) Director/Secretary Signature:)	ISABEL BURNEY ISabel Burney

NATIONAL WESTNINST PUBLIC LIMITED COMPA	ER BANK	;
	(CAPITALS))
	(SIGNED))
in the presence of:)
	(CAPITALS))
	(SIGNED))

THE COMMON SEAL OF THE MAYOR AND BURGESSES OF THE LONDON BOROUGH OF CAMDEN was hereunto Affixed by Order:-

& Alexander

Authorised Signatory



Igned and Delivered as a Deed) for and on behalf of) National Westminster Bank Plc) By a duly authorised Attorney)
n the presence of MANTYW FREEPON
Witness' Signature-Bank employee

PHILIP MARC BIRCHALL
DOCUMENTOR
CREDIT DOCUMENTATION

7158335/mp2



2015

(1) CAMDEN COMMERCIAL LIMITED

and

(2) NATIONAL WESTMINSTER BANK PUBLIC LIMITED COMPANY

and

(3) THE MAYOR AND BURGESSES OF THE LONDON BOROUGH OF CAMDEN

A G R E E M E N T relating to land known as

16 Rochester Mews London NW1 9JB

pursuant to Section 106 of the Town and Country Planning Act 1990 (as amended) and Section 278 of the Highways Act 1980

Andrew Maughan
Borough Solicitor
London Borough of Camden
Town Hall
Judd Street
London WC1H 9LP

Tel: 020 7974 5647 Fax: 020 7974 2962

CLS/PK/1781.88_final