



Material schedule:

- | | | |
|--|--|---|
| A Brick | K Wooden panel door painted white | V Lead sheet roof |
| B Render | L Wooden panel door painted white | X Rainwater Goods: Black painted profiled metal gutter, hopper and down pipe |
| C Coping stone - 20mm | M Powder coated aluminium door | |
| D Coping stone - Haddonstone TecLite 50mm | N Frameless structure glass | |
| D* Coping stone - 50mm | O Clear glass | |
| E Render plinth | P Fire rated double glazed unit | |
| F Glass balustrade | R Extractor | |
| G Wooden door | S Fence | |
| H Window stone surround | T Gate | |
| I Wooden sash window painted white | U Planter | |
| J Door stone surround | W Shadow gap | |



Notes:

- 1** Chamfer brick coping to bay parapet raised by two brick courses in relation to no.45B upper floor property
- 2** Existing single storey brick wall built up to create second storey
- 3** Rear extension parapet height lowered and sides inset

PROJECT ADDRESS: 45, MARESFIELD GARDENS LONDON	PROPOSED REVISED SIDE ELEVATION			
	2045(PLA)102			
CLIENT NAME: ~	PROJECT STAGE: PLANNING			
	VERSION:	SCALE: 1:100	SIZE: A3	
				APRIL 2015