

Tree Survey and Impact Assessment

Centre Heights

Swiss Cottage

May 2015



Landmark Trees

ARBORICULTURAL IMPACT ASSESSMENT REPORT:

Centre Heights
139-150 Finchley Road
London
NW3 6JG

REPORT PREPARED FOR:

Anaspel Ltd
C/o Savills
33 Margaret Street
London, W1G 0JD

REPORT PREPARED BY

Adam Hollis
MSc ARB MICFor FArbor A MRICS C Env

Ref: AWH/CHT/AIA/01

Date: 15th May 2015

The content and format of this report are for the exclusive use of the client. It may not be sold, lent, hired out or divulged to any third party, not directly involved in the subject matter without Landmark Trees' written consent

Web: www.landmarktrees.co.uk

e-mail: info@landmarktrees.co.uk

Tel: 0207 851 4544



London Office: 20 Broadwick Street, London, W1F 8HT

Registered Office: Grange Cottage, All Cannings, Devizes, Wiltshire, SN10 3NR

Landmark Trees is the trading name of Landmark trees Ltd. Registered in Wales. Reg No. 3882076



Section	Content	Page N°
1.0	SUMMARY	5
2.0	INTRODUCTION	6
3.0	OBSERVATIONS	8
4.0	DEVELOPMENT CONSTRAINTS	11
5.0	ARBORICULTURAL IMPACTS	14
6.0	DISCUSSION	15
7.0	CONCLUSION	17
8.0	RECOMMENDATIONS	17
9.0	REFERENCES	20
 Appendices		
APPENDIX 1	Survey Data	21
APPENDIX 2	Recommended Tree Works	23
APPENDIX 3	Recommended Tree Works to Facilitate Development	25
APPENDIX 4	Tree Constraints Plan	27
APPENDIX 5	Impact Assessment Plan	29

Caveats

This report is primarily an arboricultural report. Whilst comments relating to matters involving built structures or soil data may appear, any opinion thus expressed should be viewed as qualified, and confirmation from an appropriately qualified professional sought. Such points are usually clearly identified within the body of the report. It is not a full safety survey or subsidence risk assessment survey. These services can be provided but a further fee would be payable. Where matters of tree condition with a safety implication are noted during a survey they will of course appear in the report.

A tree survey is generally considered invalid in planning terms after 2 years, but changes in tree condition may occur at any time, particularly after acute (e.g. storm events) or prolonged (e.g. drought) environmental stresses or injuries (e.g. root severance). Routine surveys at different times of the year and within two - three years of each other (subject to the incidence of the above stresses) are recommended for the health and safety management of trees remote from highways or busy access routes. Annual surveys are recommended for the latter.

Tree works recommendations are found in the Appendices to this report. It is assumed, unless otherwise stated ("ASAP" or "Option to") that all husbandry recommendations will be carried out within 6 months of the report's first issue. Clearly, works required to facilitate development will not be required if the application is shelved or refused. However, necessary husbandry work should not be shelved with the application and should be brought to the attention of the person responsible, by the applicant, if different. Under the Occupiers Liability Act of 1957, the owner (or his agent) of a tree is charged with the due care of protecting persons and property from foreseeable damage and injury.' He is responsible for damage and/or nuisance arising from all parts of the tree, including roots and branches, regardless of the property on which they occur. He also has a duty under The Health and Safety at Work Act 1974 to provide a safe place of work, during construction. Tree works should only be carried out with local authority consent, where applicable.

Inherent in a tree survey is assessment of the risk associated with trees close to people and their property. Most human activities involve a degree of risk, such risks being commonly accepted if the associated benefits are perceived to be commensurate.

Risks associated with trees tend to increase with the age of the trees concerned, but so do many of the benefits. It will be appreciated, and deemed to be accepted by the client, that the formulation of recommendations for all management of trees will be guided by the cost-benefit analysis (in terms of amenity), of tree work that would remove all risk of tree related damage.

Prior to the commencement of any tree works, an ecological assessment of specific trees may be required to ascertain whether protected species (e.g. bats, badgers and invertebrates etc.) may be affected.

Tree Constraints & Protection Overview

Client:	Anaspel Ltd	Case Ref:	AWH/CHT/AIA/01
Local Authority:	LB Camden	Date:	15 th May 2015
Site Address: Centre Heights, 139-150 Finchley Road, London NW3 6JG			
Proposal: Refurbishment of the existing building; upward extension of Centre Heights; new residential entrances; new mews development and retail extension.			
Report Checklist	Y/N		Y/N
Arboricultural constraints on site	Y	Trees removal proposed	N
Tree Survey	Y	Topographical Survey	Y
BS5837 Report	Y	Conservation Area	N
Tree Preservation Orders	N		
Tree Protection Plan:	N/a	(Include in future method statement)	
Tree Constraints Plan:	Y		
Arboricultural Impact Assessment:	Y		
Site Layout			
Site Visit	Y	Date: 25/02/15	Access Full/Partial/None
			F
Trees on Site	Y	Off-site Trees	Y
Trees affected by development	Y	O/s trees affected by development	Y
Tree replacement proposed:	N	On or off-site trees indirectly affected by development	N
Trees with the potential to be affected			
Demolition/construction within canopy of off-site category U tree T6 – remedial tree surgery to provide construction clearance, however tree cankered and ultimately recommended for felling on grounds of sound husbandry, aside from development. Felling recommendation is merely due diligence as last professional on site.			
Comments			
Recommended works to fell category U trees T5 and T6 (note: T6 is a third party tree and not relevant to the development other than the need to cut back the overhanging branches).			
Recommendations			
1	Proposal will mean the loss of important trees (TPO/CA)		N
2	Proposal has sufficient amelioration for tree loss (good husbandry only)		N/a
3	Proposals provide adequate tree protection measures		Y
4	Proposal will mean retained trees are too close to buildings		N
5	Specialist demolition / construction techniques required		Y
6	The Proposal will result in significant root damage to retained trees		N
7	Further investigation of tree condition recommended (T4)		Y

RPA= Root Protection Area

TPP= Tree Protection Plan

AMS= Arboricultural Method Statement

AIA = Arboricultural Implication Assessment

BS5837: 2012 'Trees in relation to design, demolition and construction – Recommendations'

Arboricultural Impact Assessment Report: Centre Heights, 139-150 Finchley Road, London NW3 6JG

Prepared for: Anaspel Ltd, C/o Savills, 33 Margaret Street, London, W1G 0JD

Prepared by: Adam Hollis of Landmark Trees, 20 Broadwick Street, London W1F 8HT

1. SUMMARY

- 1.1 This report comprises an arboricultural impact assessment of the proposals for Centre Heights, 139-150 Finchley Road, London NW3 6JG, reviewing any conflicts between the proposals and material tree constraints identified in our survey.
- 1.2 There are 6 trees surveyed on or around the site, of which 2 are B category *(Moderate Quality), 2 are C category *(Low Quality) and 2 are U category *(Unsuitable for Retention). In theory, only moderate quality trees and above are significant material constraints on development. However, the low quality trees would comprise a constraint in aggregate, in terms of any collective loss / removal, where replacement planting would be appropriate. In this instance, no such collective impact is proposed.
- 1.3 There are no RPA encroachments from the proposals. The proposals though will affect the aerial parts of two category U trees, T5 and T6. The recent survey has confirmed that both trees should be removed on the grounds of sound husbandry, independent of the proposals; the on-site tree, T5, is a self-sown tree of heaven that is unsuited to the position (growing in and grafted into small gap between ramp and wall). The off-site tree, T6, is irremediably cankered and leaning with a life expectancy of less than 10 years, and should therefore be removed and replaced in the short term. However, the tree is prominent within the housing site and was considered to provide a significant level of visual amenity for local residents in previous correspondence. It is therefore proposed that the fate of this diseased tree be set-aside / bracketed off from the considerations of this application, since largely immaterial to it. Instead, the existing crown spread overhanging the car park could be cut back to the legal boundary, with some further allowance made for working space for construction (scaffolding etc); a reduction in radial spread of circa 2 metres would be appropriate. NB it is entirely up to the third-party owners what they do with their tree, nor is it of any significance either way to the applicant, but it is important I discharge my duty to make prudent recommendations, including felling and replacement where appropriate. Therefore such professional recommendations remain in my report.
- 1.4 Secondary impacts from the new elevation require the proposed crown reduction to be maintained on a 5-year pruning cycle. Thus, the requirements of the proposed elevations are no more than the current elevations. However, it is important to consider that a suitable replacement for this cankered horse chestnut would not require such maintenance and could offer visual enhancement over the existing tree. The proposed reduction will also reduce the marginal secondary impacts of litter deposition and partial shade that already exist on this site. The status quo is unlikely to change with further development, which is the salient point for planning to consider. Thus, the secondary impacts of development are minimal.
- 1.5 The site has potential for development without impacting significantly on the wider tree population or local landscape. Thus, with suitable mitigation and supervision the scheme is recommended to planning.

* British Standards Institute: Trees in relation to design, demolition and construction BS 5837: 2012 HMSO, London

2. INTRODUCTION

2.1 Terms of Reference

- 2.1.1 LANDMARK TREES were asked by Anaspel Ltd, C/o Savills to provide a survey and an arboricultural impact assessment of proposals for the site: Centre Heights, 139-150 Finchley Road, London NW3 6JG. The report is to accompany a planning application.
- 2.1.2 The proposals are for the demolition of multi-storey car park and erection of two to five storey mews development at the rear of Centre Heights to create 11 no. residential units (8 no. 2 bed and 3 no. 3 bed) together with hard and soft landscaping; improvements to rear courtyard including hard landscaping, refuse and recycling facilities and cycle parking; two storey extension with third storey set back to the main Centre Heights building to create 5 no. residential units (3 bed) with roof gardens; relocation of 7 no. telecommunications antennae at roof level; and single storey rear extension to existing retail units to create at additional 130 sqm retail floorspace
- 2.1.3 This report will assess the impact on the trees and their constraints, identified in our survey. Although the proposals were known at the time of the survey, Landmark Trees endeavour to survey each site blind, working from a topographical survey, wherever possible, with the constraints plan informing their evolution.
- 2.1.4 I am a Registered Consultant and Fellow of the Arboricultural Association and a Chartered Forester, with a Masters Degree in Arboriculture and 25 years' experience of the landscape industry - including the Forestry Commission and Agricultural Development and Advisory Service. I am a UK Registered Expert Witness, trained in single and joint expert witness duties. I am also Chairman of the UK & I Regional Plant Appraisal Committee, inaugurated to promote international standards of valuation in arboriculture.

2.2 Drawings Supplied

- 2.2.1 The drawings supplied by the client and relied upon by Landmark Trees in the formulation of our survey plans are:
Existing site survey: 8330_T
Proposals: 3073_L_1100_P7

2.3 Scope of Survey

- 2.3.1 As Landmark Trees' (LT) arboricultural consultant, I surveyed the trees on site on 25th February 2015, recording relevant qualitative data in order to assess both their suitability for retention and their constraints upon the site, in accordance with British Standard 5837:2012 Trees in relation to design, demolition and construction – Recommendations [BS5837:2012].
- 2.3.2 Our survey of the trees, the soils and any other factors, is of a preliminary nature. The trees were SURVEYED on the basis of the Visual Tree Assessment method expounded by Mattheck and Breloer (The Body Language of Trees, DoE booklet Research for Amenity Trees No. 4, 1994). LT have not taken any samples for analysis and the trees were not climbed, but inspected from ground level.
- 2.3.3 A tree survey is generally considered invalid in planning terms after 2 years, but changes in tree condition may occur at any time, particularly after acute (e.g. storm events) or prolonged (e.g. drought) environmental stresses or injuries (e.g. root severance). Routine surveys at different times of the year and within two - three years of each other (subject to the incidence of the above stresses) are recommended for the health and safety management of trees remote from highways or busy access routes. Annual surveys are recommended for the latter.
- 2.3.4 The survey does not cover the arrangements that may be required in connection with the laying or removal of underground services.

2.4 Survey Data & Report Layout

- 2.4.1 Detailed records of individual trees are given in the survey schedule in Appendix 1 to this report.
- 2.4.2 A site plan identifying the surveyed trees, based on the client's drawings / topographical survey is provided in Appendix 5.
- 2.4.3 This plan also serves as the Tree Constraints Plan with the theoretical Recommended Protection Areas (RPA's), tree canopies and shade constraints, (from BS5837: 2012) overlain onto it. These constraints are then overlain in turn onto the client's proposals to create an Arboricultural Impact Assessment Plan in Appendix 6. General observations and discussion follow, below.

3.0 OBSERVATIONS

3.1 Site Description



Photograph 1: Aerial View of Centre Heights, 139-150 Finchley Road, London NW3 6JG

- 3.1.1 Centre Heights is located on Finchley Road in the London Borough of Camden. It lies just within the Finchley Road-Swiss Cottage Town Centre and is situated just west of the junction with College Crescent and north of Swiss Cottage underground station. Belsize Road provides access into the rear of the site.
- 3.1.2 The application site comprises Centre Heights, which was completed in 1961 as a twelve storey mixed use tower with a retail plinth which fronts Finchley Road, a delivery yard to the rear of the building which serves the retail units and a car park which serves the main building.
- 3.1.3 Bounding the rear of the site to the west and the north are Campden House and Hickes House, both of which comprise six and seven storey blocks of residential accommodation. The south of the site is bounded by a pedestrianised link which connects the end of Belsize Road to Finchley Road and provides access into Swiss Cottage underground station.

- 3.1.3 In terms of the British Geological Survey, the site overlies the London Clay Formation (see indicated location on Fig.1 plan extract below). The associated soils are generally, highly shrinkable clay; e.g. slowly permeable seasonally waterlogged fine loam over clay. Such highly plastic soils are prone to movement: subsidence and heave. The actual distribution of the soil series are not as clearly defined on the ground as on plan and there may be anomalies in the actual composition of clay, silt and sand content.
- 3.1.4 Clay soils are prone to compaction during development with damage to soil structure potentially having a serious impact on tree health. The design of foundations near problematic tree species will also need to take into consideration subsidence risk. Further advice from the relevant experts on the specific soil properties can be sought as necessary.




Figure 1: Extract from the BGS Geology of Britain Viewer

3.2 Subject Trees

- 3.2.1 Of the 6 surveyed trees 2 are B category (Moderate Quality), 2 are C category (Low Quality) and 2 are U category (Unsuitable for Retention).
- 3.2.2 The tree species found on site comprise Norway maple, horse chestnut, sycamore, common ash and a tree of Heaven.
- 3.2.3 In terms of age demographics there is a range from young through to mature trees in the population.



Photograph 1: Trees T1 and T2



Photograph 2: Trees T2 and T3



Photograph 3: Tree T4



Photograph 4: Trees T5 and T6



Photo 5: Category U tree T5



Photo 6: Category U tree T6



Photo 7: Overhanging canopy of T6

3.2.4 Full details of the surveyed trees can be found in Appendix 1 of this report.

3.2.5 There are recommended works to fell the category U tree T5, in addition to Category U tree T6 (third party tree). There are also recommendations for further investigation of the basal cavity in T4. These are listed in Appendix 2.

3.3 Planning Status

3.3.1 There are no Tree Preservation Orders on the site and it stands outside any Conservation Areas.

4.0 DEVELOPMENT CONSTRAINTS

4.1 Primary Constraints

- 4.1.1 BS5837: 2012 gives Recommended Protection Areas (RPA's) for any given tree size. The individual RPA's are calculated in the Tree Schedule in Appendix 1 to this report, or rather the notional radius of that RPA, based on a circular protection zone. The prescribed radius is 12-x stem diameter at 1.5m above ground level, except where composite formulae are used in the case of multi-stemmed trees.
- 4.1.2 Circular RPA's are appropriate for individual specimen trees grown freely, but where there is ground disturbance, the morphology of the RPA can be modified to an alternative polygon, as shown in the diagram below (Figure 2). Alternatively, one need principally remember that RPA's are area-based and not linear – notional rather than fixed entities. **No modifications have been made in this instance (please see overleaf).**




Figure 2 – Generic BS 5837 RPA Adjustments

- 4.1.3 In BS5837, paragraph 4.6.2 states that RPA's should reflect the morphology and disposition of the roots; where pre-existing site conditions or other factors indicate that rooting has occurred asymmetrically, a polygon of equivalent area should be produced. Modifications to the shape of the RPA should reflect a soundly based arboricultural assessment of likely root distribution. Not infrequently, LT are requested by LPA Tree Officers to modify the RPA's to reflect their assumptions that e.g. a road will have drastically limited root growth.

- 4.1.4 Such assumptions cannot be proved without prior site investigations / trial pits. Where it is not always possible to conduct site investigations (e.g. below busy roads), we can always look to the published science. There seems little support for the popular myth that roads and services will curb root growth: research for the International Society of Arboriculture by Kopinga J (ISA 1994), found that “a constant high moisture content of the soil directly underneath the pavement surface can be considered as a major soil factor in attracting the trees’ roots to develop there.” By contrast, grass in lawns may actively antagonise tree roots with natural pathogens. Similarly, Professor F Miller (ISA 1994) found that service trenches at > 3m distances from trees had minimal impact on growth or crown shape.
- 4.1.5 A key misunderstanding, even among professionals, is that we conflate the RPA with the actual root system: RPA's are *prima facie* a notion / convention / treaty and almost entirely theoretical, but readily calculable. Conversely roots are a "known unknown," spatial entity that we predict at our folly. Yet, many are quick to do so.
- 4.1.6 LT favour the neutrality of a circular RPA, because in a difference of opinion, the tree officer will always have the prerogative to dictate the final modification of shape. With the best will in the world, the free allowance of modifications will tend to lead to inequitable outcomes, prejudicing the applicant and the practice is in our view, best avoided. The neutral circle dispenses with this inequity.
- 4.1.7 Ultimately, the point of the circular RPA is to illustrate areas of concern. The purpose of this report is to consider areas of concern (not to modify them to suit our argument or findings). Therefore, no modifications are made here to the RPA's, regardless of roads etc.
- 4.1.8 The quality of trees will also be a consideration: U Category trees are discounted from the planning process in view of their limited service life. Again, Category-C trees would not normally constrain development individually, unless they provide some external screening function.
- 4.1.9 At paragraph 5.1.1. BS5837: 2012 notes that “Care should be exercised over misplaced tree preservation; attempts to retain too many or unsuitable trees on a site are liable to result in excessive pressure on the trees during demolition or construction work, or post-completion demands on their removal.”

- 4.1.10 In theory, only moderate quality trees and above are significant material constraints on development. However, the low quality trees would comprise a constraint in aggregate, in terms of any collective loss / removal, where replacement planting would be appropriate.

4.1.11 In this instance, the only internal site tree is a category U Tree of Heaven, which is not a constraint on development and requires felling on the grounds of sound husbandry. The two category B trees are off-site and located outside the main development area. There is one other category U tree that currently overhangs the multi-storey car park on the site, which will not constrain development but is likely to require remedial tree works to cut back the overhanging branches.

4.2 Secondary Constraints

4.2.1 The second type of constraint produced by trees that are to be retained is that the proximity of the proposed development to the trees should not threaten their future with ever increasing demands for tree surgery or felling to remove nuisance shading (Figure 3), honeydew deposition or perceived risk of harm.




Figure 3 –
Generic Shading Constraints

4.2.2 The shading constraints are crudely determined from BS5837 by drawing an arc from northwest to east of the stem base at a distance equal to the height of the tree, as shown in the diagram opposite. Shade is less of a constraint on non-residential developments, particularly where rooms are only ever temporarily occupied.




Figure 4 – Shading Arc

4.2.3 This arc (see Figure 4) represents the effects that a tree will have on layout through shade, based on shadow patterns of 1x tree height for a period May to Sept inclusive 10.00-18.00 hrs daily.

4.2.4 The off-site trees have the potential to provide a variety of secondary constraints, including shading, organic deposition and the potential need to maintain crown clearance in the future. The significance of these constraints will vary depending on the location and proximity to the proposed re-development.

Note: Sections 5 & 6 will now assess the impacts upon constraints identified in Section 4. Table 1 in Section 5 presents the impacts in tabular form (drawing upon survey data presented in Appendices 1 & 2). Impacts are presented in terms of whole tree removal and the effect on the landscape or partial encroachment (% of RPA) and its effect on individual tree health. Section 6 discusses the table data, elaborating upon the impacts' significance and mitigation.

Table 1: Arboricultural Impact Assessment

(Impacts assessed prior to mitigation and rated with reference to Matheny & Clark (1998))

Hide irrelevant

Show All Trees

Ref: AWH/CHT/AIA

B.S. Cat.	Tree No.	Species	Impact	Tree / RPA Affected	Age	Growth Vitality	Species Tolerance	Impact on Tree Rating	Impact on Site Rating	Mitigation
U	6	Chestnut, Horse	Building Demolition/ Construction within Canopy	m ² N/A %	Semi-mature	Moderate	Moderate	Low	N/A	Remedial tree surgery (see Rec. Works)

6.0 DISCUSSION

6.1 Rating of Primary Impacts

6.1.1 There are 6 trees surveyed on or around the site, of which 2 are B category *(Moderate Quality), 2 are C category *(Low Quality) and 2 are U category *(Unsuitable for Retention). In theory, only moderate quality trees and above are significant material constraints on development. However, the low quality trees would comprise a constraint in aggregate, in terms of any collective loss / removal, where replacement planting would be appropriate. In this instance, no such collective impact is proposed.

6.1.2 There are no RPA encroachments from the proposals. The proposals though will affect the aerial parts of two category U trees, T5 and T6. The recent survey has confirmed that both trees should be removed on the grounds of sound husbandry, independent of the proposals; the on-site tree, T5, is a self-sown tree of heaven that is unsuited to the position (growing in and grafted into small gap between ramp and wall). The off-site tree, T6, is irremediably cankered and leaning with a life expectancy of less than 10 years, and should therefore be removed and replaced in the short term. However, the tree is prominent within the housing site and was considered to provide a significant level of visual amenity for local residents in previous correspondence. It is therefore proposed that the fate of this diseased tree be set-aside / bracketed off from the considerations of this application, since largely immaterial to it. Instead, the existing crown spread overhanging the car park could be cut back to the legal boundary, with some further allowance made for working space for construction (scaffolding etc); a reduction in radial spread of circa 2 metres would be appropriate. NB it is entirely up to the third-party owners what they do with their tree, nor is it of any significance either way to the applicant, but it is important I discharge my duty to make prudent recommendations, including felling and replacement where appropriate. Therefore such professional recommendations remain in my report.

6.1.3 The principal of RPA encroachment is established within BS5837:2012 and supported by the source document, National Joint Utilities Guidelines 10 / Vol. 4 1995 / 2010. NJUG introduced the x12 diameter *Precautionary Zone* for supervised working and *Prohibited Zone* at a universal 1m from the base of the tree. RPA's are frequently confused with the NJUG Prohibited Zone, when they clearly correlate with the NJUG Precautionary Zone.

6.1.4 An RPA encroachment of <20% of RPA may be considered as low impact, given the permissive references to 20% RPA relocation and impermeable paving within BS5837:2012 and other published references to healthy trees tolerating up to 30-50% root severance (Coder, Helliwell and Watson in CEH 2006).

6.1.5 **“In practice 50% of roots can sometimes be removed with little problem**, provided there are vigorous roots elsewhere. Inevitably, this degree of root loss will temporarily slow canopy growth and even lead to some dieback” (Thomas 2000). LT do not recommend annexing such high proportions of the root system; rather that within the context of the published science, planning should not be unduly concerned by impacts that are well below the subcritical threshold – *tree health is not at stake*. In this instance though, there are no RPA encroachments from the proposals.

6.2 Rating of Secondary Impacts

6.2.1 Secondary impacts from the new elevation require the proposed crown reduction to be maintained on a 5-year pruning cycle. Thus, the requirements of the proposed elevations are no more than the current elevations. However, it is important to consider that a suitable replacement for this cankered horse chestnut would not require such maintenance and could offer visual enhancement over the existing tree. The proposed reduction will also reduce the marginal secondary impacts of litter deposition and partial shade that already exist on this site. The status quo is unlikely to change with further development, which is the salient point for planning to consider. Thus, the secondary impacts of development are minimal.

6.3 Mitigation of Impacts

6.3.1 Assuming that T6 is retained, all plant and vehicles engaged in demolition works should either operate outside the RPA, or should run on a temporary surface designed to protect the underlying soil structure. The demolition of the building should proceed inwards in a “pull down” fashion. Hard surfacing can be lifted with caution by a skilled machine operator again working away from the tree.

6.3.2 The immediate canopy encroachment can be avoided with a 2 m radial crown reduction of T6 (subject to the tree being retained).

7.0 CONCLUSION

- 7.1 The potential impacts of development are all very low, with the replacement option of the category U tree T6 on the grounds of sound husbandry the optimal position for all parties. However, if retained T6 will simply require remedial tree surgery, which would be required in terms of the current canopy encroachment and will benefit the form of the tree. The on-site category U tree T5 should also be felled on the grounds of sound husbandry, whether the proposals proceed or not.
- 7.2 Therefore, the proposals will not have any significant impact on either the retained trees or wider landscape. Thus, with suitable mitigation and supervision the scheme is recommended to planning.

8.0 RECOMMENDATIONS

8.1 Specific Recommendations

- 8.1.1 Current husbandry works recommendations are found in Appendix 2 to this report, with specific works to facilitate the development provided in Appendix 3 (subject to the retention of Category U tree T6).

8.2 General Recommendations for Sites Being Developed with Trees

- 8.2.1 Any trees which are in close proximity to the proposed development should be protected with a Tree Protection Barrier (TPB). Protective barrier fencing should be installed immediately following the completion of the tree works, remaining in situ for the entire duration of the development unless otherwise agreed in writing by the council. It should be appropriate for the intensity and proximity of the development, usually comprising steel, mesh panels 2.4m in height ('Heras') and should be mounted on a scaffolding frame (shown in Fig 2 of BS5837:2012). The position of the TPB can be shown on plan as part of the discharge of conditions, once the lay out is agreed with the planning authority. The TPB should be erected prior to commencement of works, remain in its original form on-site for the duration of works and removed only upon full completion of works.
- 8.2.2 A TPB may no longer be required during soft landscaping work but a full arboricultural assessment must be performed prior to the undertaking of any excavations within the RPA of a tree. This will inform a decision about the requirement of protection measures. It is important that all TPBs have permanent, weatherproof notices denying access to the RPA.

- 8.2.3 On the basis of the retention of T6, the use of heavy plant machinery for building demolition, removal of imported materials and grading of surfaces should take place in one operation. The necessary machinery should be located above the existing grade level and work away from any retained trees. This will ensure that any spoil is removed from the RPAs. It is vital that the original soil level is not lowered as this is likely to cause damage to the shallow root systems.
- 8.2.4 Any pruning works must be in accordance with British Standard 3998:2010 Tree work [BS3998].
- 8.2.5 Where sections of hard surfacing are proposed in close proximity to trees, it is recommended that “No-Dig” surfacing be employed in accordance with BS5837:2012 and ‘The Principles of Arboricultural Practice: Note 1, Driveways Close to Trees, AAIS 1996 [APN1]’.
- 8.2.6 If the RPA of a tree is encroached by underground service routes then BS5837:2012 and NJUG VOLUME 4 provisions should be employed. If it is deemed necessary, further arboricultural advice must be sought.
- 8.2.7 Numerous site activities are potentially damaging to trees e.g. parking, material storage, the use of plant machinery and all other sources of soil compaction. In operating plant, particular care is required to ensure that the operational arcs of excavation and lifting machinery, including their loads, do not physically damage trees when in use.
- 8.2.8 To enable the successful integration of the proposal with the retained trees, the following points will need to be taken into account:
- 1) Plan of underground services.
 - 2) Schedule of tree protection measures, including the management of harmful substances.
 - 3) Method statements for constructional variations regarding tree proximity (e.g. foundations, surfacing and scaffolding).
 - 4) Site logistics plan to include storage, plant parking/stationing and materials handling.
 - 5) Tree works: felling, required pruning and new planting. All works must be carried out by a competent arborist in accordance with BS3998.
 - 6) Site supervision: the Site Agent must be nominated to be responsible for all arboricultural matters on site. This person must:
 - be present on site for the majority of the time;
 - be aware of the arboricultural responsibilities;
 - have the authority to stop work that is causing, or may cause harm to any tree;

- ensure all site operatives are aware of their responsibilities to the trees on site and the consequences of a failure to observe these responsibilities;
- make immediate contact with the local authority and/or a retained arboriculturalist in the event of any tree related problems occurring.

8.2.9 These points can be resolved and approved through consultation with the planning authority via their Arboricultural Officer.

8.2.10 The sequence of works should be as follows:

- i) initial tree works: felling, stump grinding and pruning for working clearances;
- ii) installation of TPB for demolition & construction;
- iii) installation of underground services;
- iv) installation of ground protection;
- v) main construction;
- vi) removal of TPB;
- vii) soft landscaping.

9.0 REFERENCES

- Barlow JF & Harrison G. 1999. Shade By Trees, Arboricultural Practice Note 5, AAIS, Farnham, Surrey.
- British Standards Institute. 2012. Trees in Relation to Design, Demolition and Construction - Recommendations BS 5837: 2012 HMSO, London.
- Centre for Ecology & Hydrology. 2006. Tree Roots in the Built Environment, HMSO, London.
- Helliwell R (1980) Provision for New Trees; Landscape Design; July/August issue
- International Society of Arboriculture (ISA). 1994. The Landscape Below Ground. ISA, Champaign, Illinois. USA.
- Lonsdale D 1999. Research for Amenity Trees No.7: Principles of Tree Hazard Assessment and Management, HMSO, London.
- Matheny, N; Clark, J. R.1998. Trees and Development: A Technical Guide to Preservation of Trees during Land Development. ISA, Champaign, Illinois. USA.
- Mattheck C. & Breloer H. 1994. Research for Amenity Trees No.2: The Body Language of Trees, HMSO, London.
- Thomas P, 2000. Trees: Their Natural History, Cambridge University Press, Cambridge.
- Trowbridge J & Bassuk N (2004) Trees in the Urban Landscape: Site Assessment, Design, and Installation; J Wiley & Sons inc. NJ USA

APPENDIX 1

TREE SCHEDULE

Notes for Guidance:

1. Height describes the approximate height of the tree measured in metres from ground level.
2. The Crown Spread refers to the crown radius in meters from the stem centre and is expressed as an average of NSEW aspect if symmetrical.
3. Ground Clearance is the height in metres of crown clearance above adjacent ground level.
4. Stem Diameter (Dm) is the diameter of the stem measured in millimetres at 1.5m from ground level for single stemmed trees. BS 5837:2012 formula (Section 4.6) used to calculate diameter of multi-stemmed trees. Stem Diameter may be estimated where access is restricted and denoted by '#'.
5. Protection Multiplier is 12 and is the number used to calculate the tree's protection radius and area
6. Protection Radius is a radial distance measured from the trunk centre.
7. Growth Vitality - Normal growth, Moderate (below normal), Poor (sparse/weak), Dead (dead or dying tree).
8. Structural Condition - Good (no or only minor defects), Fair (remediable defects), Poor - Major defects present.
9. Landscape Contribution - High (prominent landscape feature), Medium (visible in landscape), Low (secluded/among other trees).
10. B.S. Cat refers to (British Standard 5837:2012 section 4.5) and refers to tree/group quality and value; 'A' – High, 'B' - Moderate, 'C' - Low, 'U' - Unsuitable for retention. The following colouring has been used on the site plans:
 - High Quality (A) (Green),
 - Moderate Quality (B) (Blue),
 - Low Quality (C) (Grey),
 - Unsuitable for Retention (U) (Red)
11. Sub Cat refers to the retention criteria values where 1 is Arboricultural, 2 is Landscape and 3 is Cultural including Conservational, Historic and Commemorative.
12. Useful Life is the tree's estimated remaining contribution in years.



Site: Centre Heights
Date: 25th February 2015

Appendix 1

Landmark Trees Ltd

020 7851 4544

Surveyor(s): Adam Hollis

Ref: AWH/CHT/AIA

BS5837 Tree Constraints Survey Schedule

Tree No.	English Name	Height	Crown Spread	Ground Clearance	Stem Diamete	Age Class	Protection Radius	Growth Vitality	Structural Condition	B.S. Cat	Sub Cat	Useful Life	Comments
1	Maple, Norway	6	2333	2.0	140	Young	1.7	Normal	Fair	C	2	>40	Co-dominant limbs Included bark in branch unions
2	Maple, Norway	6	2333	2.0	140	Young	1.7	Normal	Fair	C	2	>40	Co-dominant limbs Included bark in branch unions
3	Sycamore	12	3334	2.5	369	Early Mature	4.4	Normal	Good	B	2	>40	Co-dominant stems Included bark in main stem unions Lifting pavement / drive
4	Ash, Common	19	4748	10.0	650	Mature	7.8	Normal	Good	B	2	>40	Basal cavity 10cm w x 30cm dp to metal probe Sounds slightly hollow to tap of mallet
5	Tree of Heaven	11	4	5.0	260	Semi-mature	3.1	Moderate	Fair	U		<10	Unsuitable species for position Self-sown / unsuitable location Growing in and grafted into small gap between ramp and wall
6	Chestnut, Horse	15	5778	3.0	400	Semi-mature	4.8	Moderate	Fair	U		<10	Bleeding canker Bleeding on lower stem NSE Tipped back from roof Housing estate tree


APPENDIX 2

RECOMMENDED TREE WORKS

Notes for Guidance:

Husbandry 1 - Urgent (ASAP), 2 - Standard (within 6 months), 3 - Non-urgent (2-3 years)

- CB - Cut Back to boundary/clear from structure.
- CL# - Crown Lift to given height in meters.
- CT#% - Crown Thinning by identified %.
- CCL - Crown Clean (remove deadwood/crossing and hazardous branches and stubs).
- CR#% - Crown Reduce by given maximum % (of outermost branch & twig length)
- DWD - Remove deadwood.
- Fell - Fell to ground level.
- FInv - Further Investigation (generally with decay detection equipment).
- Pol - Pollard or re-pollard.
- Mon - Check / monitor progress of defect(s) at next consultant inspection which should be <18 months in frequented areas and <3 years in areas of more occasional use. Where clients retain their own ground staff, we recommend an annual in- house inspection and where practical, in the aftermath of extreme weather events.
- Svr Ivy / Clr Bs - Sever ivy / clear base and re-inspect base / stem for concealed defects.



Site: Centre Heights
Date: 25th February 2015

Surveyor(s): Adam Hollis
Ref: AWH/CHT/AIA

Appendix 2

Recommended Tree Works

[Hide irrelevant](#)
[Show All Trees](#)

Landmark Trees


Tree No.	English Name	B.S. Cat	Height	Ground Clearance	Crown Spread	Recommended Works	Comments/ Reasons
4	Ash, Common	B	19	10.0	4748	FInv	Basal cavity 10cm w x 30cm dp to metal probe Sounds slightly hollow to tap of mallet Recommended husbandry 2
5	Tree of Heaven	U	11	5.0	4	Fell	Unsuitable species for position Self-sown / unsuitable location Growing in and grafted into small gap between ramp and wall Recommended husbandry 2
6	Chestnut, Horse	U	15	3.0	5778	Fell Third party tree	Bleeding canker Bleeding on lower stem NSE Tipped back from roof Housing estate tree Recommended husbandry 3

APPENDIX 3

RECOMMENDED TREE WORKS TO FACILITATE DEVELOPMENT (See Table 1)

Notes for Guidance:

- RP - Pre-emptive root pruning of foundation encroachments under arboricultural supervision.
- CB - Cut Back to boundary/clear from structure.
- CL# - Crown Lift to given height in meters.
- CT#% - Crown Thinning by identified %.
- CCL - Crown Clean (remove deadwood/crossing and hazardous branches and stubs).
- CR#% - Crown Reduce by given maximum % (of outermost branch & twig length)
- DWD - Remove deadwood.
- Fell - Fell to ground level.
- FInv - Further Investigation (generally with decay detection equipment).
- Pol - Pollard or re-pollard.
- Mon - Check / monitor progress of defect(s) at next consultant inspection which should be <18 months in frequented areas and <3 years in areas of more occasional use. Where clients retain their own ground staff, we recommend an annual in- house inspection and where practical, in the aftermath of extreme weather events.
- Svr Ivy / Clr Bs - Sever ivy / clear base and re-inspect base / stem for concealed defects.



Site: Centre Heights

Date: 25th February 2015

Surveyor(s): Adam Hollis

Ref: AWH/CHT/AIA

Appendix 3

Recommended Tree Works To Facilitate Development

Hide irrelevant

Show All Trees

Landmark Trees

Tree No.	English Name	B.S. Cat	Height	Ground Clearance	Crown Spread	Recommended Works	Comments/ Reasons
6	Chestnut, Horse	U	15	3.0	5778	CB 2m (Fell) Third party tree not relevant to proposal, other than need to cut back off roof	Bleeding canker Bleeding on lower stem NSE Tipped back from roof Housing estate tree To facilitate development

APPENDIX 4

TREE CONSTRAINTS PLAN

NOTE:
 This survey is of a preliminary nature. The trees were inspected from the ground only and no measurements were taken. The survey was conducted on a clear day. No decay detection equipment was employed. The survey does not cover the arrangements that may be required in connection with the laying or removal of underground services.
 Branch spread in metres is taken at the four cardinal points to derive an accurate representation of the crown.
 Root Protection Areas (RPA) are derived from stem diameter measured at 1.5 m above adjacent ground level (taken on sloping ground on the upslope side of the tree base).


Landmark Trees
 20 Broadwick Street, London, W1F 8HT
 Tel: 0207 593 4544 Mobile: 07812 388928
 Email: info@landmarktrees.co.uk Web: www.landmarktrees.co.uk
 Landmark Trees
 Site: Central Heights, 130-150 Finchley Road

Drawing Title: Tree Constraints Plan
 1:200@ A1
 March 2015

Key:

● High Quality	Category A	○ Crown Spread
● Medium Quality	Category B	○ Tree Number
● Low Quality	Category C	○ Species
● Trees Unsuitable for Retention	Category U	○ Category

○ Tree Position Approximate (not shown on original survey)



APPENDIX 5

ARBORICULTURAL IMPACT ASSESSMENT PLAN

