





1 The Old Hall, South Grove  
N6 6BP  
Design & Access Statement: Front Alterations - Rev.A  
14.05.15



Contents	
Site Context	3
Proposals Overview	6
Railings	7
Access	8



## Site Context

The property is situated on South Grove, a predominantly residential street that sits within the Highgate Conservation Area. The main facade of the building faces North West, separated from the road by a brick boundary garden wall, with rendered piers and a wrought-iron gate.

The main building, set back from the boundary line, is flanked by a two-storey wing to the east and by a modern single storey addition with a basement to the west. No. 1 Old Hall, the western addition to the main building, which is in separate ownership and occupation, is the subject of this application.



## EXISTING BUILDING

THE OLD HALL, HIGHGATE - Design & Access Statement: Front Alterations



## Site Context (cont.)

The Old Hall, Grade II\* listed house in the Highgate Conservation Area forms the largest residence in South Grove.

The site of The Old Hall and the site of The Lawns to the east were formerly occupied in the middle of the 16th century by Arundel house, belonging to the Cornwallis family, where Sir William Cornwallis lived during the reigns of Queen Elizabeth and James I, followed by Thomas Howard, 14th Earl of Arundel and 4th Earl of Surrey (later 1st Earl of Norfolk), and where Sir Francis Bacon, Lord Verulam, died in 1626.

The main building dates from a reconstruction in 1694 by Sir William Ashurst on the former site of the western half of Arundel House. The central three-storey block with basement is arranged symmetrically with five sash windows on the first and second floor. It has since been refronted in stock brickwork, extended by a recessed block on the east side, and given an early-19th-century porch.

The rear elevation is afforded two large projecting bays, retaining several original windows with curved heads. The southeastern gable contains a rain-water head with the date 1691 and William and Elizabeth Ashurst's initials. The basement of the two-storey wing to the east may contain brickwork from Arundel House.



The Old Hall rear facade in 1983, prior to the conservatory construction




Western wing street view in 1971, prior to the front extension construction

Reference  
[www.british-history.ac.uk](http://www.british-history.ac.uk)

Existing Building

No. 1 Old Hall, the later two storey western wing, has a pitched slate roof and brick façade which is rendered below ground level. The main entrance to the upper level sits above a lightwell, which is accessed by a rendered stair to the left of the main entrance. The bedrooms to the front and conservatory to the rear of the property are modern, late 20th century additions.

The main facade has been altered since 1971, and now features four identical, symmetrically arranged sash windows to the front gable.



No. 1 Old Hall - Existing Lower Ground Floor Plan



No. 1 Old Hall - Existing front facade



No. 1 Old Hall front facade in 1971, prior to the front extension construction



## Overview of Proposals

This application is concerned with the front of the existing western wing of the Grade II\* listed building where the intention is to create an internal sheltered link between the kitchen and the vaults below the front garden with minimal changes to existing front facade.



We are therefore, seeking planning permission and listed building consent to make the following alterations:-

- Enclose the existing lightwell with a newly formed entrance door at lower level, covered by a glazed roof (1);
- Relocate doorway into existing vault (2);
- Block up the existing small window to the bedroom (3);
- Move the existing railings at patio level forward by approximately 100mm to accommodate enclosure behind (4);
- New brick parapet, with glazed roof enclosure to void; rendered white to match the lower section of the wall behind (5).

The proposed alterations will improve the internal layout and create a more functional, usable space within a family home. The existing vaults will become a useable storage space with minimal visible alterations to the external appearance of the building and negligible impact to the existing fabric of the listed structure.

The minimal frameless glass construction of the roof and glazed elements will allow for adequate daylighting down into the vaults which is currently a gloomy and under-used space.

None of the above alterations will be visible when viewed from the street apart from the raised parapet, which, rendered white will match the wall behind and have minimal visual impact.





The Old Hall entrance gate



No. 1 entrance gate

## Comments from the Highgate Society Planning Surgery

Saturday 15th November 2014

Prior to the first planning application we sought advice on the proposals from the Highgate Society. Concerns were raised about the removal of the iron railings, which although thought to be from the 1970's, were deemed to be more in keeping with the character of the existing frontage.

## Comments from the Highgate Village CAAC

5th May 2015

These comments were echoed by the Highgate Village CAAC, who felt that the new glass balustrades and planters shown on the previous application were incongruous with the listed building.

Following this feedback the new glass balustrades and planters originally shown have been removed and it is proposed that the existing railings be retained and moved slightly forward of their current position. This would have the minimum impact on the composition of the listed building and the character of the Highgate Conservation Area.

The proposed addition of a white rendered, brick parapet as shown is more in keeping with the existing frontage, with the white render matching the rendered lower portion of the existing wall behind. Furthermore, the proposed door has been recessed and would therefore not be visible from the street.







Existing lightwell.



Existing lightwell.



Existing section through lightwell. Not to scale.



Proposed section through lightwell. Not to scale.

## Light levels

Some members of the Highgate Society voiced some concerns about light pollution as a result of light spilling out upwards through the proposed glazed roof to the link.

There will be no change in the light levels in the outdoor environment due to the proposed glazed enclosure. At present there is external lighting attached to the walls of the lightwell, meaning light washes up onto the facade above to a certain extent.

The existing artificial lighting points will be retained but with internal luminaires which will send the light downwards into the space. This plus the fact that the glazed roof will cut out some of the light means that there will be no increase in visible lighting levels as a result of the alterations.

Furthermore, as the lightwell will remain an auxiliary area, only serving as a linking space between the kitchen and the vaults it will only be used infrequently, these internal lights will only be on from time to time.

## Access

The existing steps to the upper ground floor entrance, as well as down to the lightwell would be maintained in the proposed scheme. The new low level entrance access door will not constitute a change to the access condition.

Due to the nature of the existing structure it is not possible to achieve level thresholds at the building entrance and vertical movement within the dwelling is limited by the nature of the listed building being arranged over 2 floors, on various levels, and accessed by existing stairs only.

## Materials

All of the new elements will be designed to be sympathetic with the existing elevation, with little change to the frontage visible from the street. The light touch, glazed enclosure to the roof of the void being the only discernable new element.





STUDIO  
MACKERETH

This document is for the sole use of the person or organisation for whom it has been prepared under the terms of an invitation or appointment by such person or organisation. Unless and to the extent allowed for under the terms of such invitation or appointment this document should not be copied or used or relied upon in whole or in part by third parties for any purpose whatsoever. If this document has been issued as a report under the terms of an appointment by such person or organisation, it is valid only at the time of its production. Studio Mackereth does not accept liability for any loss or damage arising from unauthorised use of this report.

If this document has been issued as a 'draft', it is issued solely for the purpose of client and/or team comment and must not be used for any other purpose without the written permission of Studio Mackereth.

© Copyright subsists in this document.