



Schedule of External Repairs : Chenias News Elevation

- ① Existing main entrance door: Site office sign to be removed and door and frame to be redecorated (to match existing finish).
- ② Existing damaged basement entrance door to be replaced with new to match existing.
- ③ Existing windows: Redundant ventilation grilles to be removed, damaged glass / glass with holes in it to be replaced and windows redecorated (colour to match existing).
- ④ Existing window and louvre frames to be redecorated (colour to match existing)
- ⑤ Plywood board to be removed, damaged glass in existing window to be replaced, window and louvre frames to be redecorated (colour to match existing).
- ⑥ Existing painted masonry and render to be redecorated. (colour to match existing)
- ⑦ Existing redundant mechanical ventilation plant on roof (not visible from street level) to be removed.

Revision	Date	Amendment	Notes
A	10/06/2015	Issued for planning charge of use	

Client	University College London
Project	Chenias News Walkway
Drawing	External Repairs: Chenias News Elevation
Scale	N.T.S.
Date	June 2015
Project No	681
Drawing No	681-C-140
Revision	A

burwell deakins : architects t 020 3995 6010 f 020 3995 6010 a 44, Abchurch Lane, London EC4N 3DF a ur1001@burwelldeakins.com	
---	--