

**PROPOSED WINDOW SCHEDULE**

- W1.1 Timber window to be retained
- W1.2 Timber window to be retained
- W1.3 Timber window to be retained
- W1.4 Timber window to be retained
- W1.5 Steel window replaced with hardwood timber casement double glazed to current building regulations
- W1.6 Steel window replaced with hardwood timber casement double glazed to current building regulations
- W1.7 Steel window replaced with hardwood timber casement double glazed to current building regulations
- W1.8 Steel window to be retained
- W1.9 Steel window to be retained

**FIRST FLOOR SERVICES**


- Drainage**  
Bathroom - 100mm PVC soil pipe receiving waste from shower and basin, run through wall into existing SVP in service shaft.
- En-Suite - 100mm PVC soil pipe receiving waste from shower and basin, run within raised floor void in hall and lobby, through wall into existing SVP in service shaft.
- Kitchen - Saniflow unit placed under sink to pump wasted through 25mm PVC pipe boxed in up wall, run horizontally through new false ceiling void and down to solid pipe in En-Suite.

**Electrical Services**

New electrical services to be taken from existing mains within service shaft and run through new false ceiling void to meter and consumer unit within cupboard off entrance lobby. Domestic cabling to be run horizontally through new false ceiling void with drops cut into plaster and made good with matching lime plaster (existing plaster to be sampled and supplied by lime mortar specialists).


**Mechanical Services**

New electric water heater to be located in cupboard off entrance hall lobby. Pipework to be taken from existing water main in void adjacent to the service shaft and run horizontally through new false ceiling void with drops to bathrooms and kitchen surface mounted to walls and boxed in.



**NOTES:**

This drawing has been prepared for the purpose of Planning and/or Building Regulations approval only, and is not to be used for any other purpose. Drawing based on measured survey / OS Plan.  
All dimensions to be checked on site and any discrepancy notified to The Martin Ralph Group. Written dimensions are to be used in preference to scaled dimensions.  
This drawing is the property of The Martin Ralph Group and must not be reproduced, in part or whole, or deviated from, without their permission.



AMENDMENTS	DATE
C Partial ground floor lobby added	10.07.15
B Window scheduler; services notes; raised floor	10.06.15
A Amendments following input from Historic England	26.05.15

**CLIENT**  
DALEPASS LTD  
7 IRON BRIDGE HOUSE  
3 BRIDGE APPROACH  
LONDON, NW1 8BD

**PROJECT**  
CONVERSION TO FLATS  
1-7 Woburn Walk  
London, WC1H 0UJ

**DRAWING TITLE**  
FIRST / GROUND FLOOR PLANS  
existing and proposed

<b>DATE</b> 09.06.2014	
<b>SCALE</b> 1:100 @ A3	
<b>DRAWING No.</b> 14A_032 011	<b>REVISION</b> C



**RICS** CHARTERED SURVEYORS  
ARCHITECTS & ENGINEERS

11 Dragon House  
Hussar Court  
Brambles Business Park  
Portsmouth  
Hampshire  
PO7 7SF  
[www.martinralph.co.uk](http://www.martinralph.co.uk)  
[info@martinralph.co.uk](mailto:info@martinralph.co.uk)  
T. 023 9225 7711  
F. 023 9225 7712

FIRST FLOOR PLAN AS PROPOSED 1:100

FIRST FLOOR 1-7 WOBURN WALK, CAMDEN

GROUND FLOOR PLAN 1:100  
PARTIAL PLAN - AS PROPOSED