

Croft Structural Engineers
Clock Shop Mews
Rear of 60 Saxon Road
London SE25 5EH

T: 020 8684 4744
E: enquiries@croftse.co.uk
W: www.croftse.co.uk

Basement Impact Assessment

Property Details

35 Greville Road
London
NW6 5JB

Client Information

Igor Gokhberg
55 Peiantho CRT
Vaughan
ON
LGA 1G1
Canada

Structural Design Reviewed by Chris Tomlin MEng CEng MStructE	Above Ground Drainage Reviewed by Phil Henry BEng MEng MICE
Hydrology Report Hannah Fraser CGeol Separate report	Geology Report Jon Smithson CGeol Separate Report
Report compiled by Noma Manzini MEng BEng	

Revision	Date	Comment
-	Aug 2015	First issue



Contents

Executive Summary / Non technical Summary.....	5
Project Summary.....	5
Stage 1 – Screening	6
Stage 2 – Scoping.....	6
Stage 3 – Site investigation and study.....	7
Stage 4 – Impact assessment	7
1. Screening Stage.....	9
Land Stability	9
Subterranean Flow	9
Surface Flow and Flooding	9
2. Scoping Stage.....	12
Land Stability	12
Subterranean Flow	12
Surface Flow & Flooding.....	12
Conceptual Model.....	12
3. Site Investigation and Study.....	14
Desk Study and Walkover Survey.....	14
Proposed Development	14
Site History	15
Local Bombing	16
Listed Buildings.....	16
Highways, Rail and London Underground.....	17
London Underground and Network Rail	17
UK Power Networks.....	17
Vicinity of Trees.....	17
Building Defects	17
Nos 37 Greville Rpad Property to right	18
Local Topography	19
Ground Investigation	19
Geology	20
Surface Flow & Flooding.....	20
Areas of Hard Standing present on site	20
Rainwater down pipes, Drains, Manholes and Gulleys	20

Local Water Sources	20
Field Investigation	20
Monitoring, Reporting and Investigation	20
Land Stability	20
Site Investigation	21
4. Basement Impact Assessment	22
Subterranean Flow.....	22
Land Stability	22
Flood Risk Assessment.....	23
Site Location	24
Potential surface water (pluvial) flooding	24
Potential flooding from infrastructure failure	25
Mitigation measures	25
Summary	25
SUDS Assessment.....	26
Hard standing.....	26
SUDS Assessment	26
SUDS Calculations.....	26
Mitigation Measures	26
Drainage effects on Structure	26
Trees.....	27
Root Protection Zone	27
Conclusion	27
Ground Movement Assessment & Predicted Damage Category.....	28
Burland Scale.....	33
Monitoring.....	34
Risk Assessment.....	35
Monitoring Conclusion	37
Basement Design & Construction Impacts.....	39
Foundation type	39
Roads.....	39
Intended use of structure and user requirements	39
Loading Requirements (EC1-1).....	39
Part A3 Progressive collapse	40

Lateral Stability	40
Exposure and wind loading conditions	40
Stability Design	40
Lateral Actions.....	40
Retained soil Parameters.....	40
Water Table	41
Drainage and Damp Waterproofing.....	41
Localised Dewatering	41
Temporary Works.....	42
Geological Assessment of Land Stability	42
Retaining Wall Calculation.....	42
piled wall 1 (temporary case)	45
Retaining wall analysis & design (BS8002)	45
RETAINING WALL ANALYSIS (BS 8002:1994)	45
RETAINING WALL DESIGN (BS 8002:1994)	48
Design of reinforced concrete retaining wall toe (BS 8002:1994).....	48
Design of reinforced concrete retaining wall stem (BS 8002:1994)	48
Indicative retaining wall reinforcement diagram.....	50
piled wall 1 (permanent case).....	51
Retaining wall analysis & design (BS8002)	51
RETAINING WALL ANALYSIS (BS 8002:1994)	51
RETAINING WALL DESIGN (BS 8002:1994)	53
Design of reinforced concrete retaining wall toe (BS 8002:1994).....	53
Design of reinforced concrete retaining wall heel (BS 8002:1994)	53
Design of reinforced concrete retaining wall stem (BS 8002:1994)	54
Indicative retaining wall reinforcement diagram.....	55
capping beam for piled wall 1	56
RC beam analysis & design (EN1992)	56
RC beam analysis & design (EN1992-1)	56
Support A	57
Mid span 1.....	58
Support B.....	59
piled wall 2 (temporary case)	61
Retaining wall analysis & design (BS8002)	62

RETAINING WALL ANALYSIS (BS 8002:1994)	63
RETAINING WALL DESIGN (BS 8002:1994)	65
Design of reinforced concrete retaining wall toe (BS 8002:1994)	65
Design of reinforced concrete retaining wall heel (BS 8002:1994)	65
Design of reinforced concrete retaining wall stem (BS 8002:1994)	66
Indicative retaining wall reinforcement diagram.....	67
piled wall 2 (permanent case).....	68
Retaining wall analysis & design (BS8002)	68
RETAINING WALL ANALYSIS (BS 8002:1994)	68
RETAINING WALL DESIGN (BS 8002:1994)	70
Design of reinforced concrete retaining wall toe (BS 8002:1994)	70
Design of reinforced concrete retaining wall heel (BS 8002:1994)	70
Design of reinforced concrete retaining wall stem (BS 8002:1994)	71
Indicative retaining wall reinforcement diagram.....	72
capping beam for piled wall 2	73
RC beam analysis & design (EN1992)	73
RC beam analysis & design (EN1992-1)	73
Support A	74
Mid span 1.....	75
Support B.....	76
Noise and Nuisance Control.....	79
CTMP.....	79
Appendix A ; Construction Method Statement.....	80
35 Greville Road	87
1. Basement Formation Suggested Method Statement.	87
2. Enabling Works	88
3. Piling Sequencing.....	88
4. Demolition, Recycling, Dust/Noise Control and Site Hoarding.....	90
5. Trench sheet design and temporary prop Calculations	91
STANDARD LAP TRENCH SHEETING	92
KD4 SHEETS	96
Appendix B : Structural Drawings.....	103

Executive Summary / Non technical Summary

The London Borough of Camden requires a Basement Impact Assessment (BIA) to be prepared for developments including basements and light wells within its area of responsibility. CGP4 – Basements and Light wells details the requirements for a BIA undertaken in support of proposed developments; in summary the Council will only allow basement construction to proceed if it does not:

- Cause harm to the built environment and local amenity;
- Result in flooding;
- Lead to ground instability.

In order to comply with the above clauses a BIA must undertake 5 stages detailed in CPG 4. This report has been produced in line with the guidance of CPG4 and the associated documents supporting CGP4 such as DP23, DP26, DP25 & DP27.

Project Summary

Description of Property

The existing property is a detached dwelling over three floors with a loft storage space area. The construction is load bearing masonry walls externally and internally with concrete floors at lower ground floor, ground floor and at first floor. Timber floors in loft storage space.




Figure 1: Side elevation

	<p>Proposed Works</p> <p>The proposed works require the construction of:</p> <ul style="list-style-type: none"> • A new basement under the property. • Light wells to the front and rear • Garden basement <ul style="list-style-type: none"> ○ Roof slab to the garden ○ SUDS (Storm water storage above the garden area) ○ Covering garden slab with new top soil <p>Croft Structural Engineers Ltd has extensive knowledge of constructing new basements. Over the last 10 years Croft Structural Engineers has been involved in the design of over 500 basements in and around London. The method to be utilised at 35 GREVILLE ROAD is:</p> <ol style="list-style-type: none"> 1. Place a contiguous pile wall around the perimeter of the garden area & light wells 2. Excavate front to allow for conveyor to be erected. 3. Safely and securely support the existing building above 4. Slowly work from the front to the rear inserting narrow cantilevered retaining walls sequentially using well developed and understood underpinning methods. 5. Prop retaining walls in temporary condition back to the central soil "dumpling" . 6. Prop across the width of the basement, excavate central soil "dumpling" & cast basement slab 7. Waterproof internal space with a drained cavity system.
<p>Stage 1 – Screening</p>	<p>Screening identified areas of concern and concluded a requirement to proceed to a scoping stable for the Land stability, Hydrology, Surface Water and flooding.</p>
<p>Stage 2 – Scoping</p>	<p>The Scoping stage identified the potential impacts and set the parameters required for further study of the areas of concern highlighted in the Screening phase.</p> <p>The property was inspected and a walk over desk survey completed by an engineer. The information from this was utilised to formulate the requirement for a ground, Geology and hydrogeology investigation.</p>


<p>Stage 3 – Site investigation and study</p>	<p>A Chartered Structural engineer inspected the building to determine the current condition of the property.</p> <p>Visual inspections were completed of the adjacent properties to determine if there were signs of structural movement.</p> <p>The neighbouring land has not been excavated on but an engineer has assessed the age of the adjacent properties and considered the type of foundations used for that period and assumed these in the design.</p> <p>A ground investigation with deep boreholes has been completed.</p> <ul style="list-style-type: none">• London Clay Formation <p>Laboratory testing was undertaken on the soil samples.</p> <p>Ground water has been measured over repeat visits to determine water levels and flows.</p> <ul style="list-style-type: none">• Perched water was found at 0.85m BGL
<p>Stage 4 – Impact assessment</p>	<p>Land stability</p> <p>The Geologist has concluded that the basement will not make the area unstable.</p> <p>The movement assessment of the basement and its construction are SLIGHT 1-0 on the Burland scale.</p> <p>It is concluded that with the construction of the new basement at 35 Greville Road should not have significant impacts on land stability provided that:</p> <ul style="list-style-type: none">• Groundwater inflow, if encountered is properly controlled and is monitored before, during and after construction.• The construction of the basement is carried out by a competent who will adopt suitable measures to maintain the stability of the excavations• Care is taken to minimise disturbance to trees and their roots.• Concrete is designed to account for the sulphate conditions anticipated.• Monitoring of the structures is carried out before, during and after construction. <p>Hydrogeology</p> <p>Groundwater inflow if encountered is reduced to a minimum and properly controlled such that there is no significant wash out of fine material. Groundwater levels should be monitored before and during construction.</p>

Drainage & Surface Water Flow

Ground water was not observed during drilling at the site, however, groundwater levels were observed at 0.83 and 0.94mBGL on subsequent monitoring visits. The direction of groundwater flow is not known at the site.

1. Screening Stage	
	<p>This stage should identify any areas for concern and therefore focus effort for further investigation.</p> <p>The questions below are taken from the Camden CPG 4 – Basements and Lightwells.</p>
Land Stability	Refer to Chartered Geologist Report.
Subterranean Flow	Refer to Chartered Hydrogeologist report completed by A Hydrogeologist with the "CGeol" (Chartered Geologist) qualification from the Geological Society of London.
Surface Flow and Flooding	
	<p>Question 1: Is the site within the catchment of the pond chains on Hampstead Heath?</p>  <p><i>Figure 2: Extract from figure 14 of the Hydrogeological Study</i></p> <p>No. The site lies outside the areas denoted by figure 14 of the Arup report.</p>

	<p>Question 2. As part of the proposed site drainage, will surface water flows (e.g. volume of rainfall and peak run-off) be materially changed from the existing route?</p> <p>Unknown –The Garden basement may reduce the impermeable areas. Carry forward to scoping</p>												
	<p>Question 3. Will the proposed basement development result in a change to the hard surfaced /paved external areas?</p> <p>Unknown –The Garden basement may reduce the impermeable areas. Carry forward to scoping</p>												
	<p>Question 4. Will the proposed basement result in changes to the inflows (instantaneous and long term of surface water being received by adjacent properties or downstream watercourses?)</p> <p>Unknown – The light wells may reduce the impermeable areas. Carry forward to scoping</p>												
	<p>Question 5. Will the proposed basement result in changes to the quality of surface water being received by adjacent properties or downstream watercourses?</p> <p>No. The quality of water is unlikely to be altered.</p>												
	<p>Question 6 : IS the site in an area identified to have surface water flood risk according to either the Local Flood Risk Management Strategy or the Strategic Flood Risk Assessment or is it at risk from flooding, for example because the proposed basement is below the static water level of nearby surface water feature?</p> <p>The potential sources of flooding are summarised below:</p> <table border="1" data-bbox="443 1653 1430 2058"> <thead> <tr> <th>Potential Source</th> <th>Potential Flood Risk at Site?</th> <th>Justification</th> </tr> </thead> <tbody> <tr> <td>Fluvial flooding</td> <td>No</td> <td>EA Flood Mapping shows Flood Zone 1. Distance from nearest surface watercourse >1km</td> </tr> <tr> <td>Tidal flooding</td> <td>No</td> <td>Site location is 'inland' and topography > 40mAOD.</td> </tr> <tr> <td>Flooding from rising / high groundwater</td> <td>No</td> <td>Site is located on low permeability London Clay.</td> </tr> </tbody> </table>	Potential Source	Potential Flood Risk at Site?	Justification	Fluvial flooding	No	EA Flood Mapping shows Flood Zone 1. Distance from nearest surface watercourse >1km	Tidal flooding	No	Site location is 'inland' and topography > 40mAOD.	Flooding from rising / high groundwater	No	Site is located on low permeability London Clay.
Potential Source	Potential Flood Risk at Site?	Justification											
Fluvial flooding	No	EA Flood Mapping shows Flood Zone 1. Distance from nearest surface watercourse >1km											
Tidal flooding	No	Site location is 'inland' and topography > 40mAOD.											
Flooding from rising / high groundwater	No	Site is located on low permeability London Clay.											

	Surface water (pluvial) flooding	NO	The 35 GREVILLE ROAD is noted on the flood street list and maps from 1975 or 2002
			
	Flooding from infrastructure failure	Yes	Drainage at or near the site could potentially become blocked or cracked and overflow or leak. Drainage of the basement terrace areas may rely on pumping.
	Flooding from reservoirs, canals and other artificial sources	No	There are no reservoirs, canals or other artificial sources in the vicinity of the site that could give rise to a flood risk.
Yes the site is noted Carry forward to scoping stage			

<h2>2. Scoping Stage</h2>	
	Identifies the potential impacts of the areas of concern highlighted in the Screening phase.
Land Stability	Refer to Chartered Geologist Report.
Subterranean Flow	Refer to Chartered Hydrogeologist report . completed by A Hydrogeologist with the "CGeol" (Chartered Geologist) qualification from the Geological Society of London.
Surface Flow & Flooding	<p>Conceptual Model</p> <p>The proposed works at 35 GREVILLE ROAD require in insertion of a basement.</p> <p>The basement is under the footing print of the property which will not affect the overall flow.</p> <p>The basement enlarges the existing single dwelling and is not an additional unit.</p> <p>The Garden basement may decrease the permeable areas and this may increase the surface water flows and further investigations should be undertaken.</p>
	<p>Question 1: Is the site within the catchment of the pond chains on Hampstead Heath?</p> <p>No further info required from Scoping stage</p> <p>Yes – Carry forward to Basement Impact Assessment Stage</p>
	<p>Question 2. As part of the proposed site drainage, will surface water flows (e.g. volume of rainfall and peak run-off) be materially changed from the existing route?</p> <p>Unknown –The Garden basement may reduce the impermeable areas. Carry forward to Site Investigation & desk Study</p>
	<p>Question 4. Will the proposed basement result in changes to the inflows (instantaneous and long term) of surface water being received by adjacent properties or downstream watercourses?</p> <p>Unknown –The Garden basement may reduce the impermeable areas. Carry forward to Site Investigation & desk Study</p>

	<p>Question 5. Will the proposed basement result in changes to the quality of surface water being received by adjacent properties or downstream watercourses?</p> <p>No.</p>
	<p>Question 6 : Is the site in an area identified to have surface water flood risk according to either the Local Flood Risk Management Strategy or the Strategic Flood Risk Assessment or is it at risk from flooding, for example because the proposed basement is below the static water level of nearby surface water feature?</p> <p>It is evident from the screening study that the only significant flood risks at 35 GREVILLE ROAD are due surface water (pluvial) flooding and failure of existing sewers in the vicinity of the site.</p> <p>Carry forward to Site Investigation & Desk Study</p>

3. Site Investigation and Study

Identifies the relevant features of the site and its immediate surroundings providing further scoping where required.

Desk Study and Walkover Survey

Noma Manzini, an Engineer from Croft Structural Engineers visited 35 GREVILLE ROAD.

Date of inspection was on the 16th of June

Proposed Development

The existing property is a detached dwelling over three floors with a loft storage space area. The construction is load bearing masonry walls externally and internally with concrete floors at lower ground floor, ground floor and at first floor. Timber floors in loft storage space.

Location

The property is located in a built up area. Mature trees are present in the vicinity. The surrounding area is relatively flat with a slight slope downwards from north-west to south-east.



Figure 3: Rear elevation




Figure 4: Rear ground elevation

Site History

What was the previous usage of the site?




Figure 5: Map of London 1868 - Edward Weller

The site and vicinity have been residential for over one hundred years.

The site is noted in Pevsner's Architectural Guide, London 4: North. The area is described as 'an enclave of trim mid-nineteenth century stuccoed streets'.

Local Bombing



Figure 6: Bomb sight map

A high-explosive bomb, is recorded in the Aggregate Night Time Bomb Census as having been dropped between 7 October 1940 and 6 June 1941, close to the site.

Listed Buildings

Is the building or Adjacent buildings listed
No the propret is not listed but the adjacent building is listed




Figure 7: Listed building map

	<p>Highways, Rail and London Underground</p> <p>Yes. Site is within 5m of the footpath/alleyway and the road surface is further than 5m from the front lightwell.</p>
<p>London Underground and Network Rail</p>	<p>Is the site over (or within the exclusion zone) of any tunnels, e.g. railway lines?</p> <p>No. Nearest is the Overground Rail, +/- 65m from site.</p>  <p><i>Figure 8: Map showing proximity of rail lines</i></p>
<p>UK Power Networks</p>	<p>Will the basement works affect any UK Power Network Assets? (Substations etc)</p>
<p>Vicinity of Trees</p>	<p>Some shrubbery and general vegetation in the neighbouring garden; A mature tree is also present in the neighbouring garden.</p> <p>Are any trees to be removed due to the basement? No trees will be removed</p>
<p>Building Defects</p>	<p>A visual inspection was undertaken of the existing building with particular attention given to movement to the building. The defects noted were:</p> <ul style="list-style-type: none"> • Fine cracking was noted above ground floor door lintel • Fine to moderate cracking was noted on the garage walls <p>Structural Assessment of ongoing movement:</p>



Figure 9: Cracking on garage walls

Adjacent Properties

The condition of the adjacent buildings have been inspected to consider whether the basement will significantly affect their structure.

Visual inspections of the internal facades have been undertaken of the properties.



Figure 10: Areal map of 35 Greville Road and 37 Greville Road

Nos 37 Greville
Rpad Property
to right

Property Age : Over 100 years old

Property use : Residential

Number of storeys : 3

Is a basement present? Planning permission for a new basement was granted on the 18-04-13. It is not know whether this was subsequently built.



Figure 11: 37 Greville Road front elevation



Figure 12: 37 Greville Road rear elevation

<p>Local Topography</p>	<p>As mentioned previously, the area surrounding the property has a general slope, downwards from north-west to south-east. The slope is gradual; there are no retaining walls for sudden changes in elevation.</p>
<p>Ground Investigation</p>	<p>Refer to the ground investigation report by Ground and Water, which is submitted as a separate document.</p>

Geology	Refer to the ground investigation report, the hydrogeology report and the land stability assessment, submitted separately.
Surface Flow & Flooding	Refer to the ground investigation report, the hydrogeology report and the land stability assessment, submitted separately.
Areas of Hard Standing present on site	Existing Area of hardstanding outside is ; Area = approximately 325m ²
Rainwater down pipes, Drains, Manholes and Gulleys	As described previously, there is a surface water drainage gully in the front yard and pea-shingle drainage in the rear yard.
Local Water Sources	<p>Are there any ponds lakes or water courses on the site or adjacent sites?</p> <p>No, there are not surface water features (natural or man-made) on the adjacent sites</p>
	<p>Field Investigation</p> <p>Ground investigation specialists visited the site and subsequently produced are report for the existing ground and groundwater conditions.</p>
	<p>Monitoring, Reporting and Investigation</p> <p>Ground investigation specialists visited the site and subsequently produced are report for the existing ground and groundwater conditions.</p>
Land Stability	<p>Refer to Chartered Geologist Report for land stability issues addressed to Stage 3.</p> <p>Features and items of concern relating to data from Stage 3 are included in this report.</p>
Subterranean Flow	Refer to Chartered Hydrogeologist report (Basement Impact Assessment: Groundwater). This is completed by a Hydrogeologist with the "CGeol" (Chartered Geologist) qualification from the Geological Society of London.

Features and items of concern relating to data from Stage 3 are included in this report.

Site Investigation

Soil investigation Brief

The Soil investigation was completed by (Soil investigation Company).

From the Scoping stage we considered that their brief should cover:

- A trial pit to the front side to confirm the existing foundations. The purpose is to consider the effect of the works on the neighbouring properties and the find the ground conditions below the site.
- It would have been preferred to complete two bore holes on this site.. With the size of site, and our knowledge of the area it is not expect for there to be a large variation across the small site, therefore one borehole 5m deep was completed.
- Stand pipe to be inserted to monitor ground water; record initial strike and the water level after 1 month.
- Site testing to determine insitu soil parameter. SPT testing to be undertaken.
- Laboratory testing to confirm soil make up and properties.
- The Historic maps and walk over survey did not highlight any significant contamination sources, therefore no site test of the ground has been requested.
- Factual Report on soil conditions.
- Interpretative reports
- Calculation of Bearing pressures from SPT.
- Indication of ϕ (angle of friction) from SPT.
- Indication of soil type

Soil Report is provided under a separate cover.


4. Basement Impact Assessment

Subterranean Flow	Refer To Hydrogeologist report : Conclusions re stated in the Executive Summary
Land Stability	Refer to Geologist Report: Conclusions re stated in the Executive Summary
Conservation and Listed Buildings	If the property is in a conservation area, or it is listed then management plan for demolition and construction may be needed. This is not included with the this BIA document and is not within the Croft Structural Engineers Brief.

Flood Risk Assessment

In accordance with guidance from CIRIA, PPS25 and the National Planning Policy Framework, the basement will be designed to be sustainable in terms of the risk of flooding. Amongst other considerations, the design will include provisions to minimise the adverse impacts of flooding on the operation of the building, the users, the surroundings and the occupants of nearby properties. This must be preceded by a Flood Risk Assessment (FRA), and is staged as follows:

- A subsequent scoping study to consider further the identified sources, assessing the risks proposing measures to mitigate them.

<p>Site Location</p>	<p>The site is approximately 325m² in size.</p> <p>It is located in a densely built-up area.</p> <p>From inspection of OS contours, the site appears to lie on ground which slopes down from north to south, by approximately 1 in 50.</p> <p>Residential houses exist either side of the site. These buildings are at the same level.</p> <p>There are gardens to the front and rear of the site. Immediately to the front, this road is relatively flat.</p> <p>The nearest water course is 250km away</p> <p>The EA has not identified any flood risks associated with the nearby water courses.</p> <div data-bbox="427 1003 603 1321"> <p>Click on the map to see what Flood Zone (National Planning Policy Guidance definitions) the proposed development is in.</p> <p><input checked="" type="checkbox"/> Flood Map for Planning (Rivers and Sea)</p> <ul style="list-style-type: none"> ■ Flood Zone 3 ■ Flood Zone 2 ■ Flood defences (Not all may be shown*) ■ Areas benefiting from flood defences (Not all may be shown*) — Main rivers </div>  <p style="text-align: center;"><i>Figure 13: Flood map for planning (Environment Agency)</i></p> <p>The site is within Zone 1, a low probability flood risk area.</p>
<p>Potential surface water (pluvial) flooding</p>	<p>35 GREVILLE ROAD basement lies on low point on Greencroft Gardens. Any surface water runoff would be directed to this section of the road. It is likely that this area of road would have been flooded in 2002.</p> <p>It is understood that this flooding was due to the Thames Water relief sewer being overloaded. It is also understood that Thames Water subsequently increased the capacity of this relief system: the likelihood of flooding of this nature is now significantly reduced.</p>

<p>Potential flooding from infrastructure failure</p>	<p>In addition to the storm water relief sewer previously mentioned, there is believed to be a trunk sewer running along the length of 35 GREVILLE ROAD. Blockage or failure of either of these may result in the following sequential events:</p> <ul style="list-style-type: none"> • Excess flow from 35 GREVILLE ROAD may accumulate in the area of road in front of the site. • This flow would travel in the direction away from the front elevation of the property owing to the site being on a slightly higher level than the opposite side of the street, and the raised level of the pavement above the road (see photo below). <p>The likelihood of flow into the front light wells is also reduced by the existing landscaped areas in the front garden: these would partially relieve any excess flow that would migrate towards the front of the building.</p> <p>A pumping mechanism will be installed for the proposed basement. There is a likelihood that this may fail and allow excess water to accumulate. If this were to occur, the build-up of water would be gradual and noticeable before it becomes a significant life-threatening hazard.</p>
<p>Mitigation measures</p>	<p>We would recommend the following measures to reduce the risks mentioned above:</p> <ul style="list-style-type: none"> • Install a dual pumping system to maintain operation in the event of a failure. This should include a battery backup and a suitable alarm system for warning purposes.
<p>Summary</p>	<p>The risk of flooding from excess surface water is not considered significant. There is a risk of flooding due to the failure of the pumping system but this can be reduced to acceptable levels with appropriate design and installation measures.</p>


SUDS Assessment							
Hard standing	<table style="width: 100%; border-collapse: collapse;"> <tr> <td style="width: 60%;">Existing Hard Standing</td> <td style="text-align: right;">= 325 m²</td> </tr> <tr> <td>Proposed Hardstanding</td> <td style="text-align: right;">= 328 m²</td> </tr> <tr> <td>Percentage Increase in Hard standing</td> <td style="text-align: right;">= 0.9 %</td> </tr> </table>	Existing Hard Standing	= 325 m ²	Proposed Hardstanding	= 328 m ²	Percentage Increase in Hard standing	= 0.9 %
Existing Hard Standing	= 325 m ²						
Proposed Hardstanding	= 328 m ²						
Percentage Increase in Hard standing	= 0.9 %						
SUDS Assessment	<p>From review of the existing and proposed hardstanding the increase will be?</p> <p style="text-align: center;">0.9 %</p> <table border="1" style="width: 100%; border-collapse: collapse; margin-top: 10px;"> <tr> <td style="width: 50%;">Percentage Increase < 5%</td> <td style="width: 50%;">No SUDS to be incorporated into scheme</td> </tr> <tr> <td>Percentage Increase Between 5% to 10%</td> <td></td> </tr> </table> <p>Where garden basements are present then a soil band of a minimum of 1m should be provided.</p> <p>Where the soil cover is greater than 1m of soil is not present then SUDs is not required</p>	Percentage Increase < 5%	No SUDS to be incorporated into scheme	Percentage Increase Between 5% to 10%			
Percentage Increase < 5%	No SUDS to be incorporated into scheme						
Percentage Increase Between 5% to 10%							
SUDS Calculations	As explained above. SUDS calculation is not required						
Mitigation Measures	As explained above. SUDS calculation is not required						
Drainage effects on Structure	<p>Not build over agreements known of.</p> <p>Flooding. The site is not in an area of high risk flooding.</p>						

Trees	
Root Protection Zone	<p>RPA = 1.5 x Crown diameter.</p> <p>The basement is within the RPA of the trees.</p>
Conclusion	<p>The Basement does Not Cuts into the Root protection Zone</p> <p>The increased depth of foundations necessary for the basement places the new foundations outside the effects of trees. The building will be more stable due to the new basement.</p>


Ground Movement Assessment & Predicted Damage Category

This assessment covers both short term and long term movements relating to the construction and the performance of the permanent works. The design and construction methodology aims to limit damage to the existing building on the site and to all adjoining buildings to Category 1 as set out in Table 2.5 of CIRIA report C 580 .


This assessment has used empirical means as set out in CIRIA2 C 580 Embedded Retaining Walls: Guidance for Economic Design.



(b) Influence of horizontal strain on $\Delta L / \epsilon_{lim}$
 (after Burland, 2001)



(c) Relationship between damage category and deflection ratio and horizontal tensile strain for hogging for $(L/H) = 1.0$ (after Burland, 2001)



Uplift Calc

Total Dead Load =

Slab =	112 kN/m		
Toe and heel =	29.75 kN/m		
Wall =	45		
Soil = (0 +	0) x 2 =	0
Total Dead load =	592.75 kN/m		-0.72

Total Uplift Force =


525.6 kN/m f.o.s. = **1.13 No Global Uplift**

Slab Uplift

Slab =	10 kN/m	Uplift =	36
Service Moment =	-637 kNm/m		
Factored Design moment =	-749.7 kNm/m		
Factored Design shear =	-214.2 kN/m		

Global Heave


Weight of building =	170 kN/m		
Weight of soil removed =	788.4		
% change	78%	place	78% of Slab area as heave protection
Wide of Heave protection =	11.4519 m	place	11.45 m of Slab area as heave protection



Horizontal movement Assessment CIRIA C580: Embedded Retaining walls - Guide to Economic Design


Potential Movement Due to wall installation

Horizontal surface movement =	0.05%				
Delta H =	0.05%	x	3600	=	1.8 mm
Vertical Surface Movement =	0.05%				
Delta V =	0.05%	x	3600	=	1.8 mm
Distance behind wall wall to negligible movement					
l _h =	3600	x	1.5	=	5400 mm




Potential Movement Due to wall Excavation

Horizontal surface movement =	0.15%				
Delta H =	0.15%	x	3600	=	5.4 mm
Vertical Surface Movement =	0.10%				
Delta V =	0.10%	x	3600	=	3.6 mm
Distance behind wall wall to negligible movement					
l _h =	3600	x	4	=	14400 mm



		Excavation movement		Installation movement	
		Distance	delta V	Distance	delta V
Nodes	x	14400	0	5400	0
	y	0	-1.8	0	-7.2



Determine Horizontal Movement

$$\text{delta } l = \frac{7.2 \text{ mm}}{14400 \text{ mm}} = 0.05\%$$

Table 2.4 CIRIA C580

Category of Damage	Normal Degree	Limiting Tensile Strain %
0	Negligible	0.00% - 0.05%
1	Very slight	0.05% - 0.075%
2	Slight	0.075% - 0.15%
3	Moderate	0.15% - 0.30%
4 to 5	Severe to Very Server	> 0.30%

Anticipated Damagae May be Categorised as **"Negligible to Slight Category 0-1"**

Any ground works pose an elevated risk to adjacent properties. The proposed works undermines the adjacent property along the party wall line:

The party wall is to be underpinned. Underpinning the party wall will remove the risk of the movement to the adjacent property.

The works must be carried out in accordance with the party wall act and condition surveys will be necessary at the beginning and end of the works.

The method statement provided at the end of this report has been formulated with our experience of over 120 basements completed without error.

The design of the retaining walls is completed to K_0 lateral design stress values. This increase the design stresses on the concrete retaining walls and limits the overall deflection of the retaining wall.

It is not expected that any cracking will occurring during the works. However our experience informs us that there is a risk of movement to the neighbours.

To reduce the risk the development:

- Employ a reputable firm for extensive knowledge of basement works.
- Employ suitably qualified consultants. Croft Structural engineer has completed over 120 basements in the last 4 years.
- Design the underpins to the stable without the need for elaborate temporary propping or needing the floor slab to be present.
- Provide method statements for the contractors to follow
- Investigate the ground, now completed.
- Record and monitor the external properties. This is completed by a condition survey on under the Party Wall Act before and after the works are completed. See end of method statement.
- Allow for unforeseen ground conditions: Loose ground is always a concern. The method statement and drawings show the use of precast lintels to areas of soft ground; this follows the guidance by the underpinning association.

	<p>With the above the maximum level of cracking anticipated is Hairline cracking which can be repaired with decorative cracking and can be repaired with decorative repairs. Under the party wall Act damage is allowed (although unwanted) to occur to a neighbouring property as long as repairs are suitability undertaken to rectify this. To mitigate this risk The Party Wall Act is to be followed and a Party Wall Surveyor will be appointed.</p>												
<p>Burland Scale</p>	<p>Extract from The Institution of Structural Engineers "Subsidence of Low-Rise Buildings"</p> <p>Table 6.2 Classification of visible damage to walls with particular reference to type of repair, and rectification consideration</p> <table border="1" data-bbox="432 674 1374 1133"> <thead> <tr> <th>Category of Damage</th> <th>Approximate crack width</th> <th>Limiting Tensile strain</th> <th>Definitions of cracks and repair types/considerations</th> </tr> </thead> <tbody> <tr> <td>0</td> <td>Up to 0.1</td> <td>0.0-0.05</td> <td>HAIRLINE – Internally cracks can be filled or covered by wall covering, and redecorated. Externally, cracks rarely visible and remedial works rarely justified.</td> </tr> <tr> <td>1</td> <td>0.2 to 2</td> <td>0.05-0.075</td> <td>FINE – Internally cracks can be filled or covered by wall covering, and redecorated. Externally, cracks may be visible, sometimes repairs required for weather tightness or aesthetics. NOTE: Plaster cracks may, in time, become visible again if not covered by a wall covering.</td> </tr> </tbody> </table> <p>The anticipated damage Category for the new basement is 0- 1</p>	Category of Damage	Approximate crack width	Limiting Tensile strain	Definitions of cracks and repair types/considerations	0	Up to 0.1	0.0-0.05	HAIRLINE – Internally cracks can be filled or covered by wall covering, and redecorated. Externally, cracks rarely visible and remedial works rarely justified.	1	0.2 to 2	0.05-0.075	FINE – Internally cracks can be filled or covered by wall covering, and redecorated. Externally, cracks may be visible, sometimes repairs required for weather tightness or aesthetics. NOTE: Plaster cracks may, in time, become visible again if not covered by a wall covering.
Category of Damage	Approximate crack width	Limiting Tensile strain	Definitions of cracks and repair types/considerations										
0	Up to 0.1	0.0-0.05	HAIRLINE – Internally cracks can be filled or covered by wall covering, and redecorated. Externally, cracks rarely visible and remedial works rarely justified.										
1	0.2 to 2	0.05-0.075	FINE – Internally cracks can be filled or covered by wall covering, and redecorated. Externally, cracks may be visible, sometimes repairs required for weather tightness or aesthetics. NOTE: Plaster cracks may, in time, become visible again if not covered by a wall covering.										

Monitoring

Monitoring - In order to safeguard the existing structures during underpinning and new basement construction movement monitoring is to be undertaken.

Risk Assessment	Monitoring Level proposed	Type of Works.
	<p>Monitoring 1</p> <p>Visual inspection and production of condition survey by Party wall surveyors at the beginning of the works and also at the end of the works.</p>	<p>Loft conversions, cross wall removals, insertion of padstones Survey of LUL and Network Rail tunnels. Mass concrete, reinforced and Piled foundations to new build properties</p>
	<p>Monitoring 2</p> <p>Visual inspection and production of condition survey by Party wall surveyors at the beginning of the works and also at the end of the works. Visual inspection of existing party wall during the works. Inspection of the footing to ensure that the footings are stable and adequate.</p>	<p>Removal of lateral stability and insertion of new stability frames Removal of main masonry load bearing walls. Underpinning works less than 1.2m deep</p>
	<p>Monitoring 3</p> <p>Visual inspection and production of condition survey by Party wall surveyors at the beginning of the works and also at the end of the works. Visual inspection of existing party wall during the works. Inspection of the footing to ensure that the footings are stable and adequate. Vertical monitoring movement by standard optical equipment</p>	<p>Lowering of existing basement and cellars more than 2.5m Underpinning works less than 3.0m deep in clays Basements up to 2.5m deep in clays</p>
	<p>Monitoring 4</p> <p>Visual inspection and production of condition survey by Party wall surveyors at the beginning of the</p>	<p>New basements greater than 2.5m and shallower than 4m Deep in gravels</p>

	<p>works and also at the end of the works. Visual inspection of existing party wall during the works. Inspection of the footing to ensure that the footings are stable and adequate. Vertical monitoring movement by standard optical equipment Lateral movement between walls by laser measurements</p>	<p>Basements up to 4.5m deep in clays Underpinning works to grade I listed building</p>
	<p>Monitoring 5</p> <p>Visual inspection and production of condition survey by Party wall surveyors at the beginning of the works and also at the end of the works. Visual inspection of existing party wall during the works. Inspection of the footing to ensure that the footings are stable and adequate. Vertical & Lateral monitoring movement by theodolite at specific times during the projects.</p>	<p>Underpinning works to Grade I listed buildings Basements to Listed building Basements deeper than 4m in Gravels Basements deeper than 4.5m in clays Underpinning, basements to buildings that are expressing defects.</p>
	<p>Monitoring 6</p> <p>Visual inspection and production of condition survey by Party wall surveyors at the beginning of the works and also at the end of the works. Visual inspection of existing party wall during the works. Inspection of the footing to ensure that the footings are stable and adequate. Vertical & Lateral monitoring movement by electronic means with live data gathering. Weekly interpretation</p>	<p>Double storey basements supported by piled retaining walls in gravels and soft sands. (N<12)</p>


	<p>Monitoring 7</p> <p>Visual inspection and production of condition survey by Party wall surveyors at the beginning of the works and also at the end of the works.</p> <p>Visual inspection of existing party wall during the works.</p> <p>Inspection of the footing to ensure that the footings are stable and adequate.</p> <p>Vertical & Lateral monitoring movement by electronic means with live data gathering with data transfer.</p>	<p>Larger Multi storey basements on particular projects.</p>		
<p>Monitoring Conclusion</p>	<p>The level of Monitoring Croft recommend on 35 Greville Road is:</p> <table border="1" data-bbox="432 1037 1430 1720"> <tr> <td data-bbox="432 1037 944 1720"> <p>Monitoring 4</p> <p>Visual inspection and production of condition survey by Party wall surveyors at the beginning of the works and also at the end of the works.</p> <p>Visual inspection of existing party wall during the works.</p> <p>Inspection of the footing to ensure that the footings are stable and adequate.</p> <p>Vertical monitoring movement by standard optical equipment</p> <p>Lateral movement between walls by laser measurements</p> </td> <td data-bbox="944 1037 1430 1720"> <p>New basements greater than 2.5m and shallower than 4m Deep in gravels</p> <p>Basements up to 4.5m deep in clays</p> <p>Underpinning works to grade I listed building</p> </td> </tr> </table> <p>Before the works begin a detailed monitoring report is required to confirm the implementation of the Monitoring. The items that this should cover are</p> <ul style="list-style-type: none"> • Risk Assessment to determine level of Monitoring • Scope of Works • Applicable standards • Specification for Instrumentation 		<p>Monitoring 4</p> <p>Visual inspection and production of condition survey by Party wall surveyors at the beginning of the works and also at the end of the works.</p> <p>Visual inspection of existing party wall during the works.</p> <p>Inspection of the footing to ensure that the footings are stable and adequate.</p> <p>Vertical monitoring movement by standard optical equipment</p> <p>Lateral movement between walls by laser measurements</p>	<p>New basements greater than 2.5m and shallower than 4m Deep in gravels</p> <p>Basements up to 4.5m deep in clays</p> <p>Underpinning works to grade I listed building</p>
<p>Monitoring 4</p> <p>Visual inspection and production of condition survey by Party wall surveyors at the beginning of the works and also at the end of the works.</p> <p>Visual inspection of existing party wall during the works.</p> <p>Inspection of the footing to ensure that the footings are stable and adequate.</p> <p>Vertical monitoring movement by standard optical equipment</p> <p>Lateral movement between walls by laser measurements</p>	<p>New basements greater than 2.5m and shallower than 4m Deep in gravels</p> <p>Basements up to 4.5m deep in clays</p> <p>Underpinning works to grade I listed building</p>			

- Monitoring of Existing cracks
- Monitoring of movement
- Reporting
- Trigger Levels using a RED AMBER GREEN System

Recommend levels are

Movement	CATEGORY	ACTION
0mm-5mm	Green	No action required
5mm-12mm	AMBER	Crack Monitoring: Carry out a local structural review; Preparation for the implementation of remedial measures should be required.
>12mm	RED	Crack Monitoring: Implement structural support as required; Cease works with the exception of necessary works for the safety and stability of the structure and personnel; Review monitoring data and implement revised method of works


Basement Design & Construction Impacts		
Foundation type	<p>Reinforced concrete cantilevered retaining walls</p> <p>The designs for the retaining walls have been calculated using software designed by TEDDS. The software is specifically designed for retaining walls and ensures the design is kept to a limit to prevent damage to the adjacent property.</p> <p>The overall stability of the walls are design using K_a & K_p values, while the design of the wall uses K_o values. This approach minimise the level of movement from the concrete affecting the adjacent properties.</p> <p>The Investigations have highlight that water is a present. The walls are designed to cope with the hydrostatic pressure. The water table was low. The design of the walls however considers the long term items. It is possible that a water main may break causing local high water table. To account for this the wall is designed for water 1m from the top of the wall.</p> <p>The Design also considers floatation as a risk. The design of has considered the weight of the building and the uplift forces from the water. The weight of the building is greater than the uplift resulting in a stable structure.</p>	
Roads	<p>The basement must be designed for</p> <p>Yes. Site is within 5m of the footpath/alleyway and the road surface is further than 5m from the front lightwell.</p> <p style="margin-left: 40px;">Highways loading allow: 10kN/m² if within 45° of road 100kN point loads if under road or with in 1.5m 5kN/m² if within 45° of Pavement Garden Surcharge 2.5kN/m² Surcharge for adjacent property 1.5kN/m² + 4kN/m² for concrete ground bearing slab</p>	
Intended use of structure and user requirements	Family/domestic use	
Loading Requirements (EC1-1)	UDL kN/m ²	Concentrated Loads kN
	Domestic Single Dwellings	1.5 2.0

	<p>The basement does not line within a 45° angle of the highway. Therefore Highways HA loading is not required to be applied.</p>						
Part A3 Progressive collapse	<p>Number of Storeys 4</p> <p>Is the Building Multi Occupancy? No</p> <table border="1" style="width: 100%;"> <tr> <td style="background-color: #4F81BD; color: white;">Class 1</td> <td>Single occupancy houses not exceeding 4 storeys</td> </tr> </table>	Class 1	Single occupancy houses not exceeding 4 storeys				
Class 1	Single occupancy houses not exceeding 4 storeys						
	<p>To NHBC guidance compliance is only required to other floors if a material change of use occurs to the property.</p> <table border="1" style="width: 100%;"> <tr> <td>Initial Building Class</td> <td>1</td> </tr> <tr> <td>Proposed Building Class</td> <td>1</td> </tr> <tr> <td>If class has changed material change has occurred</td> <td>No</td> </tr> </table> <div style="text-align: center;">  <p>3 storey over basement</p> </div>	Initial Building Class	1	Proposed Building Class	1	If class has changed material change has occurred	No
Initial Building Class	1						
Proposed Building Class	1						
If class has changed material change has occurred	No						
Lateral Stability							
Exposure and wind loading conditions	<p>Basic wind speed $V_b = 21$ m/s to EC1-2</p> <p>Topography not considered significant.</p>						
Stability Design	<p>The cantilevered walls are suitable to carry the lateral loading applied from above</p>						
Lateral Actions	<p>The soil loads apply a lateral load on the retaining walls.</p> <p>Hydrostatic pressure will be applied to the wall</p> <p>Imposed loading will surcharge the wall.</p>						
Retained soil Parameters	<p>Design overall stability to K_a & K_p values. Lateral movement necessary to achieve K_a mobilisation is height/500 (from Tomlinson). This is tighter than the deflection limits of the concrete wall.</p>						

<p>Water Table</p>	<p>Has a soil investigation been carried out Yes</p> <p><u>Known water table from boreholes</u></p> <p>Design temporary condition for water table level, If deeper than basement ignore</p> <p>Design Permanent condition for water table level: If deeper than existing, design reinforcement for water table at full basement depth to allow for local failure of water mains, drainage and storm water.</p> <p>Global uplift forces <u>can</u> be ignored when water table lower than basement. BS8102 only indicates guidance.</p>
<p>Drainage and Damp Waterproofing</p>	<p>Assumed that drainage and damp proofing is by others: Details are not provided within our brief.</p> <p>It is recommended that a water proofing specialist is employed to ensure all the water proofing requirements are met. Croft structural engineers are not the waterproofing designer nor act as the structural waterproof designer.</p> <p>Croft are not the structural waterproofer. The waterproofing specialist must name who is their structural waterproofer. The Structural waterproofer must inspect the structural details and confirm that are happy with the robustness.</p> <p>Due to the construction nature of the segmental basement it is not possible to water proof the joints. All water proofing must be made by the waterproofing specialist. They should make review of our details and recommend to us if water bars and stops are necessary.</p> <p>The waterproof design must not assume that the structure is watertight. To help reduce water floor through joints in the segmental pins all faces should be;</p> <ul style="list-style-type: none"> • Cleaned of all debris and detritus • Faces between pins should be needle hammered to improve key • All pipe work and other penetrations should have puddle flanges or hydrophilic strips
<p>Localised Dewatering</p>	<p>Localised dewater to pins may be necessary.</p> <p>Some engineers may raise the theoretical questions about pumping of water causing localised settlement. We believe that this argument is a red herring when applied to single storey basements and our reason for stating this is:</p> <ul style="list-style-type: none"> • The water table in the area is variable, • The water level naturally rises and falls over time and does not lead to subsidence • The water table has naturally been rising and falling for over the last 20,000 years, any fines that will have been removed from the soil would have done so already. • If the water table rises and falls naturally why does this not cause subsidence due to fine removals every year? It does not because

	<p>the soil has been soil is naturally consolidated by the rise and fall of the water table in the area.</p> <ul style="list-style-type: none"> • The effect of local pumping for small excavations will not affect the local area. • There is only a risk of subsidence from large scale pumping of soil which lowers the water table below is natural lowest level.
<p>Temporary Works</p>	<p>Walls are designed to be temporarily stable. Temporary propping details will be required for the ground and soil and this must be provided by the contractor. Their details should be forwarded to Croft Structural Engineers.</p> <p>Particular attention should be paid to the point loads from above.</p> <p>Critical areas where point loads are present from above</p> <ul style="list-style-type: none"> Cross wall Chimney Stack Door openings
<p>Geological Assessment of Land Stability</p>	<p>Has the retaining wall design been assessed by a Chartered Geological Engineer?</p> <p>Yes inspected see supplementary report.</p>

Retaining Wall Calculation



Reference	General Loadings			
			<u>Cavity Walls</u>	
	<u>Sloped Roof</u>		100 Facing Brick =	2.2
	Slate =	0.6 kN/m ²	100 Block (16kN/m3)=	1.6
	Battens =	0.02	Plaster & Skim =	0.18
	Rafers	0.1125	Dead Load =	3.98 kN/m2
	Felt =	0.02		
	Insulation =	0.02		
	Plaster=	0.18	<u>Internal Walls</u>	
		0.9525 kN/m2	100 Block (20kN/m3)=	2
	Roof Angle =	25 deg	Plaster & Skim =	0.36
	Plan Dead load =	1.051 kN/m2	Dead Load =	2.36 kN/m2
	Live Load =	0.6 kN/m2	<u>Existing Internal Walls</u>	
			100 Brick (20kN/m3)=	2.1
			Plaster & Skim =	0.36
			Dead Load =	2.46 kN/m2
	<u>Flat Roof</u>			
	20mm Asphalt =	0.46		
	Felt underlay =	0.02	<u>Timber Floors</u>	
	insulation =	0.04	18mm Ply	0.15
	Ply Sheeting =	0.1	Joists 50x225@400 =	0.16875
	Firing =	0.1	100 Insulation =	0.05
	of joists 50x200@400 =	0.15	Plaster & Skim =	0.18
	Plaster & Skim =	0.18	Dead Load =	0.54875 kN/m2
	Plan Dead load =	1.05 kN/m2	Live Load =	1.5 kN/m2
	Live Load =	0.75 kN/m2	<u>Terrace Floor</u>	
			Promonade Tiles =	0.4
	<u>Mansard Roof</u>		20mm Asphalt =	0.46
	Slate Tiles =	0.4	Felt underlay =	0.02
	Battens =	0.02	insulation =	0.04
	Ply Sheeting =	0.125	Ply Sheeting =	0.1
	Rafters =	0.125	Firing =	0.1
	100 Insulation =	0.06	Roof joists 50x200@400 =	0.175
	plaster & Skim =	0.18	Plaster & Skim =	0.18
	Felt =	0.02	Dead Load =	1.475 kN/m2
		0.93	Live Load =	1.5 kN/m2
			<u>Ceiling</u>	
	Roof Angle =	45 deg	50x100 Joists =	0.075
	Plan Dead load =	1.316 kN/m2	100 Insulation =	0.06
	Live Load =	0.3 kN/m2	Plaster & Skim =	0.18
			Dead Load =	0.315 kN/m2
			Live Load =	0.25 kN/m2
	<u>Precast Floor on Steel</u>			
	200PC Floor units =	3.6	Table 3 Live Load Reduction	
	60 Screed =	1.2	Area	0 0%
	Finishes =	0.1		50 5%
	Steelwork =	0.6		100 10%
	Dead Load =	5.5 kN/m2		150 15%
	Live Load =	3 kN/m2		200 20%
			Floors	1 0%
				2 10%
				3 20%
				4 30%
				5 to 10 40%

PILED WALL 1 (TEMPORARY CASE)

Location	Area			Type	L	Load kN/m ²	Load kN			
	L	W	m ²				Dead	%	Live	Total
pile wall 1										
roof DL	4.0	1.0	4.0	g _k		1.05	4.2			
roof LL				q _k		0.75			3.0	
loft DL	4.0	1.0	4.0	g _k		0.63	2.5			
loft DL				q _k		1.50			6.0	
2nd fl DL	4.0	1.0	4.0	g _k		4.62	18.5			
2nd fl LL				q _k		1.50			6.0	
2nd fl partitions	3.0	1.0	3.0	g _k		2.60	7.8			
1st fl DL	4.0	1.0	4.0	g _k		4.62	18.5			
1st fl LL				q _k		1.50			6.0	
1st fl partitions	3.0	1.0	3.0	g _k		2.60	7.8			
ground fl DL	4.0	1.0	4.0	g _k		4.62	18.5			
ground fl LL				q _k		1.50			6.0	
grd fl partitions	3.0	1.0	3.0	g _k		2.60	7.8			
walls	9.0	1.0	9.0	g _k		10.00	90.0			
							175.6	kN/m	27.0	kN/m

RETAINING WALL ANALYSIS & DESIGN (BS8002)


Loadings

Dead load DL=176kN/m

Live load LL=27kN/m

RETAINING WALL ANALYSIS (BS 8002:1994)

TEDDS calculation version 1.2.01.06



Wall details

Retaining wall type

Cantilever

Height of wall stem

$h_{stem} = 3600$ mm

Wall stem thickness

$t_{wall} = 400$ mm

Length of toe

$l_{toe} = 1700$ mm

Length of heel

$l_{heel} = 0$ mm

Overall length of base

$l_{base} = 2100$ mm

Base thickness

$t_{base} = 400$ mm

Height of retaining wall

$h_{wall} = 4000$ mm

Depth of downstand

$d_{ds} = 0$ mm

Thickness of downstand

$t_{ds} = 400$ mm

Position of downstand

$l_{ds} = 1500$ mm

Depth of cover in front of wall

$d_{cover} = 0$ mm

Unplanned excavation depth

$d_{exc} = 0$ mm

Height of ground water

$h_{water} = 0$ mm

Density of water

$\gamma_{water} = 9.81$ kN/m³

Density of wall construction

$\gamma_{wall} = 23.6$ kN/m³

Density of base construction

$\gamma_{base} = 23.6$ kN/m³

Angle of soil surface

$\beta = 0.0$ deg

Effective height at back of wall

$h_{eff} = 4000$ mm

Mobilisation factor

$M = 1.5$

Moist density

$\gamma_m = 18.0$ kN/m³

Saturated density

$\gamma_s = 21.0$ kN/m³

Design shear strength

$\phi' = 24.2$ deg

Angle of wall friction

$\delta = 0.0$ deg

Design shear strength

$\phi'_b = 24.2$ deg

Design base friction

$\delta_b = 18.6$ deg

Moist density

$\gamma_{mb} = 18.0$ kN/m³

Allowable bearing

$P_{bearing} = 130$ kN/m²

Using Coulomb theory

Active pressure

$K_a = 0.419$

Passive pressure

$K_p = 4.187$

At-rest pressure

$K_0 = 0.590$

Loading details

Surcharge load

Surcharge = 10.0 kN/m²

Vertical dead load

$W_{dead} = 176.0$ kN/m

Vertical live load

$W_{live} = 27.0$ kN/m

Horizontal dead load

$F_{dead} = 0.0$ kN/m

Horizontal live load


$F_{live} = 0.0$ kN/m

Position of vertical load

$l_{load} = 1800$ mm

Height of horizontal load

$h_{load} = 0$ mm



Loads shown in kN/m, pressures shown in kN/m²

Calculate propping force

Propping force $F_{prop} = 0.0$ kN/m

Check bearing pressure

Total vertical reaction $R = 256.8$ kN/m

Distance to reaction $X_{bar} = 1050$ mm

Eccentricity of reaction $e = 0$ mm

Reaction acts within middle third of base

Bearing pressure at toe $p_{toe} = 122.3$ kN/m²

Bearing pressure at heel $p_{heel} = 122.3$ kN/m²


PASS - Maximum bearing pressure is less than allowable bearing pressure

Calculate propping forces to top and base of wall

Propping force to top of wall $F_{prop_top} = -4.921$ kN/m

Propping force to base of wall $F_{prop_base} = 4.921$ kN/m

kN/m



Design of retaining wall stem

Shear at base of stem $V_{stem} = 96.1$ kN/m Moment at base of stem $M_{stem} = 69.5$ kNm/m
Compression reinforcement is not required

Check wall stem in bending

Reinforcement provided **12 mm dia.bars @ 200 mm centres**
 Area required $A_{s_stem_req} = 520.0$ mm²/m Area provided $A_{s_stem_prov} = 565$ mm²/m

PASS - Reinforcement provided at the retaining wall stem is adequate

Check shear resistance at wall stem

Design shear stress $V_{stem} = 0.264$ N/mm² Allowable shear stress $V_{adm} = 4.733$ N/mm²
PASS - Design shear stress is less than maximum shear stress

Concrete shear stress $V_{c_stem} = 0.428$ N/mm²
 $V_{stem} < V_{c_stem}$ - No shear reinforcement required

Design of retaining wall at mid height

Moment at mid height $M_{wall} = 31.4$ kNm/m
Compression reinforcement is not required


Reinforcement provided **12 mm dia.bars @ 200 mm centres**
 Area required $A_{s_wall_req} = 520.0$ mm²/m Area provided $A_{s_wall_prov} = 565$ mm²/m

PASS - Reinforcement provided to the retaining wall at mid height is adequate

Check retaining wall deflection

Max span/depth ratio $ratio_{max} = 30.94$ Actual span/depth ratio $ratio_{act} = 9.89$
PASS - Span to depth ratio is acceptable

Indicative retaining wall reinforcement diagram



Toe bars - 16 mm dia. @ 100 mm centres - (2011 mm²/m)

Wall bars - 12 mm dia. @ 200 mm centres - (565 mm²/m)


Stem bars - 12 mm dia. @ 200 mm centres - (565 mm²/m)

PILED WALL 1 (PERMANENT CASE)

RETAINING WALL ANALYSIS & DESIGN (BS8002)

RETAINING WALL ANALYSIS (BS 8002:1994)

TEDDS calculation version 1.2.01.06



Wall details

Retaining wall type

Cantilever

Height of wall stem

$h_{\text{stem}} = 3600$ mm

Wall stem thickness

$t_{\text{wall}} = 400$ mm

Length of toe

$l_{\text{toe}} = 1700$ mm

Length of heel

$l_{\text{heel}} = 200$ mm

Overall length of base

$l_{\text{base}} = 2300$ mm

Base thickness

$t_{\text{base}} = 400$ mm

Height of retaining wall

$h_{\text{wall}} = 4000$ mm

Thickness of downstand

$t_{\text{ds}} = 400$ mm

Depth of downstand

$d_{\text{ds}} = 0$ mm

Unplanned excavation depth

$d_{\text{exc}} = 0$ mm

Position of downstand

$l_{\text{ds}} = 1200$ mm

Density of water

$\gamma_{\text{water}} = 9.81$ kN/m³

Depth of cover in front of wall

$d_{\text{cover}} = 0$ mm

Density of base construction

$\gamma_{\text{base}} = 23.6$ kN/m³

Height of ground water

$h_{\text{water}} = 4000$ mm

Effective height at back of wall

$h_{\text{eff}} = 4000$ mm

Density of wall construction

$\gamma_{\text{wall}} = 23.6$ kN/m³

Angle of soil surface

$\beta = 0.0$ deg

Saturated density

$\gamma_s = 21.0$ kN/m³

Mobilisation factor

$M = 1.5$

Angle of wall friction

$\delta = 0.0$ deg

Moist density

$\gamma_m = 18.0$ kN/m³

Design base friction

$\delta_b = 18.6$ deg

Design shear strength

$\phi'_b = 24.2$ deg

Allowable bearing

$P_{\text{bearing}} = 130$ kN/m²

Design shear strength

$\phi'_b = 24.2$ deg

Moist density

$\gamma_{\text{mb}} = 18.0$ kN/m³

Using Coulomb theory

Active pressure

$K_a = 0.419$

Passive pressure


$K_p = 4.187$

At-rest pressure

$K_0 = 0.590$

Loading details

Surcharge load	Surcharge = 10.0 kN/m ²	Vertical live load	$W_{live} = 27.0$ kN/m
Vertical dead load	$W_{dead} = 176.0$ kN/m	Horizontal live load	$F_{live} = 0.0$ kN/m
Horizontal dead load	$F_{dead} = 0.0$ kN/m	Height of horizontal load	$h_{load} = 0$ mm
Position of vertical load	$l_{load} = 1700$ mm		



Loads shown in kN/m, pressures shown in kN/m²

Calculate propping force

Propping force $F_{prop} = 43.9$ kN/m

Check bearing pressure

Total vertical reaction $R = 275.8$ kN/m

Distance to reaction $X_{bar} = 1150$ mm

Eccentricity of reaction $e = 0$ mm

Reaction acts within middle third of base

Bearing pressure at toe $p_{toe} = 119.9$ kN/m²

Bearing pressure at heel $p_{heel} = 119.9$ kN/m²

PASS - Maximum bearing pressure is less than allowable bearing pressure

Calculate propping forces to top and base of wall

Propping force to top of wall $F_{prop_top} = 19.600$ kN/m

Propping force to base of wall $F_{prop_base} = 24.310$ kN/m

kN/m

RETAINING WALL DESIGN (BS 8002:1994)

TEDDS calculation version 1.2.01.06

Ultimate limit state load factors

Dead load factor $\gamma_{f,d} = 1.4$ Live load factor $\gamma_{f,l} = 1.6$
Earth pressure factor $\gamma_{f,e} = 1.4$

Calculate propping force

Propping force $F_{prop} = 43.9$ kN/m
Calculate propping forces to top and base of wall
Propping force to top of wall $F_{prop_top_f} = 21.216$ kN/m Propping force to base of wall $F_{prop_base_f} = 76.087$ kN/m


Design of reinforced concrete retaining wall toe (BS 8002:1994)

Material properties

Strength of concrete $f_{cu} = 35$ N/mm² Strength of reinforcement $f_y = 500$ N/mm²

Base details

Minimum reinforcement $k = 0.13$ % Cover in toe $C_{toe} = 30$ mm



Design of retaining wall toe

Shear at heel $V_{toe} = 267.2$ kN/m Moment at heel $M_{toe} = 283.7$ kNm/m
Compression reinforcement is not required

Check toe in bending

Reinforcement provided **16 mm dia.bars @ 100 mm centres**
Area required $A_{s_toe_req} = 1933.8$ mm²/m Area provided $A_{s_toe_prov} = 2011$ mm²/m

PASS - Reinforcement provided at the retaining wall toe is adequate

Check shear resistance at toe

Design shear stress $V_{toe} = 0.734$ N/mm² Allowable shear stress $V_{adm} = 4.733$ N/mm²
PASS - Design shear stress is less than maximum shear stress

Concrete shear stress $V_{c_toe} = 0.428$ N/mm²
 $V_{toe} > V_{c_toe}$ - Shear reinforcement required

Design of reinforced concrete retaining wall heel (BS 8002:1994)

Material properties

Strength of concrete $f_{cu} = 35$ N/mm² Strength of reinforcement $f_y = 500$ N/mm²

Base details

Minimum reinforcement $k = 0.13$ % Cover in heel $C_{heel} = 30$ mm

As the moment is negative the design of the retaining wall heel is beyond the scope of this calculation


Design of reinforced concrete retaining wall stem (BS 8002:1994)

Material properties

Strength of concrete $f_{cu} = 35 \text{ N/mm}^2$ Strength of reinforcement $f_y = 500 \text{ N/mm}^2$

Wall details

Minimum reinforcement $k = 0.13 \%$
Cover in stem $C_{stem} = 30 \text{ mm}$ Cover in wall $C_{wall} = 30 \text{ mm}$
 $\leftarrow 150 \rightarrow$



Design of retaining wall stem

Shear at base of stem $V_{stem} = 140.4 \text{ kN/m}$ Moment at base of stem $M_{stem} = 91.6 \text{ kNm/m}$
Compression reinforcement is not required

Check wall stem in bending

Reinforcement provided **12 mm dia.bars @ 150 mm centres**
Area required $A_{s_stem_req} = 608.9 \text{ mm}^2/\text{m}$ Area provided $A_{s_stem_prov} = 754 \text{ mm}^2/\text{m}$

PASS - Reinforcement provided at the retaining wall stem is adequate

Check shear resistance at wall stem

Design shear stress $V_{stem} = 0.386 \text{ N/mm}^2$ Allowable shear stress $V_{adm} = 4.733 \text{ N/mm}^2$
PASS - Design shear stress is less than maximum shear stress
Concrete shear stress $V_{c_stem} = 0.428 \text{ N/mm}^2$
 $V_{stem} < V_{c_stem}$ - No shear reinforcement required

Design of retaining wall at mid height

Moment at mid height $M_{wall} = 42.8 \text{ kNm/m}$
Compression reinforcement is not required


Reinforcement provided **12 mm dia.bars @ 150 mm centres**
Area required $A_{s_wall_req} = 520.0 \text{ mm}^2/\text{m}$ Area provided $A_{s_wall_prov} = 754 \text{ mm}^2/\text{m}$

PASS - Reinforcement provided to the retaining wall at mid height is adequate

Check retaining wall deflection

Max span/depth ratio $ratio_{max} = 32.77$ Actual span/depth ratio $ratio_{act} = 9.89$
PASS - Span to depth ratio is acceptable

Indicative retaining wall reinforcement diagram



Toe bars - 16 mm dia. @ 100 mm centres - (2011 mm²/m)

The design of the retaining wall heel is beyond the scope of this calculation!

Wall bars - 12 mm dia. @ 150 mm centres - (754 mm²/m)

Stem bars - 12 mm dia. @ 150 mm centres - (754 mm²/m)

CAPPING BEAM FOR PILED WALL 1


Propping force = 43.9kN/m

RC BEAM ANALYSIS & DESIGN (EN1992)

RC BEAM ANALYSIS & DESIGN (EN1992-1)

In accordance with UK national annex

TEDDS calculation version 2.1.15



Support conditions

Support A	Vertically restrained
	Rotationally free
Support B	Vertically restrained
	Rotationally free

Applied loading

Permanent self weight of beam $\times 1$
 Permanent full UDL 45 kN/m

Load combinations


Load combination 1	Support A	Permanent $\times 1.35$ Variable $\times 1.50$
	Span 1	Permanent $\times 1.35$ Variable $\times 1.50$
	Support B	Permanent $\times 1.35$

Variable $\times 1.50$

Analysis results

Maximum moment support A	$M_{A_max} = 0 \text{ kNm}$	$M_{A_red} = 0 \text{ kNm}$
Maximum moment span 1 at 1500 mm	$M_{S1_max} = 78 \text{ kNm}$	$M_{S1_red} = 78 \text{ kNm}$
Maximum moment support B	$M_{B_max} = 0 \text{ kNm}$	$M_{B_red} = 0 \text{ kNm}$
Maximum shear support A	$V_{A_max} = 104 \text{ kN}$	$V_{A_red} = 104 \text{ kN}$
Maximum shear support A span 1 at 449 mm	$V_{A_s1_max} = 73 \text{ kN}$	$V_{A_s1_red} = 73 \text{ kN}$
Maximum shear support B	$V_{B_max} = -104 \text{ kN}$	$V_{B_red} = -104 \text{ kN}$
Maximum shear support B span 1 at 2551 mm	$V_{B_s1_max} = -73 \text{ kN}$	$V_{B_s1_red} = -73 \text{ kN}$
Maximum reaction at support A	$R_A = 104 \text{ kN}$	
Maximum reaction at support B	$R_B = 104 \text{ kN}$	

Rectangular section details



Concrete details (Table 3.1 - Strength and deformation characteristics for concrete)

Concrete strength class	C28/35	Char.comp.cube strength	$f_{ck,cube} = 35 \text{ N/mm}^2$
Char.comp.cylinder strength	$f_{ck} = 28 \text{ N/mm}^2$	Mean axial tensile strength	$f_{ctm} = 2.8 \text{ N/mm}^2$
Mean comp.cylinder strength	$f_{cm} = 36 \text{ N/mm}^2$	Maximum aggregate size	$h_{agg} = 20 \text{ mm}$
Secant modulus of elasticity	$E_{cm} = 32308 \text{ N/mm}^2$	Comp.strength coefficient	$\alpha_{cc} = 0.85$
Partial factor for concrete	$\gamma_C = 1.50$		
Design compressive strength	$f_{cd} = 15.9 \text{ N/mm}^2$		


Reinforcement details

Characteristic yield strength	$f_{yk} = 500 \text{ N/mm}^2$	Partial factor for reinforcement	$\gamma_S = 1.15$
Design yield strength	$f_{yd} = 435 \text{ N/mm}^2$		

Nominal cover to reinforcement

Nominal cover to top	$c_{nom_t} = 35 \text{ mm}$	Nominal cover to bottom	$c_{nom_b} = 35 \text{ mm}$
Nominal cover to sides	$c_{nom_s} = 35 \text{ mm}$		

Support A



Rectangular section in flexure (Section 6.1) -

Design bending moment $M = 19 \text{ kNm}$ $K = 0.007$ $K' = 0.207$
 $K' > K$ - No compression reinforcement is required

Tens.reinforcement required $A_{s,req} = 105 \text{ mm}^2$
Tens.reinforcement provided $4 \times 16\phi$ bars Tens.reinforcement provided $A_{s,prov} = 804 \text{ mm}^2$
Min area of reinforcement $A_{s,min} = 323 \text{ mm}^2$ Max area of reinforcement $A_{s,max} = 10000 \text{ mm}^2$

PASS - Area of reinforcement provided is greater than area of reinforcement required

Minimum bottom reinforcement at supports (cl.9.2.1.4(1))

Adj span reinforcement $A_{s,span} = 1257 \text{ mm}^2$ Min btm reinforcement reqd $A_{s2,min} = 314 \text{ mm}^2$
Btm reinforcement provided $4 \times 20\phi$ bars Btm reinforcement provided $A_{s2,prov} = 1257 \text{ mm}^2$

PASS - Area of reinforcement provided is greater than minimum area of reinforcement required

Rectangular section in shear (Section 6.2)

Des.shear force at support support $V_{Ed,max} = 104 \text{ kN}$ Max.design shear force
 $V_{Rd,max} = 901 \text{ kN}$

PASS - Design shear force at support is less than maximum design shear force

Des.shear span 1 at 449 mm $V_{Ed} = 73 \text{ kN}$
Shear reinforcement required $A_{sv,req} = 157 \text{ mm}^2/\text{m}$ Min shear reinforcement $A_{sv,min} = 423 \text{ mm}^2/\text{m}$
Shear reinforcement provided $2 \times 8\phi$ legs at 200 c/c Shear reinforcement provided $A_{sv,prov} = 503 \text{ mm}^2/\text{m}$

PASS - Area of shear reinforcement provided exceeds minimum required

Max longitudinal spacing $s_{vl,max} = 337 \text{ mm}$

PASS - Longitudinal spacing of shear reinforcement provided is less than maximum

Crack control (Section 7.3)

Maximum crack width $w_k = 0.3 \text{ mm}$ Modulus of elasticity reinf $E_s = 200000 \text{ N/mm}^2$
Mean conc. tensile strength $f_{ct,eff} = f_{ctm} = 2.8 \text{ N/mm}^2$ Stress distribution coefficient $k_c = 0.4$
Self-equilibrating stress coef $k = 0.86$ Actual tension bar spacing $s_{bar} = 133 \text{ mm}$
Max stress permitted (T.7.3N) $\sigma_s = 294 \text{ N/mm}^2$ Conc/steel mod of elast. ratio $\alpha_{cr} = 6.19$
Distance of the ENA $y = 247 \text{ mm}$ Area of conc in tensile zone $A_{ct} = 123366 \text{ mm}^2$
Min area of reinf reqd (exp.7.1) $A_{sc,min} = 399 \text{ mm}^2$

PASS - Area of tension reinforcement provided exceeds minimum required for crack control

Quasi-perm value $\psi_2 = 0.30$ Quasi-perm limit state moment $M_{QP} = 0 \text{ kNm}$
Permanent load ratio $R_{PL} = 0.00$ Service stress in reinf $\sigma_{sr} = 0 \text{ N/mm}^2$
Max bar spacing (Table 7.3N) $s_{bar,max} = 300 \text{ mm}$


PASS - Maximum bar spacing exceeds actual bar spacing for crack control

Minimum bar spacing

Minimum bottom bar spacing $s_{bot,min} = 131 \text{ mm}$ Min allowable bottom spacing $s_{bar_bot,min} = 45 \text{ mm}$
Minimum top bar spacing $s_{top,min} = 133 \text{ mm}$ Min allowable top spacing $s_{bar_top,min} = 45 \text{ mm}$

PASS - Actual bar spacing exceeds minimum allowable

Mid span 1



Rectangular section in flexure (Section 6.1) - - Positive midspan moment

Design bending moment $M = 78 \text{ kNm}$ $K = 0.028$ $K' = 0.207$
 $K' > K$ - No compression reinforcement is required

Tens.reinforcement required $A_{s,req} = 422 \text{ mm}^2$
Tens.reinforcement provided $4 \times 20\phi$ bars Tens.reinforcement provided $A_{s,prov} = 1257 \text{ mm}^2$
Min area of reinforcement $A_{s,min} = 321 \text{ mm}^2$ Max area of reinforcement $A_{s,max} = 10000 \text{ mm}^2$

PASS - Area of reinforcement provided is greater than area of reinforcement required

Rectangular section in shear (Section 6.2)

Shear reinforcement provided $2 \times 8\phi$ legs at 150 c/c Shear reinforcement provided $A_{sv,prov} = 670 \text{ mm}^2/\text{m}$

Min shear reinforcement $A_{sv,min} = 423 \text{ mm}^2/\text{m}$

PASS - Area of shear reinforcement provided exceeds minimum required

Max longitudinal spacing $s_{vl,max} = 335 \text{ mm}$

PASS - Longitudinal spacing of shear reinforcement provided is less than maximum

Crack control (Section 7.3)

Maximum crack width $w_k = 0.3 \text{ mm}$

Modulus of elasticity reinf $E_s = 200000 \text{ N/mm}^2$

Mean conc. tensile strength $f_{ct,eff} = f_{ctm} = 2.8 \text{ N/mm}^2$

Stress distribution coefficient $k_c = 0.4$

Self-equilibrating stress coef $k = 0.86$

Actual tension bar spacing $s_{bar} = 131 \text{ mm}$

Max stress permitted (T.7.3N) $\sigma_s = 295 \text{ N/mm}^2$

Conc/steel mod of elast. ratio $\alpha_{cr} = 6.19$

Distance of the ENA $y = 245 \text{ mm}$

Area of conc in tensile zone $A_{ct} = 122496 \text{ mm}^2$

Min area of reinf reqd (exp.7.1) $A_{sc,min} = 395 \text{ mm}^2$

PASS - Area of tension reinforcement provided exceeds minimum required for crack control

Quasi-perm value $\psi_2 = 0.30$

Quasi-perm limit state moment $M_{QP} = 58 \text{ kNm}$

Permanent load ratio $R_{PL} = 0.74$

Service stress in reinf $\sigma_{sr} = 108 \text{ N/mm}^2$

Max bar spacing (Table 7.3N) $s_{bar,max} = 300 \text{ mm}$

PASS - Maximum bar spacing exceeds actual bar spacing for crack control

Minimum bar spacing

Minimum bottom bar spacing $s_{bot,min} = 131 \text{ mm}$

Min allowable bottom spacing $s_{bar_bot,min} = 45 \text{ mm}$

Minimum top bar spacing $s_{top,min} = 133 \text{ mm}$

Min allowable top spacing $s_{bar_top,min} = 45 \text{ mm}$

PASS - Actual bar spacing exceeds minimum allowable


Deflection control (Section 7.4)

Allowable span to depth ratio $span_to_depth_{allow} = 40.0$
 $= 6.7$

Actual span to depth ratio $span_to_depth_{actual}$

PASS - Actual span to depth ratio is within the allowable limit

Support B



Rectangular section in flexure (Section 6.1) -

Design bending moment $M = 19 \text{ kNm}$

$K = 0.007$

$K' = 0.207$

$K' > K$ - No compression reinforcement is required

Tens.reinforcement required $A_{s,req} = 105 \text{ mm}^2$

Tens.reinforcement provided $4 \times 16\phi$ bars

Tens.reinforcement provided $A_{s,prov} = 804 \text{ mm}^2$

Min area of reinforcement $A_{s,min} = 323 \text{ mm}^2$

Max area of reinforcement $A_{s,max} = 10000 \text{ mm}^2$

PASS - Area of reinforcement provided is greater than area of reinforcement required

Minimum bottom reinforcement at supports (cl.9.2.1.4(1))

Adj span reinforcement	$A_{s,span} = 1257 \text{ mm}^2$	Min btm reinforcement reqd	$A_{s2,min} = 314 \text{ mm}^2$
Btm reinforcement provided	$4 \times 20\phi$ bars	Btm reinforcement provided	$A_{s2,prov} = 1257 \text{ mm}^2$

PASS - Area of reinforcement provided is greater than minimum area of reinforcement required

Rectangular section in shear (Section 6.2)

Des.shear force at support support force	$V_{Rd,max} = 901 \text{ kN}$	$V_{Ed,max} = 104 \text{ kN}$	Max.design shear
--	-------------------------------	-------------------------------	------------------

PASS - Design shear force at support is less than maximum design shear force

Des.shear span 1 at 2551 mm	$V_{Ed} = 73 \text{ kN}$	Min shear reinforcement	$A_{sv,min} = 423 \text{ mm}^2/\text{m}$
Shear reinforcement required	$A_{sv,req} = 157 \text{ mm}^2/\text{m}$	Shear reinforcement provided	$A_{sv,prov} = 503 \text{ mm}^2/\text{m}$
Shear reinforcement provided	$2 \times 8\phi$ legs at 200 c/c		

PASS - Area of shear reinforcement provided exceeds minimum required

Max longitudinal spacing	$S_{vl,max} = 337 \text{ mm}$
--------------------------	-------------------------------

PASS - Longitudinal spacing of shear reinforcement provided is less than maximum

Crack control (Section 7.3)

Maximum crack width	$w_k = 0.3 \text{ mm}$	Modulus of elasticity reinf	$E_s = 200000 \text{ N/mm}^2$
Mean conc. tensile strength	$f_{ct,eff} = f_{ctm} = 2.8 \text{ N/mm}^2$	Stress distribution coefficient	$K_c = 0.4$
Self-equilibrating stress coef	$k = 0.86$	Actual tension bar spacing	$S_{bar} = 133 \text{ mm}$
Max stress permitted (T.7.3N)	$\sigma_s = 294 \text{ N/mm}^2$	Conc/steel mod of elast. ratio	$\alpha_{cr} = 6.19$
Distance of the ENA	$y = 247 \text{ mm}$	Area of conc in tensile zone	$A_{ct} = 123366 \text{ mm}^2$
Min area of reinf reqd (exp.7.1)	$A_{sc,min} = 399 \text{ mm}^2$		

PASS - Area of tension reinforcement provided exceeds minimum required for crack control

Quasi-perm value	$\psi_2 = 0.30$	Quasi-perm limit state moment	$M_{QP} = 0 \text{ kNm}$
Permanent load ratio	$R_{PL} = 0.00$	Service stress in reinf	$\sigma_{sr} = 0 \text{ N/mm}^2$
Max bar spacing (Table 7.3N)	$S_{bar,max} = 300 \text{ mm}$		

PASS - Maximum bar spacing exceeds actual bar spacing for crack control


Minimum bar spacing

Minimum bottom bar spacing	$S_{bot,min} = 131 \text{ mm}$	Min allowable bottom spacing	$S_{bar_bot,min} = 45 \text{ mm}$
Minimum top bar spacing	$S_{top,min} = 133 \text{ mm}$	Min allowable top spacing	$S_{bar_bot,min} = 45 \text{ mm}$

PASS - Actual bar spacing exceeds minimum allowable

PILED WALL 2 (TEMPORARY CASE)

Location	Area			Type	L	Load kN/m ²	Load kN			
	L	W	m ²				Dead	%	Live	Total
pile wall 2										
roof DL	4.0	1.0	4.0	g _k		1.05	4.2			
roof LL				q _k		0.75			3.0	
loft DL	4.0	1.0	4.0	g _k		0.63	2.5			
loft DL				q _k		1.50			6.0	
2nd fl DL	4.0	1.0	4.0	g _k		4.62	18.5			
2nd fl LL				q _k		1.50			6.0	
2nd fl partitions	3.0	1.0	3.0	g _k		2.60	7.8			
1st fl DL	4.0	1.0	4.0	g _k		4.62	18.5			
1st fl LL				q _k		1.50			6.0	
1st fl partitions	3.0	1.0	3.0	g _k		2.60	7.8			
ground fl DL	4.0	1.0	4.0	g _k		4.62	18.5			
ground fl LL				q _k		1.50			6.0	
grd fl partitions	3.0	1.0	3.0	g _k		2.60	7.8			
walls	9.0	1.0	9.0	g _k		10.00	90.0			
							175.6	kN/m	27.0	kN/m
37 greville road										
roof DL	2.0	1.0	2.0	g _k		1.05	2.1			
roof LL				q _k		0.75			1.5	
loft DL	2.0	1.0	2.0	g _k		0.63	1.3			
loft DL				q _k		1.50			3.0	
2nd fl DL	2.0	1.0	2.0	g _k		4.62	9.2			
2nd fl LL				q _k		1.50			3.0	
2nd fl partitions	3.0	1.0	3.0	g _k		2.60	7.8			
1st fl DL	2.0	1.0	2.0	g _k		4.62	9.2			
1st fl LL				q _k		1.50			3.0	
1st fl partitions	3.0	1.0	3.0	g _k		2.60	7.8			
ground fl DL	2.0	1.0	2.0	g _k		4.62	9.2			
ground fl LL				q _k		1.50			3.0	
grd fl partitions	3.0	1.0	3.0	g _k		2.60	7.8			
walls	9.0	1.0	9.0	g _k		10.00	90.0			
							144.5	kN/m	13.5	kN/m



37 Greville Road

$$\begin{aligned} \text{Total service load} &= 144 \text{ kN/m} + 14 \text{ kN/m} \\ &= 158 \text{ kN/m} \end{aligned}$$

Surcharge on 35 Greville Road

$$= \frac{158 \text{ kN/m}}{2.75 \text{ m}}$$

$$= 57 \text{ kN/m}^2$$

RETAINING WALL ANALYSIS & DESIGN (BS8002)

Loadings


Dead load DL=176kN/m

Live load LL=27kN/m

Surcharge from 37 Greville Road

RETAINING WALL ANALYSIS (BS 8002:1994)


TEDDS calculation version 1.2.01.06



Wall details

Retaining wall type	Cantilever	Wall stem thickness	$t_{wall} = 400$ mm
Height of wall stem	$h_{stem} = 3600$ mm	Length of heel	$l_{heel} = 200$ mm
Length of toe	$l_{toe} = 1700$ mm	Base thickness	$t_{base} = 400$ mm
Overall length of base	$l_{base} = 2300$ mm	Thickness of downstand	$t_{ds} = 400$ mm
Height of retaining wall	$h_{wall} = 4000$ mm	Unplanned excavation depth	$d_{exc} = 0$ mm
Depth of downstand	$d_{ds} = 0$ mm	Density of water	$\gamma_{water} = 9.81$ kN/m ³
Position of downstand	$l_{ds} = 1250$ mm	Density of base construction	$\gamma_{base} = 23.6$ kN/m ³
Depth of cover in front of wall	$d_{cover} = 0$ mm	Effective height at back of wall	$h_{eff} = 4000$ mm
Height of ground water	$h_{water} = 0$ mm	Saturated density	$\gamma_s = 21.0$ kN/m ³
Density of wall construction	$\gamma_{wall} = 23.6$ kN/m ³	Angle of wall friction	$\delta = 0.0$ deg
Angle of soil surface	$\beta = 0.0$ deg	Design base friction	$\delta_b = 18.6$ deg
Mobilisation factor	$M = 1.5$	Allowable bearing	$P_{bearing} = 130$ kN/m ²
Moist density	$\gamma_m = 18.0$ kN/m ³	Passive pressure	$K_p = 4.187$
Design shear strength	$\phi' = 24.2$ deg	Active pressure	$K_a = 0.419$
Design shear strength	$\phi'_b = 24.2$ deg	At-rest pressure	$K_0 = 0.590$
Moist density	$\gamma_{mb} = 18.0$ kN/m ³		
Using Coulomb theory			
Surcharge load	Surcharge = 57.0 kN/m ²	Vertical live load	$W_{live} = 27.0$ kN/m
Vertical dead load	$W_{dead} = 176.0$ kN/m	Horizontal live load	$F_{live} = 0.0$ kN/m
Horizontal dead load	$F_{dead} = 0.0$ kN/m		

Position of vertical load $l_{load} = 1700 \text{ mm}$ Height of horizontal load $h_{load} = 0 \text{ mm}$



Loads shown in kN/m, pressures shown in kN/m²

Calculate propping force

Propping force $F_{prop} = 67.6 \text{ kN/m}$
 Check bearing pressure
 Total vertical reaction $R = 283.1 \text{ kN/m}$
 Eccentricity of reaction $e = 0 \text{ mm}$

Distance to reaction $X_{bar} = 1150 \text{ mm}$

Reaction acts within middle third of base

Bearing pressure at toe $p_{toe} = 123.1 \text{ kN/m}^2$ Bearing pressure at heel $p_{heel} = 123.1 \text{ kN/m}^2$

PASS - Maximum bearing pressure is less than allowable bearing pressure

Calculate propping forces to top and base of wall

Propping force to top of wall $F_{prop_top} = 43.667 \text{ kN/m}$ Propping force to base of wall $F_{prop_base} = 23.972 \text{ kN/m}$

RETAINING WALL DESIGN (BS 8002:1994)

TEDDS calculation version 1.2.01.06

Ultimate limit state load factors

Dead load factor $\gamma_{f_d} = 1.4$ Live load factor $\gamma_{f_l} = 1.6$
Earth pressure factor $\gamma_{f_e} = 1.4$

Calculate propping force

Propping force $F_{prop} = 67.6$ kN/m
Calculate propping forces to top and base of wall
Propping force to top of wall $F_{prop_top_f} = 82.573$ kN/m Propping force to base of wall $F_{prop_base_f} = 128.378$ kN/m


Design of reinforced concrete retaining wall toe (BS 8002:1994)

Material properties

Strength of concrete $f_{cu} = 35$ N/mm² Strength of reinforcement $f_y = 500$ N/mm²

Base details

Minimum reinforcement $k = 0.13$ % Cover in toe $C_{toe} = 30$ mm



Design of retaining wall toe

Shear at heel $V_{toe} = 276.1$ kN/m Moment at heel $M_{toe} = 293.2$ kNm/m
Compression reinforcement is not required

Check toe in bending

Reinforcement provided **16 mm dia.bars @ 100 mm centres**
Area required $A_{s_toe_req} = 2003.8$ mm²/m Area provided $A_{s_toe_prov} = 2011$ mm²/m

PASS - Reinforcement provided at the retaining wall toe is adequate

Check shear resistance at toe

Design shear stress $V_{toe} = 0.759$ N/mm² Allowable shear stress $V_{adm} = 4.733$ N/mm²
PASS - Design shear stress is less than maximum shear stress

Concrete shear stress $V_{c_toe} = 0.490$ N/mm²
 $V_{toe} > V_{c_toe}$ - Shear reinforcement required

Design of reinforced concrete retaining wall heel (BS 8002:1994)

Material properties

Strength of concrete $f_{cu} = 35$ N/mm² Strength of reinforcement $f_y = 500$ N/mm²

Base details

Minimum reinforcement $k = 0.13$ % Cover in heel $C_{heel} = 30$ mm

As the moment is negative the design of the retaining wall heel is beyond the scope of this calculation


Design of reinforced concrete retaining wall stem (BS 8002:1994)

Material properties

Strength of concrete $f_{cu} = 35 \text{ N/mm}^2$ Strength of reinforcement $f_y = 500 \text{ N/mm}^2$

Wall details

Minimum reinforcement $k = 0.13 \%$
Cover in stem $C_{stem} = 30 \text{ mm}$ Cover in wall $C_{wall} = 30 \text{ mm}$

Design of retaining wall stem

Shear at base of stem $V_{stem} = 196.0 \text{ kN/m}$ Moment at base of stem $M_{stem} = 145.4 \text{ kNm/m}$

Compression reinforcement is not required

Check wall stem in bending

Reinforcement provided **12 mm dia.bars @ 100 mm centres**
Area required $A_{s_stem_req} = 966.5 \text{ mm}^2/\text{m}$ Area provided $A_{s_stem_prov} = 1131 \text{ mm}^2/\text{m}$

PASS - Reinforcement provided at the retaining wall stem is adequate

Check shear resistance at wall stem

Design shear stress $V_{stem} = 0.538 \text{ N/mm}^2$ Allowable shear stress $V_{adm} = 4.733 \text{ N/mm}^2$
PASS - Design shear stress is less than maximum shear stress

Concrete shear stress $V_{c_stem} = 0.490 \text{ N/mm}^2$

$V_{stem} > V_{c_stem}$ - Shear reinforcement required

Design of retaining wall at mid height

Moment at mid height $M_{wall} = 74.1 \text{ kNm/m}$

Compression reinforcement is not required

Reinforcement provided **12 mm dia.bars @ 150 mm centres**
Area required $A_{s_wall_req} = 520.0 \text{ mm}^2/\text{m}$ Area provided $A_{s_wall_prov} = 754 \text{ mm}^2/\text{m}$


PASS - Reinforcement provided to the retaining wall at mid height is adequate

Check retaining wall deflection

Max span/depth ratio $ratio_{max} = 27.03$ Actual span/depth ratio $ratio_{act} = 9.89$

PASS - Span to depth ratio is acceptable

Indicative retaining wall reinforcement diagram



Toe bars - 16 mm dia. @ 100 mm centres - (2011 mm²/m)

The design of the retaining wall heel is beyond the scope of this calculation!

Wall bars - 12 mm dia. @ 150 mm centres - (754 mm²/m)


Stem bars - 12 mm dia. @ 100 mm centres - (1131 mm²/m)

PILED WALL 2 (PERMANENT CASE)

RETAINING WALL ANALYSIS & DESIGN (BS8002)

RETAINING WALL ANALYSIS (BS 8002:1994)

TEDDS calculation version 1.2.01.06




Wall details

Retaining wall type	Cantilever	Wall stem thickness	$t_{\text{wall}} = 400 \text{ mm}$
Height of wall stem	$h_{\text{stem}} = 3600 \text{ mm}$	Length of heel	$l_{\text{heel}} = 200 \text{ mm}$
Length of toe	$l_{\text{toe}} = 1700 \text{ mm}$	Base thickness	$t_{\text{base}} = 400 \text{ mm}$
Overall length of base	$l_{\text{base}} = 2300 \text{ mm}$	Thickness of downstand	$t_{\text{ds}} = 400 \text{ mm}$
Height of retaining wall	$h_{\text{wall}} = 4000 \text{ mm}$	Unplanned excavation depth	$d_{\text{exc}} = 0 \text{ mm}$
Depth of downstand	$d_{\text{ds}} = 0 \text{ mm}$	Density of water	$\gamma_{\text{water}} = 9.81 \text{ kN/m}^3$
Position of downstand	$l_{\text{ds}} = 1200 \text{ mm}$	Density of base construction	$\gamma_{\text{base}} = 23.6 \text{ kN/m}^3$
Depth of cover in front of wall	$d_{\text{cover}} = 0 \text{ mm}$	Effective height at back of wall	$h_{\text{eff}} = 4000 \text{ mm}$
Height of ground water	$h_{\text{water}} = 4000 \text{ mm}$	Saturated density	$\gamma_s = 21.0 \text{ kN/m}^3$
Density of wall construction	$\gamma_{\text{wall}} = 23.6 \text{ kN/m}^3$	Angle of wall friction	$\delta = 0.0 \text{ deg}$
Angle of soil surface	$\beta = 0.0 \text{ deg}$	Design base friction	$\delta_b = 18.6 \text{ deg}$
Mobilisation factor	$M = 1.5$	Allowable bearing	$P_{\text{bearing}} = 130 \text{ kN/m}^2$
Moist density	$\gamma_m = 18.0 \text{ kN/m}^3$	Passive pressure	$K_p = 4.187$
Design shear strength	$\phi' = 24.2 \text{ deg}$		
Design shear strength	$\phi'_b = 24.2 \text{ deg}$		
Moist density	$\gamma_{\text{mb}} = 18.0 \text{ kN/m}^3$		
Using Coulomb theory			
Active pressure	$K_a = 0.419$		
At-rest pressure	$K_0 = 0.590$		

Loading details

Surcharge load	Surcharge = 57.0 kN/m ²	Vertical live load	$W_{live} = 27.0$ kN/m
Vertical dead load	$W_{dead} = 176.0$ kN/m	Horizontal live load	$F_{live} = 0.0$ kN/m
Horizontal dead load	$F_{dead} = 0.0$ kN/m	Height of horizontal load	$h_{load} = 0$ mm
Position of vertical load	$l_{load} = 1800$ mm		



Loads shown in kN/m, pressures shown in kN/m²

Calculate propping force

Propping force $F_{prop} = 122.6$ kN/m

Check bearing pressure

Total vertical reaction $R = 285.2$ kN/m

Distance to reaction $X_{bar} = 1150$ mm

Eccentricity of reaction $e = 0$ mm

Reaction acts within middle third of base

Bearing pressure at toe $p_{toe} = 124.0$ kN/m²

Bearing pressure at heel $p_{heel} = 124.0$ kN/m²

PASS - Maximum bearing pressure is less than allowable bearing pressure

Calculate propping forces to top and base of wall

Propping force to top of wall $F_{prop_top} = 55.083$ kN/m

Propping force to base of wall $F_{prop_base} = 67.508$ kN/m


Design of reinforced concrete retaining wall stem (BS 8002:1994)

Material properties

Strength of concrete $f_{cu} = 35 \text{ N/mm}^2$ Strength of reinforcement $f_y = 500 \text{ N/mm}^2$

Wall details

Minimum reinforcement $k = 0.13 \%$
Cover in stem $C_{stem} = 30 \text{ mm}$ Cover in wall $C_{wall} = 30 \text{ mm}$
 $\leftarrow 150 \rightarrow$



Design of retaining wall stem

Shear at base of stem $V_{stem} = 240.2 \text{ kN/m}$ Moment at base of stem $M_{stem} = 167.5 \text{ kNm/m}$

Compression reinforcement is not required

Check wall stem in bending

Reinforcement provided **16 mm dia.bars @ 150 mm centres**
Area required $A_{s_stem_req} = 1119.4 \text{ mm}^2/\text{m}$ Area provided $A_{s_stem_prov} = 1340 \text{ mm}^2/\text{m}$

PASS - Reinforcement provided at the retaining wall stem is adequate

Check shear resistance at wall stem

Design shear stress $V_{stem} = 0.664 \text{ N/mm}^2$ Allowable shear stress $V_{adm} = 4.733 \text{ N/mm}^2$
PASS - Design shear stress is less than maximum shear stress

Concrete shear stress $V_{c_stem} = 0.521 \text{ N/mm}^2$

$V_{stem} > V_{c_stem}$ - Shear reinforcement required

Design of retaining wall at mid height

Moment at mid height $M_{wall} = 85.5 \text{ kNm/m}$

Compression reinforcement is not required

Reinforcement provided **12 mm dia.bars @ 150 mm centres**
Area required $A_{s_wall_req} = 568.4 \text{ mm}^2/\text{m}$ Area provided $A_{s_wall_prov} = 754 \text{ mm}^2/\text{m}$


PASS - Reinforcement provided to the retaining wall at mid height is adequate

Check retaining wall deflection

Max span/depth ratio $ratio_{max} = 26.20$ Actual span/depth ratio $ratio_{act} = 9.94$

PASS - Span to depth ratio is acceptable

Indicative retaining wall reinforcement diagram



Toe bars - 20 mm dia. @ 100 mm centres - (3142 mm²/m)

The design of the retaining wall heel is beyond the scope of this calculation!

Wall bars - 12 mm dia. @ 150 mm centres - (754 mm²/m)

Stem bars - 16 mm dia. @ 150 mm centres - (1340 mm²/m)

CAPPING BEAM FOR PILED WALL 2


RC BEAM ANALYSIS & DESIGN (EN1992)

Prop force DL=122.6kN/m

RC BEAM ANALYSIS & DESIGN (EN1992-1)

In accordance with UK national annex

TEDDS calculation version 2.1.15



Support conditions

Support A

Vertically restrained

Rotationally free

Support B

Vertically restrained

Rotationally free

Applied loading

Permanent self weight of beam \times 1

Permanent full UDL 126 kN/m

Load combinations

Load combination 1

Support A

Permanent \times 1.35

Variable \times 1.50

Span 1

Permanent \times 1.35

Variable \times 1.50


Support B

Permanent × 1.35
Variable × 1.50

Analysis results

Maximum moment support A	$M_{A_max} = 0 \text{ kNm}$	$M_{A_red} = 0 \text{ kNm}$
Maximum moment span 1 at 1000 mm	$M_{s1_max} = 89 \text{ kNm}$	$M_{s1_red} = 89 \text{ kNm}$
Maximum moment support B	$M_{B_max} = 0 \text{ kNm}$	$M_{B_red} = 0 \text{ kNm}$
Maximum shear support A	$V_{A_max} = 179 \text{ kN}$	$V_{A_red} = 179 \text{ kN}$
Maximum shear support A span 1 at 449 mm	$V_{A_s1_max} = 98 \text{ kN}$	$V_{A_s1_red} = 98 \text{ kN}$
Maximum shear support B	$V_{B_max} = -179 \text{ kN}$	$V_{B_red} = -179 \text{ kN}$
Maximum shear support B span 1 at 1551 mm	$V_{B_s1_max} = -98 \text{ kN}$	$V_{B_s1_red} = -98 \text{ kN}$
Maximum reaction at support A	$R_A = 179 \text{ kN}$	
Maximum reaction at support B	$R_B = 179 \text{ kN}$	

Rectangular section details



Concrete details (Table 3.1 - Strength and deformation characteristics for concrete)

Concrete strength class	C28/35		
Char.comp.cylinder strength	$f_{ck} = 28 \text{ N/mm}^2$	Char.comp.cube strength	$f_{ck,cube} = 35 \text{ N/mm}^2$
Mean comp.cylinder strength	$f_{cm} = 36 \text{ N/mm}^2$	Mean axial tensile strength	$f_{ctm} = 2.8 \text{ N/mm}^2$
Secant modulus of elasticity	$E_{cm} = 32308 \text{ N/mm}^2$	Maximum aggregate size	$h_{agg} = 20 \text{ mm}$
Partial factor for concrete	$\gamma_c = 1.50$	Comp.strength coefficient	$\alpha_{cc} = 0.85$
Design compressive strength	$f_{cd} = 15.9 \text{ N/mm}^2$		


Reinforcement details

Characteristic yield strength	$f_{yk} = 500 \text{ N/mm}^2$	Partial factor for reinforcement	$\gamma_s = 1.15$
Design yield strength	$f_{yd} = 435 \text{ N/mm}^2$		

Nominal cover to reinforcement

Nominal cover to top	$c_{nom_t} = 35 \text{ mm}$	Nominal cover to bottom	$c_{nom_b} = 35 \text{ mm}$
Nominal cover to sides	$c_{nom_s} = 35 \text{ mm}$		

Support A



Rectangular section in flexure (Section 6.1) -

Design bending moment $M = 22 \text{ kNm}$

$K = 0.008$

$K' = 0.207$

$K' > K$ - No compression reinforcement is required

Tens.reinforcement required $A_{s,req} = 120 \text{ mm}^2$

Tens.reinforcement provided $5 \times 16\phi$ bars

Tens.reinforcement provided $A_{s,prov} = 1005 \text{ mm}^2$

Min area of reinforcement $A_{s,min} = 323 \text{ mm}^2$

Max area of reinforcement $A_{s,max} = 10000 \text{ mm}^2$

PASS - Area of reinforcement provided is greater than area of reinforcement required

Minimum bottom reinforcement at supports (cl.9.2.1.4(1))

Adj span reinforcement $A_{s,span} = 1571 \text{ mm}^2$

Min btm reinforcement reqd $A_{s2,min} = 393 \text{ mm}^2$

Btm reinforcement provided $5 \times 20\phi$ bars

Btm reinforcement provided $A_{s2,prov} = 1571 \text{ mm}^2$

PASS - Area of reinforcement provided is greater than minimum area of reinforcement required

Rectangular section in shear (Section 6.2)

Des.shear force at support support
force $V_{Rd,max} = 901 \text{ kN}$

$V_{Ed,max} = 179 \text{ kN}$

Max.design shear

PASS - Design shear force at support is less than maximum design shear force

Des.shear span 1 at 449 mm $V_{Ed} = 98 \text{ kN}$

Shear reinforcement required $A_{sv,req} = 212 \text{ mm}^2/\text{m}$

Min shear reinforcement $A_{sv,min} = 423 \text{ mm}^2/\text{m}$

Shear reinforcement provided $2 \times 8\phi$ legs at 100 c/c
 mm^2/m

Shear reinforcement provided $A_{sv,prov} = 1005$

PASS - Area of shear reinforcement provided exceeds minimum required

Max longitudinal spacing $S_{vl,max} = 337 \text{ mm}$

PASS - Longitudinal spacing of shear reinforcement provided is less than maximum

Crack control (Section 7.3)

Maximum crack width $w_k = 0.3 \text{ mm}$

Modulus of elasticity reinf $E_s = 200000 \text{ N/mm}^2$

Mean conc. tensile strength $f_{ct,eff} = f_{ctm} = 2.8 \text{ N/mm}^2$

Stress distribution coefficient $K_c = 0.4$

Self-equilibrating stress coef $k = 0.86$

Actual tension bar spacing $S_{bar} = 99 \text{ mm}$

Max stress permitted (T.7.3N) $\sigma_s = 320 \text{ N/mm}^2$

Conc/steel mod of elast. ratio $\alpha_{cr} = 6.19$

Distance of the ENA $y = 246 \text{ mm}$

Area of conc in tensile zone $A_{ct} = 122966 \text{ mm}^2$

Min area of reinf reqd (exp.7.1) $A_{sc,min} = 365 \text{ mm}^2$

PASS - Area of tension reinforcement provided exceeds minimum required for crack control

Quasi-perm value $\psi_2 = 0.30$

Quasi-perm limit state moment $M_{QP} = 0 \text{ kNm}$

Permanent load ratio $R_{PL} = 0.00$

Service stress in reinf $\sigma_{sr} = 0 \text{ N/mm}^2$

Max bar spacing (Table 7.3N) $S_{bar,max} = 300 \text{ mm}$

PASS - Maximum bar spacing exceeds actual bar spacing for crack control

Minimum bar spacing

Minimum bottom bar spacing $S_{bot,min} = 98 \text{ mm}$


Min allowable bottom spacing $S_{bar_bot,min} = 45 \text{ mm}$

Minimum top bar spacing $S_{top,min} = 99 \text{ mm}$

Min allowable top spacing $S_{bar_bot,min} = 45 \text{ mm}$

PASS - Actual bar spacing exceeds minimum allowable

Mid span 1



Rectangular section in flexure (Section 6.1) - - Positive midspan moment

Design bending moment $M = 89$ kNm $K = 0.032$ $K' = 0.207$

$K' > K$ - No compression reinforcement is required

Tens.reinforcement required $A_{s,req} = 484$ mm²

Tens.reinforcement provided $5 \times 20\phi$ bars

Tens.reinforcement provided $A_{s,prov} = 1571$ mm²

Min area of reinforcement $A_{s,min} = 321$ mm²

Max area of reinforcement $A_{s,max} = 10000$ mm²

PASS - Area of reinforcement provided is greater than area of reinforcement required

Rectangular section in shear (Section 6.2)

Shear reinforcement provided $2 \times 8\phi$ legs at 100 c/c
mm²/m

Shear reinforcement provided $A_{sv,prov} = 1005$

Min shear reinforcement $A_{sv,min} = 423$ mm²/m

PASS - Area of shear reinforcement provided exceeds minimum required

Max longitudinal spacing $s_{vl,max} = 335$ mm

PASS - Longitudinal spacing of shear reinforcement provided is less than maximum

Crack control (Section 7.3)

Maximum crack width $w_k = 0.3$ mm

Modulus of elasticity reinf $E_s = 200000$ N/mm²

Mean conc. tensile strength $f_{ct,eff} = f_{ctm} = 2.8$ N/mm²

Stress distribution coefficient $k_c = 0.4$

Self-equilibrating stress coef $k = 0.86$

Actual tension bar spacing $s_{bar} = 98$ mm

Max stress permitted (T.7.3N) $\sigma_s = 321$ N/mm²

Conc/steel mod of elast. ratio $\alpha_{cr} = 6.19$

Distance of the ENA $y = 244$ mm

Area of conc in tensile zone $A_{ct} = 121889$ mm²

Min area of reinf reqd (exp.7.1) $A_{sc,min} = 361$ mm²

PASS - Area of tension reinforcement provided exceeds minimum required for crack control

Quasi-perm value $\psi_2 = 0.30$

Quasi-perm limit state moment $M_{QP} = 66$ kNm

Permanent load ratio $R_{PL} = 0.74$

Service stress in reinf $\sigma_{sr} = 99$ N/mm²

Max bar spacing (Table 7.3N) $s_{bar,max} = 300$ mm

PASS - Maximum bar spacing exceeds actual bar spacing for crack control

Minimum bar spacing

Minimum bottom bar spacing $s_{bot,min} = 98$ mm

Min allowable bottom spacing $s_{bar_bot,min} = 45$ mm

Minimum top bar spacing $s_{top,min} = 99$ mm

Min allowable top spacing $s_{bar_bot,min} = 45$ mm

PASS - Actual bar spacing exceeds minimum allowable


Deflection control (Section 7.4)

Allowable span to depth ratio $span_to_depth_{allow} = 40.0$
= 4.5

Actual span to depth ratio $span_to_depth_{actual}$

PASS - Actual span to depth ratio is within the allowable limit

Support B



Rectangular section in flexure (Section 6.1) -

Design bending moment $M = 22$ kNm $K = 0.008$ $K' = 0.207$

$K' > K$ - No compression reinforcement is required

Tens.reinforcement required $A_{s,req} = 120$ mm²

Tens.reinforcement provided $5 \times 16\phi$ bars

Tens.reinforcement provided $A_{s,prov} = 1005$ mm²

Min area of reinforcement $A_{s,min} = 323 \text{ mm}^2$ Max area of reinforcement $A_{s,max} = 10000 \text{ mm}^2$

PASS - Area of reinforcement provided is greater than area of reinforcement required

Minimum bottom reinforcement at supports (cl.9.2.1.4(1))

Adj span reinforcement $A_{s,span} = 1571 \text{ mm}^2$ Min btm reinforcement reqd $A_{s2,min} = 393 \text{ mm}^2$
Btm reinforcement provided $5 \times 20\phi$ bars Btm reinforcement provided $A_{s2,prov} = 1571 \text{ mm}^2$

PASS - Area of reinforcement provided is greater than minimum area of reinforcement required

Rectangular section in shear (Section 6.2)

Des.shear force at support support $V_{Ed,max} = 179 \text{ kN}$ Max.design shear force
 $V_{Rd,max} = 901 \text{ kN}$

PASS - Design shear force at support is less than maximum design shear force

Des.shear span 1 at 1551 mm $V_{Ed} = 98 \text{ kN}$
Shear reinforcement required $A_{sv,req} = 212 \text{ mm}^2/\text{m}$ Min shear reinforcement $A_{sv,min} = 423 \text{ mm}^2/\text{m}$
Shear reinforcement provided $2 \times 8\phi$ legs at 100 c/c Shear reinforcement provided $A_{sv,prov} = 1005 \text{ mm}^2/\text{m}$

PASS - Area of shear reinforcement provided exceeds minimum required

Max longitudinal spacing $s_{vl,max} = 337 \text{ mm}$

PASS - Longitudinal spacing of shear reinforcement provided is less than maximum

Crack control (Section 7.3)

Maximum crack width $w_k = 0.3 \text{ mm}$ Modulus of elasticity reinf $E_s = 200000 \text{ N/mm}^2$
Mean conc. tensile strength $f_{ct,eff} = f_{ctm} = 2.8 \text{ N/mm}^2$ Stress distribution coefficient $k_c = 0.4$
Self-equilibrating stress coef $k = 0.86$ Actual tension bar spacing $s_{bar} = 99 \text{ mm}$
Max stress permitted (T.7.3N) $\sigma_s = 320 \text{ N/mm}^2$ Conc/steel mod of elast. ratio $\alpha_{cr} = 6.19$
Distance of the ENA $y = 246 \text{ mm}$ Area of conc in tensile zone $A_{ct} = 122966 \text{ mm}^2$
Min area of reinf reqd (exp.7.1) $A_{sc,min} = 365 \text{ mm}^2$

PASS - Area of tension reinforcement provided exceeds minimum required for crack control

Quasi-perm value $\psi_2 = 0.30$ Quasi-perm limit state moment $M_{QP} = 0 \text{ kNm}$
Permanent load ratio $R_{PL} = 0.00$ Service stress in reinf $\sigma_{sr} = 0 \text{ N/mm}^2$
Max bar spacing (Table 7.3N) $s_{bar,max} = 300 \text{ mm}$

PASS - Maximum bar spacing exceeds actual bar spacing for crack control

Minimum bar spacing

Minimum bottom bar spacing $s_{bot,min} = 98 \text{ mm}$ Min allowable bottom spacing $s_{bar_bot,min} = 45 \text{ mm}$
Minimum top bar spacing $s_{top,min} = 99 \text{ mm}$ Min allowable top spacing $s_{bar_top,min} = 45 \text{ mm}$

PASS - Actual bar spacing exceeds minimum allowable

	Wall DL	203 kN/m	ϕ	30	Wall DL	203 kN/m		
	W =	0.3 m	δ	18				
Sur 1 =	10		Span =	14 m			Sur 2 =	10
			H 1 =	3 m			Water =	3.6 m
			H 2 =	3 m				
			Slab Thickness =	0.4				
Heel =	0		Slab =	11.2				
			Toe =	0.35 m				
			Toewidth =	1.4 m				
		57.2958						
	kp =	3						
	ka =	0.33333						
	Thrust from left =	19			Thrust from Right	19		
	Resistance from Left =	162			Resistance from Right =	162		
			Equilibrium check	Kp from Right Adequate				
				Kp from left Adequate				

<p>Noise and Nuisance Control</p>	<p>The contractor is to follow the good working practices and guidance laid down in the "Considerate Constructors Scheme".</p> <p>The hours of working will be limited to those allowed; 8am to 5pm Monday to Friday and Saturday Morning 8am to 1pm.</p> <p>None of the practices cause undue noise that one would typically expect from a construction site. The conveyor belt typically runs at around 70dB.</p> <p>The site has car parking to the front to which the skip will be stored.</p> <p>The site will be hoarded with 8' site hoarding to prevent access.</p> <p>The hours of working will further be defined within the Party Wall Act.</p> <p>The site is to be hoarded to minimise the level of direct noise from the site.</p> <p>Ground floor slab is not being removed minimising the vibration and sound to adjacent properties. While working in the basement the work generally requires hand tools to be used. The level of noise generally will be no greater than that of digging of soil. The noise is reduced and muffled by the works being undertaken underground. A level of noise from a basement is lower than typical ground level construction due to this.</p>
<p>CTMP</p>	<p>The council may require a Construction Traffic Management plan to be produced. This is outside the brief of the Basement impact assessment and is not covered within Croft's Brief</p>

Appendix A ; Construction Method Statement

Basement Method Statement

35 Greville Road
London
NW6 5JB

Client Information
Igor Gokhberg
55 Peiantho CRT
Vaughan
ON
LGA 1G1
Canada

Contents

Executive Summary / Non technical Summary.....	5
Project Summary.....	5
Stage 1 – Screening	6
Stage 2 – Scoping.....	6
Stage 3 – Site investigation and study.....	7
Stage 4 – Impact assessment	7
1. Screening Stage.....	9
Land Stability	9
Subterranean Flow	9
Surface Flow and Flooding	9
2. Scoping Stage.....	12
Land Stability	12
Subterranean Flow	12
Surface Flow & Flooding.....	12
Conceptual Model.....	12
3. Site Investigation and Study.....	14
Desk Study and Walkover Survey.....	14
Proposed Development	14
Site History	15
Local Bombing	16
Listed Buildings.....	16
Highways, Rail and London Underground.....	17
London Underground and Network Rail	17
UK Power Networks.....	17
Vicinity of Trees.....	17
Building Defects	17
Nos 37 Greville Rpad Property to right	18
Local Topography	19
Ground Investigation	19
Geology	20
Surface Flow & Flooding.....	20
Areas of Hard Standing present on site	20

Rainwater down pipes, Drains, Manholes and Gulleys	20
Local Water Sources	20
Field Investigation	20
Monitoring, Reporting and Investigation	20
Land Stability	20
Site Investigation	21
4. Basement Impact Assessment	22
Subterranean Flow	22
Land Stability	22
Flood Risk Assessment	23
Site Location	24
Potential surface water (pluvial) flooding	24
Potential flooding from infrastructure failure	25
Mitigation measures	25
Summary	25
SUDS Assessment	26
Hard standing	26
SUDS Assessment	26
SUDS Calculations	26
Mitigation Measures	26
Drainage effects on Structure	26
Trees	27
Root Protection Zone	27
Conclusion	27
Ground Movement Assessment & Predicted Damage Category	28
Burland Scale	33
Monitoring	34
Risk Assessment	35
Monitoring Conclusion	37
Basement Design & Construction Impacts	39
Foundation type	39
Roads	39
Intended use of structure and user requirements	39
Loading Requirements (EC1-1)	39

Part A3 Progressive collapse	40
Lateral Stability	40
Exposure and wind loading conditions	40
Stability Design	40
Lateral Actions	40
Retained soil Parameters	40
Water Table	41
Drainage and Damp Waterproofing	41
Localised Dewatering	41
Temporary Works	42
Geological Assessment of Land Stability	42
Retaining Wall Calculation	42
piled wall 1 (temporary case)	45
Retaining wall analysis & design (BS8002)	45
RETAINING WALL ANALYSIS (BS 8002:1994)	45
RETAINING WALL DESIGN (BS 8002:1994)	48
Design of reinforced concrete retaining wall toe (BS 8002:1994)	48
Design of reinforced concrete retaining wall stem (BS 8002:1994)	48
Indicative retaining wall reinforcement diagram	50
piled wall 1 (permanent case)	51
Retaining wall analysis & design (BS8002)	51
RETAINING WALL ANALYSIS (BS 8002:1994)	51
RETAINING WALL DESIGN (BS 8002:1994)	53
Design of reinforced concrete retaining wall toe (BS 8002:1994)	53
Design of reinforced concrete retaining wall heel (BS 8002:1994)	53
Design of reinforced concrete retaining wall stem (BS 8002:1994)	54
Indicative retaining wall reinforcement diagram	55
capping beam for piled wall 1	56
RC beam analysis & design (EN1992)	56
RC beam analysis & design (EN1992-1)	56
Support A	57
Mid span 1	58
Support B	59
piled wall 2 (temporary case)	61

Retaining wall analysis & design (BS8002)	62
RETAINING WALL ANALYSIS (BS 8002:1994)	63
RETAINING WALL DESIGN (BS 8002:1994)	65
Design of reinforced concrete retaining wall toe (BS 8002:1994)	65
Design of reinforced concrete retaining wall heel (BS 8002:1994)	65
Design of reinforced concrete retaining wall stem (BS 8002:1994)	66
Indicative retaining wall reinforcement diagram.....	67
piled wall 2 (permanent case).....	68
Retaining wall analysis & design (BS8002)	68
RETAINING WALL ANALYSIS (BS 8002:1994)	68
RETAINING WALL DESIGN (BS 8002:1994)	70
Design of reinforced concrete retaining wall toe (BS 8002:1994)	70
Design of reinforced concrete retaining wall heel (BS 8002:1994)	70
Design of reinforced concrete retaining wall stem (BS 8002:1994)	71
Indicative retaining wall reinforcement diagram.....	72
capping beam for piled wall 2	73
RC beam analysis & design (EN1992)	73
RC beam analysis & design (EN1992-1)	73
Support A	74
Mid span 1.....	75
Support B.....	76
Noise and Nuisance Control.....	79
CTMP.....	79
Appendix A ; Construction Method Statement.....	80
35 Greville Road	87
1. Basement Formation Suggested Method Statement	87
2. Enabling Works	88
3. Piling Sequencing.....	88
4. Demolition, Recycling, Dust/Noise Control and Site Hoarding.....	90
5. Trench sheet design and temporary prop Calculations	91
STANDARD LAP TRENCH SHEETING	92
KD4 SHEETS	96
Appendix B : Structural Drawings.....	103



35 Greville Road

1. Basement Formation Suggested Method Statement.

- 1.1. This method statement provides an approach which will allow the basement design to be correctly considered during construction, and the temporary support to be provided during the works. The Contractor is responsible for the works on site and the final temporary works methodology and design on this site and any adjacent sites.
- 1.2. This method statement for 35 Greville Road has been written by a Chartered Engineer. The sequencing has been developed considering guidance from ASUC.
- 1.3. This method has been produced to allow for improved costings and for inclusion in the party wall Award. Should the contractor provide alternative methodology the changes shall be at their own costs, and an Addendum to the Party Wall Award will be required.
 - 1.0
- 1.4. Contact party wall surveyors to inform them of any changes to this method statement.
- 1.5. The approach followed in this design is; to remove load from above and place loads onto supporting steelwork, then to cast retaining walls in underpin sections at the new basement level.
- 1.6. A soil investigation has been undertaken. The soil conditions are London Clay formation
- 1.7. The bearing pressures have been limited to 130-150kN/m². This is standard loadings for local ground conditions and acceptable to building control and their approvals.
- 1.8. The water table is expected to be encountered at 0.8m BGL
 - 2.0
- 1.9. Structural Water proofer (Not Croft) must comment on the design proposed and ensure they are satisfied that proposals will provide adequate water proofing.
 - 3.0
- 1.1. Provide engineers with concrete mix, supplier, deliver and placement methods 2 weeks prior to first pour. Site mixing of concrete should not be employed apart from in small sections <1m³. Contractor must provide method on how to achieve site mixing to correct specification, contractor must undertake tool box talks with staff to ensure site quality is maintained.

2. Enabling Works

- 2.1. The site is to be hoarded with ply sheet to 2.2m to prevent unauthorised public access.
- 2.2. Licenses for Skips and conveyors to be posted on hoarding
- 2.3. Provide protection to public where conveyor extends over footpath. Depending on the requirements of the local authority, construct a plywood bulkhead onto the pavement. Hoarding to have a plywood roof covering, night-lights and safety notices.
 - 4.0
- 2.4. Dewater: Water is expected at 0.5 depths
 - 5.0
 - 2.4.1. Place a bore hole to the rear of the property down to a depth of 6m
 - 2.4.2. Pump water away from site.
- 2.5. On commencement of construction the contractor should report any discrepancies to the structural engineer in order that the detailed design may be modified as necessary.

3. Piling Sequencing

- 3.1. Piles are to be installed at different levels and positions around the development. All piles are installed from the same level and cut down as required.
 - 6.0
 - 3.1.1. Prior to bringing the piling rig on site, check with the piling contractor the requirements of a working platform and install to their design and specification if required.
 - 3.1.2. Mark out datum line to determine various surface heights
 - 7.0
 - 3.1.3. Mark out pile sequence locations as specified by Engineer's drawings.
 - 8.0
 - 3.1.4. Following the sequencing guidance from the Engineers drawings mark out proposed pile position with a pair of reference markers at 1.0m from the pile pin, approximately 90 degrees apart.
 - 9.0
 - 3.1.5. Rig operator to set up over the pile pin position and position auger relative to reference marks. Directed and checked by banks man.
 - 10.0
 - 3.1.6. The flap at the tip of the auger is closed and secured. Auger tip lowered to ground level and position rechecked. Drilling to commence upon banks man approval.
 - 11.0
 - 3.1.7. Concrete is prepared while piling gang grout up concrete pump, hoses and flight, concrete pump operator to check concrete complies with design mix. Concrete held in agitator.
 - 12.0
 - 3.1.8. Rig operator augers to require design depth. Reference makers are to be used to check pile position during the first few meters of drilling.
 - 13.0
 - 3.1.9. If obstruction encountered, Engineer to be notified of pile number and depth. Move rig to next pile position whilst obstruction removal is dealt with. Contractor to be

advised on procedure should obstruction not be removable. If necessary, pile bores to be backfilled and made safe. Open excavation to be protected when open.

14.0

15.0

3.1.10. When design depth reached, the auger is to be kept rotating to allow spoil in the bore to rise.

3.1.11. Concrete can be pumped to rig while rig operator monitors instrumentation and adjust auger rate of withdrawal accordingly.

16.0

3.1.12. Pressure, concrete flow and over-break to be monitored throughout operation.

17.0

3.1.13. During the withdrawal the rig operator is to activate the flight cleaner. If an automatic cleaner is not fitted to the rig then the piling gang must clean the flight manually to prevent spoil/ arising travelling above head height – this will be controlled by the piling foreman who must ensure the auger is not rotating when it is manually cleaned.

18.0

3.1.14. When auger tip reaches platform level, concrete pumping is stopped.

19.0

3.1.15. Attendant excavator as directed by the banks man clears spoil and concrete slurry from pile heap.

20.0

3.1.16. Banks man to check position of the cage in the pile, centring where necessary. Reinforcement generally to be installed flush with Piling Platform Level (PPL). Anchor pile reinforcement or threaded bars that project above piling platform to have protective caps.

21.0

3.1.17. Concrete testing cube samples to be taken as per engineering specification.

22.0

3.1.18. Rig is moved onto next pile in the sequence and positioned as above, with piles installed as per points 3.1.5 – 3.1.12

23.0

3.1.19. Equipment to be cleaned and maintained as per normal methods.

24.0

3.1.20. This sequence of piling is to continue until all perimeter piles have been installed.

25.0

3.1.21. Cast internal bases and columns from basement to ground floor level.

26.0

3.2. Once all piles have been installed, bases and steel columns have been installed and additional temporary piles included, the next step sequence is to cast capping beams and install the steelwork at ground level that which in permanent condition will prop the external perimeter of the basement.

3.3. When steelwork has been set up, the excavation of the central mass can begin using mechanic excavators (an opening big enough to allow for access for machinery and spoil removal should be left.

27.0

3.4. As excavation continues down, a dewatering system will need to be considered. There are several method of doing this but the most common method is to install well points from which ground water can be pumped as mentioned in point 2.4.1

28.0

- 3.5. Once excavation is level done to the intermediate floor level the steelwork is installed: this will prop the external perimeter of the basement in permanent condition as the ground floor steelwork. Effectively the basement is constructed in a top down method for other works to be the development to be undertaken at the same time as the basement dig out.
29.0

4. Demolition, Recycling, Dust/Noise Control and Site Hoarding

- 4.1. Demolition work is to take place within the hoarded confines of the materials such as stock bricks, timber etc. are to be recycled where possible. To minimise dust and dirt from demolition the following measures shall be implemented:
- 4.1.1. Any debris or dust or dirt falling on the street and public highway will be cleared as it occurs by designated cleaners and washed down fully every night.
 - 4.1.2. Demolished materials are to be removed to a skip placed in front of the site which will be emptied regularly as required.
 - 4.1.3. All brickwork and concrete demolition work is to be constantly watered to reduce airborne dust
30.0
- 4.2. Building work which can be heard at the boundary of the site will not be carried out on Sundays or bank holidays and will be carried out within working hours as agreed by the council.

5. Trench sheet design and temporary prop Calculations

This calculation has been provided for the trench sheet and prop design of standard underpins in the temporary condition. There are gaps left between the sheeting and as such no water pressure will occur. Any water present will flow through the gaps between the sheeting and will be required to pump out.

Trench sheets should be placed at centres to deal with the ground. It is expected that the soil between the trench sheeting will arch. Looser soil will require tighter centres. It is typical for underpins to be placed at 1200c/c, in this condition the highest load on a trench sheet is when 2 nos trench sheets are used. It is for this design that these calculations have been provided.

Soil and ground conditions are variable. Typically one finds that in the temporary condition clays are more stable and the C_u (cohesive) values in clay reduce the risk of collapse. It is this cohesive nature that allows clays to be cut into a vertical slope. For these calculations weak sand and gravels have been assumed. The soil properties are:

Surcharge	$sur = 10. \text{ kN/m}^2$	
Soil density	$\delta = 20 \text{ kN/m}^3$	
Angle of friction	$\phi = 25^\circ$	
Soil depth	$D_{soil} = 3000.000 \text{ mm}$	
	$k_a = (1 - \sin(\phi)) / (1 + \sin(\phi))$	= 0.406
	$k_p = 1 / k_a$	= 2.464
Soil Pressure bottom	$soil = k_a * \delta * D_{soil}$	= 21.916 kN/m²
Surcharge pressure	$surcharge = sur * k_a$	= 4.059 kN/m²

STANDARD LAP TRENCH SHEETING

STANDARD LAP

The overlapping trench sheeting profile is designed primarily for construction work and also temporary deployment.



Technical Information

Effective width per sheet (mm)	330
Thickness (mm)	3.4
Depth (mm)	35
Weight per linear metre (kg/m)	10.8
Weight per m ² (kg)	32.9
Section modulus per metre width (cm ³)	48.3
Section modulus per sheet (cm ³)	15.9
I value per metre width (cm ⁴)	81.7
I value per sheet (cm ⁴)	26.9
Total rolled metres per tonne	92.1




$$S_{xx} = 15.9 \text{ cm}^3$$


$$p_y = 275 \text{ N/mm}^2$$

$$I_{xx} = 26.9 \text{ cm}^4$$

$$A = (1 \text{ m}^2 * 32.9 \text{ kg/m}^2) / (330 \text{ mm} * 7750 \text{ kg/m}^3) = 12864.125 \text{ mm}^2$$



Length a a = 2.600 m
 Length b bottom b = 0.700 m
 Length c Middle c = a - b = 1.900m
 Length d top d = Dsoil - a = 0.400m



CONTINUOUS BEAM ANALYSIS - INPUT

BEAM DETAILS

Number of spans = 3

Material Properties:

Modulus of elasticity = 205 kN/mm²

Material density = 7860 kg/m³

Support Conditions:

Support A Vertically "Restrained"
Support B Vertically "Restrained"
Support C Vertically "Restrained"

Rotationally "Free"
 Rotationally "Free"
 Rotationally "Free"

Support D Vertically "Free"

Rotationally "Free"

Span Definitions:

Span 1	Length = 700 mm	Cross-sectional area = 12864 mm ²	Moment of inertia = 269.×10³ mm ⁴
Span 2	Length = 1900 mm	Cross-sectional area = 12864 mm ²	Moment of inertia = 269.×10³ mm ⁴
Span 3	Length = 400 mm	Cross-sectional area = 12864 mm ²	Moment of inertia = 269.×10³ mm ⁴

LOADING DETAILS

Beam Loads:

- Load 1** UDL Dead load **4.1** kN/m
- Load 2** VDL Dead load **21.9** kN/m to **0.0** kN/m

LOAD COMBINATIONS

Load combination 1

- Span 1** 1×Dead
- Span 2** 1×Dead
- Span 3** 1×Dead

CONTINUOUS BEAM ANALYSIS - RESULTS

Unfactored support reactions



	Dead (kN)							
Support A	-1.4	0.0	0.0	0.0	0.0	0.0	0.0	0.0
Support B	-32.8	0.0	0.0	0.0	0.0	0.0	0.0	0.0
Support C	-10.8	0.0	0.0	0.0	0.0	0.0	0.0	0.0
Support D	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0

Support Reactions - Combination Summary

Support A	Max react = -1.4 kN	Min react = -1.4 kN	Max mom = 0.0 kNm	Min mom = 0.0 kNm
Support B	Max react = -32.8 kN	Min react = -32.8 kN	Max mom = 0.0 kNm	Min mom = 0.0 kNm
Support C	Max react = -10.8 kN	Min react = -10.8 kN	Max mom = 0.0 kNm	Min mom = 0.0 kNm
Support D	Max react = 0.0 kN	Min react = 0.0 kN	Max mom = 0.0 kNm	Min mom = 0.0 kNm

Beam Max/Min results - Combination Summary

Maximum shear = 17.8 kN	Minimum shear F_{min} = -15.0 kN
Maximum moment = 3.7 kNm	Minimum moment = -5.0 kNm
Maximum deflection = 21.0 mm	Minimum deflection = -14.3 mm



Number of sheets Nos = 2

$$\text{Mallowable} = S_{xx} * p_y * \text{Nos} = 8.745\text{kNm}$$

Safe working loads for Acrow Props — loads given in kN

SRU 4.0

For normal purposes 1 kilo Newton (kN) = 100 kg	Height	m		2.25		2.5		2.75		3.0		3.25		3.5		3.75		4.0		4.25		4.5		4.75	
		ft	6.6	7.4	8.2	9.0	9.8	10.7	11.5	12.3	13.1	13.9	14.8	15.6											
TABLE A Props loaded concentrically and erected vertically	Prop size 1 or 2	35	35	35	34	27	23																		
	Prop size 3				34	27	23	21	19	17															
	Prop size 4							32	25	21	18	16	14	12											
TABLE B Props loaded concentrically and erected 1½° max. out of vertical	Prop size 1 or 2 or 3	35	32	26	23	19	17	15	13	12															
	Prop size 4							24	19	15	12	11	10	9											
TABLE C Props loaded 25 mm eccentricity and erected 1½° max. out of vertical	Prop size 1 or 2 or 3	17	17	17	17	15	13	11	10	9															
	Prop size 4							17	14	11	10	9	8	7											
TABLE D Props loaded concentrically and erected 1½° out of vertical and laced with scaffold tubes and fittings	Prop size 3				35	33	32	28	24	20															
	Prop size 4							35	35	35	35	27	25	21											


$$\text{Shear } V = (14.6\text{kN} + 13.4\text{kN}) / 2 = 14.000\text{kN}$$

Any Acro Prop is acceptable

KD4 SHEETS

KD4

The overlapping trench sheeting profile is a heavier version of the Standard Lap, with a wider gauge and width coverage, designed in large for construction work.



Technical Information

Effective width per sheet (mm)	400
Thickness (mm)	6.0
Depth (mm)	50
Weight per linear metre (kg/m)	21.90
Weight per m ² (kg)	55.2
Section modulus per metre width (cm ³)	101
Section modulus per sheet (cm ³)	40.34
I value per metre width (cm ⁴)	250
I value per sheet (cm ⁴)	101
Total rolled metres per tonne	45.659




$$S_{xx} = 48.3\text{cm}^3$$


$$p_y = 275\text{N/mm}^2$$

$$I_{xx} = 26.9\text{cm}^4$$

$$A = (1\text{m}^2 * 55.2\text{kg/m}^2) / (400\text{mm} * 7750\text{kg/m}^3) = 17806.452\text{mm}^2$$



Length a $a = 2.700$ m
 Length b bottom $b = 1.100$ m
 Length c Middle $c = a - b = 1.600$ m
 Length d top $d = D_{soil} - a = 0.300$ m



CONTINUOUS BEAM ANALYSIS - INPUT

BEAM DETAILS

Number of spans = 3

Material Properties:

Modulus of elasticity = 205 kN/mm²

Material density = 7860 kg/m³

Support Conditions:

Support A	Vertically "Restrained"	Rotationally "Free"
Support B	Vertically "Restrained"	Rotationally "Free"
Support C	Vertically "Restrained"	Rotationally "Free"
Support D	Vertically "Free"	Rotationally "Free"

Span Definitions:

Span 1	Length = 1100 mm	Cross-sectional area = 17806 mm ²	Moment of inertia = 269.x10 ³ mm ⁴
Span 2	Length = 1600 mm	Cross-sectional area = 17806 mm ²	Moment of inertia = 269.x10 ³ mm ⁴

Span 3 Length = **300 mm** Cross-sectional area = **17806 mm²** Moment of inertia = **269.x10³ mm⁴**

LOADING DETAILS

Beam Loads:

- Load 1** VDL Dead load **21.9 kN/m to 0.0 kN/m**
- Load 2** UDL Dead load **4.1 kN/m**

LOAD COMBINATIONS

Load combination 1

- Span 1** 1xDead
- Span 2** 1xDead
- Span 3** 1xDead



CONTINUOUS BEAM ANALYSIS - RESULTS

Support Reactions - Combination Summary

Support A	Max react = -9.5 kN	Min react = -9.5 kN	Max mom = 0.0 kNm	Min mom = 0.0 kNm
Support B	Max react = -28.0 kN	Min react = -28.0 kN	Max mom = 0.0 kNm	Min mom = 0.0 kNm
Support C	Max react = -7.5 kN	Min react = -7.5 kN	Max mom = 0.0 kNm	Min mom = 0.0 kNm
Support D	Max react = 0.0 kN	Min react = 0.0 kN	Max mom = 0.0 kNm	Min mom = 0.0 kNm

Beam Max/Min results - Combination Summary

Maximum shear = 13.4 kN	Minimum shear F_{min} = -14.6 kN
Maximum moment = 2.0 kNm	Minimum moment = -3.6 kNm
Maximum deflection = 7.7 mm	Minimum deflection = -4.9 mm



Number of sheets Nos = 2

Mallowable = $S_{xx} * p_y * Nos = 26.565kNm$

SRU 4-0

Safe working loads for Acrow Props — loads given in kN


For normal purposes 1 kilo Newton (kN) = 100 kg	Height	m													
		2.0	2.25	2.5	2.75	3.0	3.25	3.5	3.75	4.0	4.25	4.5	4.75		
	ft	6.6	7.4	8.2	9.0	9.8	10.7	11.5	12.3	13.1	13.9	14.8	15.6		
TABLE A Props loaded concentrically and erected vertically	Prop size 1 or 2	35	35	35	34	27	23								
	Prop size 3				34	27	23	21	19	17					
	Prop size 4						32	25	21	18	16	14	12		
TABLE B Props loaded concentrically and erected 1½° max. out of vertical	Prop size 1 or 2 or 3	35	32	26	23	19	17	15	13	12					
	Prop size 4						24	19	15	12	11	10	9		
TABLE C Props loaded 25 mm eccentricity and erected 1½° max. out of vertical	Prop size 1 or 2 or 3	17	17	17	17	15	13	11	10	9					
	Prop size 4						17	14	11	10	9	8	7		
TABLE D Props loaded concentrically and erected 1½° out of vertical and laced with scaffold tubes and fittings	Prop size 3				35	33	32	28	24	20					
	Prop size 4						35	35	35	35	27	25	21		

Mabey 25 across and piles to be used


Sheeting requirements

Ground Type	Trench Depth, D			
	less than 1.2m ⁽¹⁾	1.2 to 3m	3 to 4.5m	4.5 to 6m
Sands and gravels	Close, ½, ¼, ⅛ or nil	Close	Close	Close
Silt				
Soft Clay				
High compressibility Peat				
Firm/stiff Clay	¼, ⅛ or nil	½ or ¼	½ or ¼	Close or ½
Low compressibility Peat				
Rock ⁽²⁾	From ½ for incompetent rock to nil for competent rock⁽³⁾			

Sheeting requirements




Sheeting requirements



Half sheeting
shown for 1.5 m deep trench

11/04/2015


Sheeting requirements




11/04/15 Quarter sheeting

Design to CIRIA 97


Note:
 For standard Speedshore hydraulic strut and waling or equivalent use the curve for 229 x 89 RSC.
 Heavy duty Speedshores have a capacity of 35.5 kN/metre run of waling at 3.2m horizontal strut spacing.

 Any proprietary system should be checked against manufacturer's latest information.


Use for:
 Granular soils
 Mixed soils
 Short term trenches in clay
 (see notes opposite)



Note:
 For standard Speedshore hydraulic strut and waling or equivalent use the curve for 229 x 89 RSC.
 Heavy duty Speedshores have a capacity of 35.5 kN/metre run of waling at 3.2m horizontal strut spacing.


 Any proprietary system should be checked against manufacturer's latest information.

Use for:
 Granular soils
 Mixed soils
 Short term trenches in clay
 (see notes opposite)



Appendix B : Structural Drawings

- 1:100 Basement Plan on A3 Showing Neighbouring basements if present
- 1:100 Ground Floor plan on A3 Showing Neighbouring property
- 1:50 Section on A3 Including section through Neighbouring Footings



**Lower Ground
Floor plan**
Scale (1:100)


-	27/08/15	First issue for comment
Rev	Date	Amendments


Client: Igor Gokhberg
Project: 35 Greville Road

Title : Lower Ground Floor plan
BIA

Job No.s 150525	Drawn NM	Date Aug 15
Dwg Nos SL-20	Rev -	Scale As Shown @ A3

**Croft
Structural
Engineers**
Clockshop Mews, 0208 684 4744
Rear 60 Saxon Rd, www.croftse.co.uk
London, SE25 5EH





Basement plan

Scale (1:100)


-	27/08/15	First issue for comment
Rev	Date	Amendments


Client: **Igor Gokhberg**
 Project: **35 Greville Road**

Title : **Basement Floor plan
 BIA**

Job No.s 150525	Drawn NM	Date Aug 15
Dwg Nos SL-10	Rev -	Scale As Shown @ A3

**Croft
 Structural
 Engineers**
 Clockshop Mews, 0208 684 4744
 Rear 60 Saxon Rd, www.croftse.co.uk
 London, SE25 5EH





Section 1-1

Scale (1:50)

General Notes:

- USE ONLY FIGURED DIMENSIONS. All dimensions in mm's. Refer to Architect's drawings for setting out. This drawing is to be read in conjunction with all relevant Architects, subcontractors and engineers drawings and specifications. Final co-ordination of cladding, drainage, insulation, steelwork, and other elements is the responsibility of the contractor.
- All dimensions and levels shown are based on survey drawings. The contractor is to satisfy themselves that dimensions levels etc are sufficiently accurate to complete construction to the necessary tolerances. Existing structure to be verified on site by the contractor and any discrepancies reported immediately to Engineer.
- Domestic jobs: the contractor is to notify the local H.S.E. area office of the works using form F10 (rev.) in accordance with the C.D.M. regulations, 2007. A copy of the notification is to be displayed on site and copied to the Engineer. The client must appoint a CDM co-ordinator and comply with CDM Regulations for all projects which are not their private residency.
- Imposed load design Typical Domestic 1.5kN/m²
- Concrete to be in accordance with BS8110 Concrete for mass concrete foundations to be To FND 3 in accordance with BS8500 (minimum strength 35N/mm², 20mm maximum aggregate size, 75mm slump and ordinary Portland Cement). Reinforced concrete to be RC28/35 min (previous designation C35N/mm²) unless noted otherwise. Minimum Cement contents 320kg/m³, Water cement ratio 0.55.2 Cubes to be taken for every 10m³, or every pour, and 1 tested at 28 days with the results provided to the engineer.
- Reinforcement required is noted on the drawings or in the calculations as either areas of reinforcement or bar/mesh requirements. Schedules are to be completed by the contractor and provided to the engineer 1 week before ordering. Reinforcement schedules to be completed in accordance with BS8666:2005 or BS EN ISO 3766
- Water proofing, damp proofing and all weather proofing are not the responsibility of Croft Structural Engineers. Basement water proofing is the responsibility of the specialist

- waterproofing contractor. Croft are not the Structural Water-proofer. The specialist water proofing contractor must review our drawings and design and if greater waterproofing resistance is required then Croft are to be informed and the additional requirements will be added to the plans.
- The Specialist water-proofer must provide details, M = Factored Moments. Connection their drainage layout and sump locations to Calculations, Fabrication details are to be provided by fabricator to the Engineer prior to installation.
 - Pipes below slab to have to be encased in 150mm of concrete. Pipes within slab to have a minimum of 150mm concrete around them.
 - Grace Adcor ES waterstop is to be added to all day joints and construction joints in the basement. If high water table encountered include Caltite admixture to the concrete.
 - Dewatering must be turned off 2 weeks before internal drain cavity is fixed. Any leaks are to be plugged in accordance to SIKA's specifications.

- Structural steelwork to be in accordance with ADVANCED275JR internally, for high grade steel use ADVANCED355JR internally. BS5950 for design detail and workmanship. Steelwork must be fabricated in accordance with BS EN 1090. Fabricated Steelwork must be provided with a CE Mark, FPC, RWC and WQMS. All structural work and fire protection to be to the satisfaction of the Building Control Officer.

External Steel - ADVANCED275JR up to 15mm, above 15mm use ADVANCED275J0. For high grade steel use ADVANCED355JR up to 11mm for external use and ADVANCED355J0 above 11mm

- All Steel to be painted: prepared by grit blasting in accordance with BS7079, the standard of surface cleanliness is to Swedish Standard SA2.5. Paint specification to be in accordance with BS5493. In shop applied high build Red zinc phosphate modified alkyd, to 75 microns. On site, degrease and touch up as necessary using high build zinc phosphate modified alkyd to 60 microns. Thicknesses are dry film thicknesses. Steelwork built into cavity to be galvanised in accordance to EN ISO 1461 with a minimum 85µm thickness. Site repairs to existing masonry stainless steel furfix connections are required. Provide stainless steel EML Bed joint reinforcement two course (150 and 300 spacing) above and below all new window and door openings. Below DPCS, all masonry to the Frost resistant. Block work

- Unless noted otherwise, steelwork welds to below DPC to be sulphate resistant. be minimum 6mm fillet weld, all bolts to be grade 8.8 with minimum 16mm diameter. Overall lengths & Connection design is the responsibility of the contractor and details where shown are indicative. Where loads are shown on the drawings, V = Factored Shear
- Double up timber joists under all new partition walls and velux windows.
- Masonry to be in accordance with BS5628, Class (ii) above DPC and Class (i) to be used below DPC's and to chimneys. New brickwork to be carefully bonded to existing. Block bonding is not permitted for exposed masonry brickwork. Block contraction joints required at 6m c/c and brickwork expansion joints at 12m c/c. Where existing new masonry meets existing masonry stainless steel furfix connections are required. Provide stainless steel EML Bed joint reinforcement two course (150 and 300 spacing) above and below all new window and door openings. Below DPCS, all masonry to the Frost resistant. Block work

- Padstones, required under all new beam bearing onto masonry, to be 1:1.5:3 mix, (C30). Or PC Lintels if noted. 15mm thick Plate can be used with engineers approval.
- Dry packing to be to be 2:1 Sand:Cement mixed to a "damp" consistence. Beams over 5m and underpins Dry pack to contain Fosroc CBex 100. Dry pack to be well rammed in. 48 hours to be left from drypacking to removal of any temporary supports.
- The main contractor is to be responsible for the temporary stability of existing structures and earthworks on the site and adjoining sites, and must take all necessary precautions to safeguard this stability. Details of propping/needling and method statement to be provided to Engineer prior to commencing works.
- Foundations designed on an assumed bearing pressure of 100kN/m². Formation level to be 1200 min to external foundations and 1000 for internal. Footings to extend 300mm below any roots found. Formation to be inspected & agreed on site to the satisfaction of the Building Control Officer.
- Any drain run undermining existing foundations to be encased in minimum 100mm, grade C20 concrete.
- Existing lintels to be inspected and replaced if showing signs of deterioration.
- Existing masonry to be inspected. Where cracked or debonded repairs as specified if not repairs are specified contact the engineer. Existing walls to be checked for lateral restraint. If restraint is inadequate provide lateral restraint.
- Provide Lateral Restraint straps (1200x30x3) at 1200centres to floors and roof. Provide Holding Down straps (1200x30x3) at 1200centres roof sole plate.
- Use Ancon ST1 Wall ties for new cavity over 75mm. Fix at standard spacing. Less than 75mm cavity standard wall ties to be used.

Rev	Date	Amendments
-	27/08/15	First issue for comment

Job No.s 150525	Client: Igor Gokhberg
Dwg Nos SD-11	Project: 35 Greville Road
Date Aug 15	Title : Lower Ground Floor plan BIA
Drawn NM Chkd CT	
Scale As shown @ A3	

Croft Structural Engineers

Clockshop Mews,
r/o 60 Saxon Rd,
London, SE25 5EH.

020 8684 4744
www.croftse.co.uk

