

## NOTES: -

- (1) New curved link extension in the north-east corner of the New Court. Link to be of framed construction, with a leaf of second hand plum stock headers over the basement level. Ground Floor of the link to be of hardwood timber frame construction, with infill panels, timber panelled at low level and glazed upper sections match the pattern of the No. 12 Breakfast Parlour. Glass to be pale yellow colour to match glass elsewhere in the Museum.
- 2 Existing (1889) doorway to the New Court to be bricked up to recreate Soane's 1837 arrangement for the Catacombs. Existing door to be taken off and re-used, frame, fanlight and metal gate to be dismantled and cleared away from site.
- 3 New doorway formed between the Store and the New Court Link Passage. (NB this wall was completely reconstructed by Wild in 1889 when he rearranged the Catacombs in this space). New door to be timber panelled. Threshold of the formed Wild door to the New Court to be used in this location.
- A New h/w timber beaded door frame with fanlight (NB head section curved on plan to be installed in opening in West Wall. Wild door from existing New Court door to be re-hung in this position. Doorway to have an arched brick head and Portland stone threshold step.
- (5) New traditional lead rwp, with ears to connect existing outlets on the East Wall of the New Court, assume 110mm dia.
- 6 New traditional lead rwp, to run up New Court Link Passage, with ears to connect existing outlets on the East Wall of the New Court, assume 110mm dia. RWP to drain to existing inspection chambers, as installed in OUTS Phase 1. (Provisional sum to be allowed for in forming new swept branches to take connections as necessary).
- Existing metal security gate, hinges and keep to be removed and reused as the grille to the new doorway to the New Court, item 7a. Contractor to provisionally allow for fabricating a new keep and supplying and installing a new Chubb lock and lock plate on gate (details to follow).
- 8 Existing York stone flags to be lifted and cleaned down and re-beded on a 25mm hydraulic lime bed. NB some flags may require cutting down to suit new floor plan.

DRAWING REVISIONS: Rev. A: Nov. 2013: Plan amended. Rev. B: Jul. 2015: Door revised. Notes 2, 4 & 7 amended.





