Project title	Installation of Individual Boiler at Brookfield Estate	Date	17/10/2013
Project no	12121	Sheet	1 of 1

Condition	Diference	As Approved	As Proposed
2	**Removal of 89 Croftdown Road from Scheme**	89 Croftdown Road included	89 Croftdwon road has been removed from the scheme.
2	**Installation of Gas Meter Boxes**	No gas infrastructure shown	A new Multibox Gas Meter Box is proposed to be installed at ground level, in as close a location as is possible to the individual boiler location to limit the amount of distribution pipework required. The meter boxes are manufactured in glass reinforced plastic and are brown in colour, see included data sheet
2	**Installation of Gas Distribution pipework**	No gas infrastructure shown	From each new gas meter box it is proposed that a Ø32mm gas pipe runs on the external wall to each dwelling. The pipework will be manufactured in steel and is proposed to be painted black in colour to match the existing gutters, rainwater down pipes, above ground drainage pipes and external electrical cabling
3	**Flue Terminal Colour**	The terminals were originally proposed to be painted to an approved colour to blend into the existing building as closely as possible	The flue terminals are proposed to be white in colour where the terminals are penetrate through windows to match the existing window frames and new white composite panels. Where flues penetrate through walls and roofs it is proposed that the terminals are black to match the existing gutters, rainwater down pipes, above ground drainage pipes and external electrical cabling