

Demolition/removal of fixed installations/partitions/fences



AREA 1 External

REMOVED

- 1 Pitched roof canopy, supports, gutters and sign
- 2 Railings leading to entrance door (orientated north/south) removed
- 3 Planter
- **4** Front entrance gates to be re-used but reconfigured as per design drawings.

ALSO REMOVED

- Tarmac and brick pavers
- Suspended school sign
- Existing lighting
- Green wall paint
- Green wall pa NOTE
- 5 Railings on street front mounted to low wall (5 orientated east/west) to be retained

AREA 2 Internal

REMOVED

- **6** Front Entrance doors and fanlight/panel above
- 7 Steps/Handrail
- 8 Stair-lift
- 9 Radiator and TV above
- 10 -
- 11 -12 -
- 13 -
- 13 -14 -
- **15** Raised creche floor removed, including steps and partition walls
- 16 -17 Low level units to be removed.

GENERAL


All floor coverings removed. Floors made level where necessary

Blinds removed throughout

All lighting to be replaced where possible

Partitions, lay-in grid suspended ceilings and FF+E removed in offices, G02,G03,G04 and adjacent corridor. Where services are mounted on removed partitions, services are to be relocated.

Fixed furniture in G05 Bursars office to be retained as current



•—

Ø

4

n n

0

Approval

Planning

All dimensions to be

Levels are not co-ordinated to Ordnance Survey standards and are indicated for guidance using the lobby floor as a datum

Refer to schedule of works in design and access statement for more information

Drawing to be read in

GA Ground Floor

Demolitions

This drawing is copyright of Michael Tite Are Ltd. Do not scale off the drawings

 $\begin{array}{c} 1403_{\rm P_}1101 \\ {\rm drawing\ number} \end{array}$

Plan

title

checked on site

Rhyl Job For P

School

Primary