

Project Title	38 Heath Drive -	
Location:	2013/7355/P	
Client:		
Correspondence File:		

**ESTIMATED/MEASURED BILL OF QUANTITIES**

ITEM	DESCRIPTION	QUANTITY	UNIT	SELECTED RATE	TOTAL
200.006	Take up or down and remove to tip off site precast concrete or york stone paving slabs any size or type including steel reinforced between 66 and 80mm thick	176.80	m2		
200.012	Take up or down and remove to tip off site granite sett paving any size up to 200mm thick	8.00	m2		
200.019	Take up or down and set aside for reuse granite flat, edge or standard profile bus boarder kerb	52.00	m		
200.021	Take up or down and remove to tip off site granite flat, edge or standard profile bus boarder kerb	10.00	m		
600.001	Excavation of any material in footways, verges and other pedestrian areas	35.36	m3		
600.007	Extra over excavation for excavation in hard material in footways, verges and other pedestrian areas	17.68	m3		
600.020	Completion of formation on material other than Class 1C, 6B or rock in cuttings	176.80	m2		
1100.001	Granite flat kerb 300x200mm, 'fine picked' finish, laid straight or curved exceeding 12 metres radius	10.00	m		
1100.031	Remove from set aside area and relay flat granite kerb, laid straight or curved exceeding 12 metres radius	42.00	m		
1100.059	75mm thick steel reinforced Artificial Stone Paving, any size A or B on existing base or base measured separately and sand bedding 30mm thick	176.80	m2		
1100.079	Extra and any item of paving sand bedding 30mm thick for sand cement mortar	176.80	m2		
1100.080	100mm ST1 concrete base in footways	176.80	m2		
1100.084	100mm Type 1 unbound material in footway base	176.80	m2		
				<b>Sub Total</b>	
<b>Contractor Adjustment</b>			%	£0.00	
<b>Fees</b>			%	£0.00	
<b>Contingencies</b>			%	£0.00	

**GRAND TOTAL      £18,617.98**

Produced By:	Yuksel Arikan	Date:26.06.14	
Checked by:		Date	
Approved by:		Date	
Revision:		Date	