

K:\0000 Boots\PI5-144 Boots Kings Cross (1126)\Boots DWG Structure\WORK-IN-PROGRESS\100-119 GA\autocad\1126100C - Rev Application.dwg

Red line Indicates walls to be demolished

Please refer to drawing E1638-R1 for details of proposed chillers.

NOTES
Do not scale this drawing

K-C 14-2: Introduce new fin/gate to protect Pharmacy meds backwall.
Details: Proposed fin wall to be same height as it is now and 500mm deep.
Remove existing LFGT poster by the counter wall and provide new.

KC 1-2: Refit No.7 within new footprint.

GENERAL NOTES:
Spot cleaning where wall to where any gondolas removed.
Note: Exit 1No. Rapid cash-taking.
Note: Exit 1No. DDA photo kiosk.
*(6No. recall noticeboards - NEW)



Replace existing acrylic panel backing single-sided gondola (located 500mm from glazing face) with new dark blue vinyl panel P280C. Welcome and lettering in white. Arrow in pale blue. To be applied to the back of the gondolas. Refer to elevation drawing 1126120B.

Existing gondola end to be over clad in dark blue vinyl (RAL P280C) non-illuminated aluminum pedestals. Welcome information and green cross to be replaced with new - like for like but to include "order and collect" lettering. So that it reads: order & collect, healthcare, food & drink, baby & child, photo. Please refer to the proposed shopfront document

Existing dark blue (P280C) non-illuminated aluminum pedestals. Welcome information and green cross to be replaced with new - like for like but to include "order and collect" lettering. So that it reads: order & collect, healthcare, food & drink, baby & child, photo. Please refer to the proposed shopfront document

KC 5-2: Relocate 3No. Existing cash-taking. Patch floor where tills are moved forward.

Door A - Remove handles on these double doors. Place them in remote stock room. Cover any holes.

K-C 14-1: Extend existing furniture with new as shown. Refer to brief re note on gondolas. Gondolas marked on drawing 1-6.

Door B: Door to office - Redecorate. Fix door closer. Remove piece of paper from glass. Fit a blind.

Wall D: Behind chillers - Tape and joint as required. Make good service penetrations.

K-C 7-9: Introduce consultation booth/room. See brief and drawing 102 for detailed notes. Provide ventilation to consultation room only.

New ceiling to corridor and consultation room including new sprinklers. Refer to drawing 1126150A and subcontractor's drawings.
Column A: Decorate.
Spot clean where wall to Back of House removed.

Wall B: Clean, laminate, provide cladding to posters, new plinths.

Clean out window beds. Improve lighting in window bed to fully illuminate posters. Use suspended LEDs. Allow to change tubes in bottom lights. Replace existing posters with 2No new. Ensure 2No. poster holders are the same size to accommodate the larger sales plan posters. Please take dimensions prior to ordering the poster.

Wall A: by redundant entrance door - Provide powder coated white angle.

Column B: Decorate.

Wall C: Cash-taking wall - Retain wall, but make good.

Column C: Clean.

24.11.15	REVISED_ADVERTISEMENT+CONROOM
REV_C	
7.10.15	NOTE_RE_REMOTE_CHILLERS
REV_B	
29.09.15	CLEARER_PLAN
REV_A	
03.09.15	First issue.
Rev --	



NOTTINGHAM NG90 1BS Tel No 0115 9506111

Contractors Name cgl	Contractors Details Studio1 155 Commercial Street Spitalfields London E1 6BJ
	T: +44 (0) 20 7539 1200 E: +44 (0) 20 7539 1201 www.cgj.uk.com www.cgj.uk.com
Contractor's Ref P15-144/100	

Project Name Kings Cross
Drawing Title Proposed Floor + signage plan
Dept Retail
Drawn By LC
Scale 1:50
Approved Approved
Date 14: 04: 15

Drq No 1126/C233427/100	Rev C
-----------------------------------	-----------------

1 Proposed Plan
Scale 1:50 @ A1

