



LIGHTING LEGEND

- RED PENDANT-L01A**
 MFR: NUVO LIGHTING
 MODEL#: 60-1296 STD RED FINISH GU24
 LAMP: (1)13 W GU24 BASE CFL
 LAMPS: (13 W)
 FINISH: RED (INSIDE & OUT)
 NOTE: DO NOT PAINT WIRING
- WHITE PENDANT-L01B**
 MANUF: NUVO LIGHTING
 MODEL#: 60-1297 STD WHITE FINISH GU24
 LAMP: (1)13 W GU24 BASE CFL
 LAMPS: (13 W)
 FINISH: WHITE (INSIDE & OUT)
 NOTE: DO NOT PAINT WIRING
- 600 x 1200 RECESSED LED LIGHTING**
- 600 x 600 RECESSED LED LIGHTING**
- TRACK LIGHT**
 MODEL#: TBC
 LAMP: TBC
 LAMPS: TBC
 LAMPT: TO MATCH CEILING FINISH
 LAMPU: DO NOT PAINT WIRING

NEW LIGHT FITTINGS TO BE ENERGY EFFICIENT IN ACCORDANCE WITH ADL28.

CEILING FINISH LEGEND

- C1**
 MF PLASTERBOARD
 JOINTS TO BE TAPED AND JOINED TO RECEIVE PAINT FINISH
 CEILING FINISH
 PT01 BLACK PAINT FINISH
 PT02 WHITE PAINT FINISH
- C2**
 LAY-IN GRID CEILING TILE WITH A WIPE CLEAN VINYL SURFACE, INCORPORATING AN INTEGRATED BIOCIDES, PREVENTS BACTERIAL GROWTH, INCLUDING MRSA, ECOLI 0157 AND SALMONELLA.
 SIZE 600x600 - FRONT OF HOUSE
 SIZE: 600x1200 - KITCHEN / BACK OF HOUSE
- BRITISH GYPSUM**
 HEAD OFFICE
 EAST LEAKE
 LOUGHBOROUGH
 LEICESTERSHIRE
 LE12 6HX
 TEL: 0115 945 1000

NOTES

1. PENDANT FIXTURES IN DINING AREA SHALL BE 2590mm AFFL.
2. PENDANT FIXTURES UNDER SERVICE SOFFIT SHALL HAVE 150mm CORD
3. PENDANT FIXTURES OVER POS, SERVICE COUNTER, AND BEVERAGE STATION REQUIRE TUFF COAT
4. PIR SENSORS TO BE FITTED TO ALL LOW OCCUPATION AREAS.
5. HIGH LEVEL SERVICES WITHIN VOID TO RUN WITHIN CABLING TRAYS AND BE TO LSF.
6. SPRINKLER SYSTEM TO BE INSTALLED BY LPBC CERTIFIED CONTRACTOR.

FLOOR PLAN GENERAL NOTES

- EGRESS DOORS SHALL BE READILY OPENABLE FROM THE EGRESS SIDE WITHOUT THE USE OF A KEY OR SPECIAL KNOWLEDGE OR EFFORT.
1. ALL FIRE RATED DOORS TO BE SELF-CLOSING.
 2. ALL INTERIOR FINISHES TO BE MINIMUM CLASS 0 FLAME SPREAD RATING.
 3. SEE REFLECTED CEILING PLAN FOR LIGHTING AND DUCTWORK LAYOUT.
 4. DO NOT FASTEN STUDS OR PLASTERBOARD TO TOP RUNNER OF NON-BEARING PLASTERBOARD PARTITIONS. CUT STUDS AND PLASTERBOARD 10mm MAX. SHORT TO ALLOW FOR VERTICAL SLAB DEFLECTION.
 5. ALL DIMENSIONS TO BE FINISHED SURFACE UNLESS OTHERWISE NOTED.
 6. CONTRACTOR TO COORDINATE ALL CEILING HEIGHTS WITH BUILDING SYSTEMS. OWNER TO APPROVE ALL CEILING HEIGHTS BEFORE INSTALLATION.

NOTE:
 ALL CEILING HEIGHTS TO BE CONFIRMED WITH BLACKSHEEP BEFORE INSTALLATION.

01 FLOOR PLAN
 SCALE 1:50 @ A1

NOTES:
 DO NOT SCALE FROM THIS DRAWING ALL DRAWINGS TO BE CHECKED ON SITE COPYRIGHT PROTECTED

- THIS DRAWING IS TO BE READ IN CONJUNCTION WITH SPECIFICATIONS SCHEDULES & DRAWINGS BY BLACKSHEEP.
 - ALL DIMENSIONS TO BE CHECKED ON SITE PRIOR TO MANUFACTURE. ROD DRAWINGS TO BE ISSUED FOR BLACKSHEEP COMMENT.
 - SAMPLE OF ALL FINISHES TO BE SUBMITTED TO BLACKSHEEP FOR APPROVAL.
 - ALL DISCREPANCIES AND OMISSIONS ON SITE MUST BE REPORTED TO DESIGNER FOR THEIR COMMENTS OR APPROVAL PRIOR TO COMMENCING WORK.
 - ALL ELECTRICAL, LIGHTING, HVAC AND PLUMBING ISSUES TO BE REFERRED TO ENGINEERS DRAWINGS PRIOR TO COMMENCEMENT OF WORKS.
 - THE DESIGNS ARE SUBJECT TO APPROVAL BY STATUTORY AUTHORITIES AND ANY NECESSARY ALTERNATIONS SHOULD BE MADE IF REQUIRED TO COMPLY WITH STATUTORY REQUIREMENTS.

CONSTRUCTION

Revisions	Comment	Date	Drawn	Checked	Location Plan (NTS)
			CN	BT	

Blacksheep.

13-19 Vibe Hill
 London EC1R 6DW
 +44 (0) 20 7718 7418
 contact@blacksheep.co.uk
 blacksheep.co.uk

Client: **FIVE GUYS**
 Project: **KINGS CROSS**
 THE LIGHTHOUSE BLOCK
 LONDON WC2K

Drawing: **REFLECTED CEILING PLAN**

Drawing No.	Date	Scale	Revision	Drawn By	Checked By
FIV091-A250	13/10/15	1:50 @ A1		CN	BT